

PUCO Case No. 23-0961-EL-BNR

Submitted to:

The Ohio Power Siting Board Pursuant to Ohio Administrative Code Section 4906-6-05

Submitted by: Ohio Power Company

Construction Notice

Ohio Power Company

Conesville-Corridor 345 kV Cut-in and Innovation-Mordor 138 kV Tie Lines #1 & #2 Project

4906-6-05

Ohio Power Company (the "Company") provides the following information to the Ohio Power Siting Board ("OPSB") pursuant to Ohio Administrative Code Section 4906-6-05.

4906-6-5(B) General Information

B(1) Project Description

The name of the project and applicant's reference number, names and reference number(s) of resulting circuits, a brief description of the project, and why the project meets the requirements for a Construction Notice.

The Company proposes to construct the Conesville-Corridor 345 kV Cut-in and Innovation Mordor 138 kV Tie Lines #1 & #2 Project (the "Project") in the City of New Albany, Licking County, Ohio. A customer has requested additional service southeast of the intersection of Jug Street and Harrison Road, adjacent to the AEP Ohio Transmission Company Inc's, Innovation Station (approved in Case No. 21-1083-EL-BLN). The Project involves cutting into the Conesville – Corridor 345 kV Transmission Line (approved in Case No. 22-0058-EL-BLN) to provide 345 kV service to the Innovation Station. Additionally, the Project will require two, 0.1-mile greenfield single circuit tie lines (Innovation – Mordor 138 kV Tie Line #1 and #2) from the Company's Innovation Station to a customer's step-down station (Mordor Station). No new structures are proposed for the Project, only new spans of conductor are required, and the Project is located entirely on Company or customer property. The location of the Project and the associated previously approved projects are shown on Figure 2 in Appendix A

The Project meets the requirements for a CN because it is within the types of projects defined by item (1)(d)(i) of Ohio Administrative Code Section 4906-1-01 Appendix A of the Application Requirement Matrix For Electric Power Transmission Lines:

(1) New construction extension, or relocation of single or multiple circuit electric power transmission line(s), or upgrading existing transmission or distribution line(s) for operation at a higher transmission voltage, as follows:

1

- (d) Line(s) primarily need to attract or meet the requirements of a specific customer or customers, as follows:
 - i. The line is completely on property owned by the specific customer or the applicant.

The Project has been assigned PUCO Case No. 23-0961-EL-BNR.

B(2) Statement of Need

If the proposed project is an electric power transmission line or gas or natural gas transmission line, a statement explaining the need for the proposed facility.

The Project is needed to address an additional 138 kV service requested by an existing customer in New Albany, Licking County, Ohio. To meet the customer's needs of 247 MW of peak load, additional 138 kV service is needed at the customer's stepdown station (Mordor). Due to the customer request and the overall load growth in the area, the Company must add capacity to Innovation Station and upgrade it to a 345 kV Station. Upgrading the Innovation Station requires the construction of the Conesville – Corridor 345 kV Cut-In and the installation of a 345 kV to 138 kV transformation. The Innovation Station fence will not expand to accommodate the 345 kV to 138 kV transformer. The customer has requested an in-service date of April 30, 2024.

Failure to move forward with the proposed Project will result in the inability to serve the customer's load expectations and thereby jeopardize the customer's plans in the New Albany area. Furthermore, failure to upgrade Innovation Station service to 345 kV will affect additional customers in the area and render facilities insufficient to serve the approximately 2,400 MW of peak load in the New Albany area.

The need was presented and reviewed with stakeholders at the April 22, 2022, PJM SSRTEP Western Meeting. The solution was reviewed with stakeholders at the May 9, 2023, PJM TEAC Meeting, see Appendix B. The Project has not yet been assigned a PJM identifier to date, but one is anticipated by the end of 2023. The Project was inadvertently not included in the Company's 2023 Long Term Forecast Report ("LTFR") but will be included in the Company's 2024 LTFR.

B(3) Project Location

The applicant shall provide the location of the project in relation to existing or proposed lines and substations shown on an area system map of sufficient scale and size to show existing and proposed transmission facilities in the Project Area.

The location of the Project in relation to existing transmission line and proposed relocation is shown in Figure 1 of Appendix A.

B(4) Alternatives Considered

The applicant shall describe the alternatives considered and reasons why the proposed location or route is best suited for the proposed facility. The discussion shall include, but not be limited to, impacts associated with socioeconomic, ecological, construction, or engineering aspects of the project.

The Project is located on Company and customer property. Based on the customer's proposed development and existing facilities in the area, the proposed transmission line alignments are the most suitable location for the Project. Other alternatives would require impacting neighboring properties as opposed to remaining on the customer's property or within existing right-of-way and would add additional transmission length

for the interconnections without any additional benefit. The proposed Project will result in no impacts to wetlands, streams, or known cultural resource areas eligible for the National Register of Historic Places (NRHP). Therefore, this alternative represents the most suitable location and is the most appropriate solution for meeting the Company and specific customer's needs in the area.

B(5) Public Information Program

The applicant shall describe its public information program to inform affected property owners and tenants of the nature of the project and the proposed timeframe for project construction and restoration activities.

The Company maintains a website (http://aeptransmission.com/ohio/) on which an electronic copy of this CN is available. An electronic copy of the CN will be served to the public library in each political subdivision affected by this Project. The Company also retains land agents who will discuss Project timelines, construction and restoration activities with affected owners and tenants.

B(6) Construction Schedule

The applicant shall provide an anticipated construction schedule and proposed in-service date of the project.

Construction of the Project is planned to begin in February 2024, and the anticipated in-service date will be April 2024.

B(7) Area Map

The applicant shall provide a map of at least 1:24,000 scale clearly depicting the facility with clearly marked streets, roads, and highways, and an aerial image.

Figure 1 in Appendix A provides the proposed Project area on a map of 1:24,000-scale (1 inch equals 1,000 feet), showing the Project on the United States Geological Survey (USGS) 7.5-minute topographic map of the Jersey, Ohio quadrangle. Figure 2 in Appendix A shows the Project Area on recent aerial photography, dated 2023, as provided by Licking County at a scale of 1:6,000 scale (1 inch equals 500 feet).

To visit the Project site from Columbus, Ohio, take I-670 East to I-270 North. Take exit 33 towards Easton Way, then take exit 30 and merge onto OH-161 East for approximately 12.5 miles. Take exit 51 for County Highway 41/Mink Street. Turn left onto Mink Street and follow the road for 1.2 miles. Then turn left onto Jug Street and follow the road for 0.7 mile. The Project site will be on the left. The approximate address of the Project site is 12525 Jug Street Road NW, at latitude 40.09489°, longitude -82.72631°.

B(8) Property Agreements

The applicant shall provide a list of properties for which the applicant has obtained easements, options, and/or land use agreements necessary to construct and operate the facility and a list of the additional properties for which such agreements have not been obtained.

The Project is located on two parcels. Parcel 095-112074-00.010 is owned by AEP Ohio Transmission Company, Inc. Parcel 095-112074-00.000 is owned by the customer. New right-of-way has been acquired from the customer for the short portions of the transmission lines that extend beyond the Company's property. No other property easements, options, or land use agreements are necessary to construct the Project.

A list of properties required for the Project is provided in the table below.

Property Parcel Number	Agreement Type	Easement/ Option Obtained (Yes/No)
095-112074-00.010	Company Owned	Not Applicable
095-112074-00.000	New and Supplemental ROW	Yes

B(9) Technical Features

The applicant shall describe the following information regarding the technical features of the project:

B(9)(a) Operating characteristics, estimated number and types of structures required, and right-of-way and/or land requirements.

Line Asset Name: Conesville-Corridor Ownership: Ohio Power Company

Voltage: 345 kV

Conductors: (3) ACSR Bittern 1272 (45/7) Static Wire: (1) Guinea 159 ACSR (12/7)

Insulators: Polymer ROW Width: 150 feet

Structure Type: Not Applicable

Line Asset Name: Innovation-Mordor #1
Ownership: Ohio Power Company

Voltage: 138 kV

Conductors: (3) ACSR Dove 556.5 (26/7)

Static Wire: (1) 7#8 Alumoweld

Insulators: Polymer
ROW Width: 100 feet

Structure Type: Not Applicable

Line Asset Name: Innovation-Mordor #2
Ownership: Ohio Power Company

Voltage: 138 kV

Conductors: (3) ACSR Dove 556.5 (26/7)

Static Wire: (2) 7#8 Alumoweld

Insulators: Polymer
ROW Width: 100 feet
Structure Type: Not Applica

Structure Type: Not Applicable

B(9)(b) Electric and Magnetic Fields

For electric power transmission lines that are within one hundred feet of an occupied residence or institution, the production of electric and magnetic fields during the operation of the proposed electric power transmission line.

No occupied residences or institutions are located within 100 feet of the Project.

B(9)(c) Project Cost

The estimated capital cost of the project.

The capital cost estimate for the proposed Project, which is comprised of applicable tangible and capital costs, is approximately \$300,000 based on a Class 4 estimate. Forty percent (40%) of the costs for the construction of Innovation-Mordor #1 and #2 tie lines will be recovered through reimbursement from the customer. Pursuant to the PJM Open Access Transmission Tariff ("OATT"), the remainder of the costs for this Project will be recovered in the Company's Federal Energy Regulatory Commission ("FERC") formula rate (Attachment H-14 to the PJM OATT) and allocated to the AEP Zone.

B(10) Social and Economic Impacts

The applicant shall describe the social and ecological impacts of the project:

B(10)(a) Land Use Characteristics

Provide a brief, general description of land use within the vicinity of the proposed project, including a list of municipalities, townships, and counties affected.

Aerial photography of the Project vicinity is provided as Figure 2 in Appendix A. The Project is located in the City of New Albany, Licking County, Ohio. The Project location and vicinity have historically been primarily agricultural land and scrub-shrub vegetation cover with scattered woodlots throughout the Project area. Recently, the vicinity, including the Project area, has undergone land use change to light commercial and industrial use.

B(10)(b) Agricultural Land Information

Provide the acreage and a general description of all agricultural land, and separately all agricultural district land, existing at least sixty days prior to submission of the application within the potential disturbance area of the project.

No agricultural land is located within the Project footprint or adjacent properties. On September 12, 2023, the Licking County Auditor indicated that the properties crossed by the Project are not identified as Agricultural District Land parcels.

B(10)(c) Archaeological and Cultural Resources

Provide a description of the applicant's investigation concerning the presence or absence of significant archaeological or cultural resources that may be located within the potential disturbance area of the project, a statement of the findings of the investigation, and a copy of any document produced as a result of the investigation.

The Company's consultant completed a Cultural Resource Management Investigation of the 42.5-acre customer property, which included the current Company property and Project area in June 2021. One new archaeological site and two architectural resources greater than 50 years of age were identified. The Company's consultant recommended that these resources are not eligible for inclusion in the NRHP. No additional investigation was recommended. The Ohio Historic Preservation Office ("SHPO") concurred that no additional survey or coordination is necessary, and the Project as proposed will have no effect on historic properties. The coordination response from SHPO is provided in Appendix C.

B(10)(d) Local, State, and Federal Agency Correspondence

Provide a list of the local, state, and federal governmental agencies known to have requirements that must be met in connection with the construction of the project, and a list of documents that have been or are being filed with those agencies in connection with siting and constructing the project.

A Notice of Intent will be filed with the Ohio Environmental Protection Agency for authorization of construction storm water discharges under General Permit OHCD000006, if ground disturbance exceeds one acre. The Company will implement and maintain best management practices to minimize erosion control sediment to protect surface water quality during storm events. The Company will also coordinate storm water permitting needs with local government agencies, as necessary.

The Company's consultant conducted a stream and wetland delineation within the Project study area that extended across the customer's and Company's properties. Two wetlands and no streams were identified within the Project study area. The wetlands are not located in the disturbance areas associated with the Project. No wetlands or streams will be disturbed by the Project.

The FEMA Flood Insurance Rate Map was reviewed to identify any floodplains/flood hazard areas that have been mapped within the Project Area (specifically, map number **39049Co230K**). Based on this mapping, no mapped FEMA floodplains are located in the Project Area. Therefore, no floodplain permit will be required for this Project.

There are no other known local, state, or federal requirements that must be met prior to commencement of the proposed Project.

B(10)(e) Threatened, Endangered, and Rare Species

Provide a description of the applicant's investigation concerning the presence or absence of federal and state designated species (including endangered species, threatened species, rare species, species proposed for listing, species under review for listing, and species of special interest) that may be located within the potential disturbance area of the project, a statement of the findings of the investigation, and a copy of any document produced as a result of the investigation.

As part of the ecological study completed for the Project, a coordination letter was submitted to the USFWS Ohio Ecological Services Field Office seeking technical assistance on the Project for potential impacts to threatened or endangered species. The October 7, 2021 response letter from the USFWS (see Appendix C) indicated that the Indiana bat and northern long-eared bat occur throughout Ohio. The letter indicated the Company should adhere to seasonal tree clearing requirements or coordinate with the appropriate agencies. No tree clearing is anticipated for the Project. Due to the Project type, size, and location, USFWS does not anticipate adverse effects to any other federally endangered, threatened, proposed, or candidate species.

A coordination letter was submitted to the Ohio Department of Natural Resources ("ODNR") Division of Wildlife ("DOW") Ohio Natural Heritage Program ("ONHP") and the ODNR - Office of Real Estate in seeking an environmental review of the proposed Project for potential impacts on state-listed and federally listed threatened or endangered species. Correspondence from ODNR's DOW/OHNP and the ODNR - Office of Real Estate was received on June 14, 2022 (see Appendix C).

According to the ODNR-DOW, the Project is within the range of the Indiana bat, northern long-eared bat, little brown bat, and tricolored bat. The ODNR recommends cutting between October 1 and March 31, if necessary. No winter hibernacula were observed within the Project Area and no potential hibernaculum were identified within 0.25 mile of the Project Area based on review of karst and mining GIS data as well as topographic quadrangle maps and aerial photography. No tree clearing is anticipated for the Project.

The ODNR-DOW indicated that the Project is within the range of the fawnsfoot, a state listed mussel, and the lake chubsucker, a state listed fish species. Due to no in-water work and no perennial streams in the Project area, these species are not anticipated to be impacted by the Project.

The ODNR-DOW indicated that the Project is within the range of the least bittern, northern harrier, and upland sandpiper, state endangered or threatened birds. Based on the ecological survey, no habitat for these species was identified. No impacts to these species are anticipated.

B(10)(f) Areas of Ecological Concern

Provide a description of the applicant's investigation concerning the presence or absence of areas of ecological concern (including national and state forests and parks, floodplains, wetlands, designated or proposed wilderness areas, national and state wild and scenic rivers, wildlife areas, wildlife refuges, wildlife management areas, and wildlife sanctuaries) that may be located within the potential disturbance area of the project, a statement of the findings of the investigation, and a copy of any document produced as a result of the investigation.

The ODNR-DOW response indicated that unique ecological sites, geologic features, animal assemblages, scenic rivers, state wildlife areas, state nature preserves, state or national parks, state or national forests, or other protected natural areas were not identified within the Project Area (see Appendix C).

FEMA Flood Insurance Rate Maps were consulted to identify any floodplains/flood hazard areas that have been mapped in the Project Area (specifically, map number **39049Co23oK**). Based on these maps, no mapped FEMA floodplains are located in the Project area.


The Company's consultant conducted a stream and wetland delineation within the Project study area that extended across the customer's and company's properties. Two wetlands and no streams were identified within the Project study area. The wetlands are not located in the disturbance areas associated with the Project. No wetlands or streams will be disturbed by the Project (see Figure 3 in Appendix D).


B(10)(g) Unusual Conditions

Provide any known additional information that will describe any unusual conditions resulting in significant environmental, social, health, or safety impacts.

To the best of the Company's knowledge, no unusual conditions exist that would result in significant environmental, social, health, or safety impacts.

Appendix A Project Maps





Appendix B PJM Slides



AEP Transmission Zone M-3 Process Innovation Build Out

Need Number: AEP-2022-OH036

Process Stage: Solutions Meeting 5/9/2023

Previously Presented: Need Meeting 04/22/2022

Project Driver: Customer Service

Specific Assumption Reference:


AEP Connection Requirements for the AEP Transmission System

(AEP Assumptions Slide 12)

Problem Statement:

Customer Service:

- The customer served out of Innovation station (S2578) has requested additional transmission service at their existing site just south of the existing Conesville Corridor 345 kV circuit in New Albany, OH.
- The customer has indicated a peak demand of 286.5 247 MW at the site.
- The customer has requested an ISD of 4/1/2024





AEP Transmission Zone M-3 Process New Albany, OH

Need Number: AEP-2022-OH036

Process Stage: Solutions Meeting 5/9/2023

Proposed Solution:

The following work is all direct connect substations to physically connect demand to the grid.

• Innovation 345/138 kV: Cut into the Corridor - Conesville 345 kV circuit and construct ~0.1 miles of double circuit line, utilizing 2-bundled ACSR Bittern 1272 conductor, SE rating 2278 MVA, to a new 345 kV ring bus at Innovation station (s2578) with (4) 5000 A, 63kA circuit breakers, (2) 345/138/34.5 kV, 675 MVA transformers, (15) 4000 A, 80, kA, 138 kV circuit breakers, (2) 69.1 MVAR, 138 kV Cap banks. Upgrade the line protection relays at Conesville & Corridor 345 kV. Construct (2) 138 kV tie lines to the customers dead end structures ~0.04 miles utilizing ACSR Dove 556.5 (26/7) conductor SE 284 MVA. Cost: \$53.7 M

Appendix C Agency Coordination



In reply, refer to 2021-LIC-51787

July 14, 2021

Mr. Ryan J. Weller Weller & Associates, Inc. 1395 West Fifth Avenue Columbus, Ohio 43212

RE: Innovation Station Project, Jersey Township, Licking County, Ohio

Dear Mr. Weller:

This letter is in response to the correspondence received on June 15, 2021 regarding the proposed Innovation Station Project, Jersey Township, Licking County, Ohio. We appreciate the opportunity to comment on this project. The comments of the Ohio State Historic Preservation Office (SHPO) are made pursuant to Section 149.53 of the Ohio Revised Code and the Ohio Power Siting Board rules for siting this project (OAC 4906-5). The comments of the Ohio SHPO are also submitted in accordance with the provisions of Section 106 of the National Historic Preservation Act of 1966, as amended (54 U.S.C. 306108 [36 CFR 800]).

The following comments pertain to the *Phase I Cultural Resource Management Investigations for the 17.2 ha (42.5 ac) Innovation Station Project in Jersey Township, Licking County, Ohio* by Weller & Associates, Inc. (2021).

A literature review, visual inspection, surface collection, shovel probe and shovel test unit excavation was completed as part of the investigations. No previously identified archaeological sites are located within the project area. One (1) new archaeological site was identified during survey. Ohio Archaeological Inventory (OAI)# 33LI2721 is recommended not eligible for listing in the National Register of Historic Places (NRHP). Our office agrees with this recommendation and no additional archeological investigation is needed.

A literature review and field survey were completed as part of the investigations. Two (2) history/architecture resource fifty years of age or older were identified within the Area of Potential Effects (APE) during the field survey. It is Weller's recommendation that these properties are not eligible for inclusion in the NRHP. Our office agrees with Weller's recommendations of eligibility.

Based on the information provided, we agree that the project as proposed will have no effect on historic properties. No further coordination with this office is necessary, unless the project changes or unless new or additional historic properties are discovered during implementation of this project. In such a situation, this office should be contacted. If you have any questions, please contact me at (614) 298-2022, or by e-mail at khorrocks@ohiohistory.org or Joy Williams at jwilliams@ohiohistory.org. Thank you for your cooperation.

Sincerely,

Krista Horrocks, Project Reviews Manager

Resource Protection and Review

RPR Serial No: 1088972



Ohio Department of Natural Resources

MIKE DEWINE, GOVERNOR

MARY MERTZ, DIRECTOR

Fax: (614) 267-4764

Office of Real Estate John Kessler, Chief 2045 Morse Road – Bldg. E-2 Columbus, OH 43229 Phone: (614) 265-6621

October 21, 2021

Jake Lubbers AECOM 525 Vine Street, Suite 1800 Cincinnati, Ohio 45202

Re: 21-0913; AEP Innovation Station Project

Project: The proposed project involves the construction of the Innovation Substation.

Location: The proposed project is located in Jersey Township, Licking County, Ohio.

The Ohio Department of Natural Resources (ODNR) has completed a review of the above referenced project. These comments were generated by an inter-disciplinary review within the Department. These comments have been prepared under the authority of the Fish and Wildlife Coordination Act (48 Stat. 401, as amended; 16 U.S.C. 661 et seq.), the National Environmental Policy Act, the Coastal Zone Management Act, Ohio Revised Code and other applicable laws and regulations. These comments are also based on ODNR's experience as the state natural resource management agency and do not supersede or replace the regulatory authority of any local, state or federal agency nor relieve the applicant of the obligation to comply with any local, state or federal laws or regulations.

Natural Heritage Database: The Natural Heritage Database has no records at or within a one-mile radius of the project area.

A review of the Ohio Natural Heritage Database indicates there are no other records of state endangered or threatened plants or animals within the project area. There are also no records of state potentially threatened plants, special interest or species of concern animals, or any federally listed species. In addition, we are unaware of any unique ecological sites, geologic features, animal assemblages, scenic rivers, state wildlife areas, state nature preserves, state or national parks, state or national wildlife refuges, or other protected natural areas within the project area. The review was performed on the project area you specified in your request as well as an additional one-mile radius. Records searched date from 1980.

Please note that Ohio has not been completely surveyed and we rely on receiving information from many sources. Therefore, a lack of records for any particular area is not a statement that rare species or unique features are absent from that area. Although all types of plant communities have been surveyed, we only maintain records on the highest quality areas.

Fish and Wildlife: The Division of Wildlife (DOW) has the following comments.

The DOW recommends that impacts to streams, wetlands and other water resources be avoided and minimized to the fullest extent possible, and that Best Management Practices be utilized to minimize erosion and sedimentation.

The project is within the vicinity of records for the northern long-eared bat (*Myotis septentrionalis*), a state endangered and federally threatened species. Because presence of state endangered bat species has been established in the area, summer tree cutting is not recommended, and additional summer surveys would not constitute presence/absence in the area. However, limited summer tree cutting inside this buffer may be acceptable after further consultation with DOW (contact Erin Hazelton at Erin.hazelton@dnr.ohio.gov).

In addition, the entire state of Ohio is within the range of the Indiana bat (*Myotis sodalis*), a state endangered and federally endangered species, the northern long-eared bat (*Myotis septentrionalis*), a state endangered and federally threatened species, the little brown bat (*Myotis lucifugus*), a state endangered species, and the tricolored bat (*Perimyotis subflavus*), a state endangered species. During the spring and summer (April 1 through September 30), these bat species predominately roost in trees behind loose, exfoliating bark, in crevices and cavities, or in the leaves. However, these species are also dependent on the forest structure surrounding roost trees. The DOW recommends tree cutting only occur from October 1 through March 31, conserving trees with loose, shaggy bark and/or crevices, holes, or cavities, as well as trees with DBH ≥ 20 if possible.

The DOW also recommends that a desktop habitat assessment is conducted, followed by a field assessment if needed, to determine if a potential hibernaculum is present within the project area. Direction on how to conduct habitat assessments can be found in the current USFWS "Rangewide Indiana Bat Survey Guidelines." If a habitat assessment finds that a potential hibernaculum is present within 0.25 miles of the project area, please send this information to Erin Hazelton for project recommendations. If a potential or known hibernaculum is found, the DOW recommends a 0.25-mile tree cutting and subsurface disturbance buffer around the hibernaculum entrance, however, limited summer or winter tree cutting may be acceptable after consultation with the DOW. If no tree cutting or subsurface impacts to a hibernaculum are proposed, this project is not likely to impact these species.

The project is within the range of the fawnsfoot (*Truncilla donaciformis*), a state threatened mussel. Due to the location, and that there is no in-water work proposed in a perennial stream of sufficient size, this project is not likely to impact this species.

The project is within the range the lake chubsucker (*Erimyzon sucetta*) a state threatened fish. The DOW recommends no in-water work in perennial streams from March 15 through June 30 to reduce impacts to indigenous aquatic species and their habitat. If no in-water work is proposed in a perennial stream, this project is not likely to impact this or other aquatic species.

The project is within the range of the least bittern (*Ixobrychus exilis*), a state threatened bird. This secretive marsh species prefers dense emergent wetlands with dense, tall growths of aquatic or semiaquatic vegetation (particularly cattail, sedge, rushes, arrowheads, or sawgrass) interspersed with clumps of woody vegetation and open water. Nests are made from dried vegetation suspended .5 to 2.5 feet above the water. If this type of habitat will be impacted, construction should be avoided in this habitat during the species' nesting period of May 1 through July 31. If this type of habitat will not be impacted, this project is not likely to impact this species.

The project is within the range of the northern harrier (*Circus hudsonis*), a state endangered bird. This is a common migrant and winter species. Nesters are much rarer, although they occasionally breed in large marshes and grasslands. Harriers often nest in loose colonies. The female builds a nest out of sticks on the ground, often on top of a mound. Harriers hunt over grasslands. If this type of habitat will be impacted, construction should be avoided in this habitat during the species' nesting period of April 15 through July 31. If this habitat will not be impacted, this project is not likely to impact this species.

The project is within the range of the upland sandpiper (*Bartramia longicauda*), a state endangered bird. Nesting upland sandpipers utilize dry grasslands including native grasslands, seeded grasslands, grazed and ungrazed pasture, hayfields, and grasslands established through the Conservation Reserve Program (CRP). If this type of habitat will be impacted, construction should be avoided in this habitat during the species' nesting period of April 15 through July 31. If this type of habitat will not be impacted, this project is not likely to impact this species.

Due to the potential of impacts to federally listed species, as well as to state listed species, we recommend that this project be coordinated with the US Fish & Wildlife Service.

Water Resources: The Division of Water Resources has the following comment.

The local floodplain administrator should be contacted concerning the possible need for any floodplain permits or approvals for this project. Your local floodplain administrator contact information can be found at the website below.

http://water.ohiodnr.gov/portals/soilwater/pdf/floodplain/Floodplain%20Manager%20Community%20Contact%20List 8 16.pdf

ODNR appreciates the opportunity to provide these comments. Please contact Mike Pettegrew at mike.pettegrew@dnr.ohio.gov if you have questions about these comments or need additional information.

Mike Pettegrew Environmental Services Administrator (Acting)

Brewster, Heather

From: Ohio, FW3 <ohio@fws.gov>

Sent: Thursday, October 07, 2021 3:27 PM

To: Lubbers, Jake

Cc: nathan.reardon@dnr.state.oh.us; Parsons, Kate; ajtoohey@aep.com; Brewster, Heather

Subject: [EXTERNAL] AEP Innovation Station Project in Licking County, Ohio



UNITED STATES DEPARTMENT OF THE INTERIOR
U.S. Fish and Wildlife Service
Ecological Services Office
4625 Morse Road, Suite 104
Columbus, Ohio 43230
(614) 416-8993 / Fax (614) 416-8994



TAILS# 03E15000-2019-TA-1865

Dear Mr. Lubbers,

The U.S Fish and Wildlife Service (Service) has received your recent correspondence requesting information about the subject proposal. We offer the following comments and recommendations to assist you in minimizing and avoiding adverse impacts to threatened and endangered species pursuant to the Endangered Species Act of 1973 (16 U.S.C. 1531 et seq), as amended (ESA).

Federally Threatened and Endangered Species: The endangered Indiana bat (*Myotis sodalis*) and threatened northern long-eared bat (*Myotis septentrionalis*) occur throughout the State of Ohio. The Indiana bat and northern long-eared bat may be found wherever suitable habitat occurs unless a presence/absence survey has been performed to document absence. Suitable summer habitat for Indiana bats and northern long-eared bats consists of a wide variety of forested/wooded habitats where they roost, forage, and breed that may also include adjacent and interspersed nonforested habitats such as emergent wetlands and adjacent edges of agricultural fields, woodlots, fallow fields, and pastures. Roost trees for both species include live and standing dead trees ≥3 inches diameter at breast height (dbh) that have any exfoliating bark, cracks, crevices, hollows and/or cavities. These roost trees may be located in forested habitats as well as linear features such as fencerows, riparian forests, and other wooded corridors. Individual trees may be considered suitable habitat when they exhibit the characteristics of a potential roost tree and are located within 1,000 feet of other forested/wooded habitat. Northern long-eared bats have also been observed roosting in human-made structures, such as buildings, barns, bridges, and bat houses; therefore, these structures should also be considered potential summer habitat. In the winter, Indiana bats and northern long-eared bats hibernate in caves, rock crevices and abandoned mines.

Seasonal Tree Clearing for Federally Listed Bat Species: Should the proposed project site contain trees ≥3 inches dbh, we recommend avoiding tree removal wherever possible. If any caves or abandoned mines may be disturbed, further coordination with this office is requested to determine if fall

or spring portal surveys are warranted. If no caves or abandoned mines are present and trees ≥3 inches dbh cannot be avoided, we recommend removal of any trees ≥3 inches dbh only occur between October 1 and March 31. Seasonal clearing is recommended to avoid adverse effects to Indiana bats and northern long-eared bats. While incidental take of northern long-eared bats from most tree clearing is exempted by a 4(d) rule (see http://www.fws.gov/midwest/endangered/mammals/nleb/index.html), incidental take of Indiana bats is still prohibited without a project-specific exemption. Thus, seasonal clearing is recommended where Indiana bats are assumed present.

If implementation of this seasonal tree cutting recommendation is not possible, a summer presence/absence survey may be conducted for Indiana bats. If Indiana bats are not detected during the survey, then tree clearing may occur at any time of the year. Surveys must be conducted by an approved surveyor and be designed and conducted in coordination with the Ohio Field Office. Surveyors must have a valid federal permit. Please note that in Ohio summer mist net surveys may only be conducted between June 1 and August 15.

Section 7 Coordination: If there is a federal nexus for the project (e.g., federal funding provided, federal permits required to construct), then no tree clearing should occur on any portion of the project area until consultation under section 7 of the ESA, between the Service and the federal action agency, is completed. We recommend the federal action agency submit a determination of effects to this office, relative to the Indiana bat and northern long-eared bat, for our review and concurrence. This letter provides technical assistance only and does not serve as a completed section 7 consultation document.

Stream and Wetland Avoidance: Over 90% of the wetlands in Ohio have been drained, filled, or modified by human activities, thus is it important to conserve the functions and values of the remaining wetlands in Ohio (https://epa.ohio.gov/portals/47/facts/ohio wetlands.pdf). We recommend avoiding and minimizing project impacts to all wetland habitats (e.g., forests, streams, vernal pools) to the maximum extent possible in order to benefit water quality and fish and wildlife habitat. Additionally, natural buffers around streams and wetlands should be preserved to enhance beneficial functions. If streams or wetlands will be impacted, the U.S. Army Corps of Engineers should be contacted to determine whether a Clean Water Act section 404 permit is required. Best management practices should be used to minimize erosion, especially on slopes. Disturbed areas should be mulched and revegetated with native plant species. In addition, prevention of non-native, invasive plant establishment is critical in maintaining high quality habitats.

Due to the project type, size, and location, we do not anticipate adverse effects to any other federally endangered, threatened, or proposed species, or proposed or designated critical habitat. Should the project design change, or additional information on listed or proposed species or their critical habitat become available, or if new information reveals effects of the action that were not previously considered, coordination with the Service should be initiated to assess any potential impacts.

Thank you for your efforts to conserve listed species and sensitive habitats in Ohio. We recommend coordinating with the Ohio Department of Natural Resources due to the potential for the proposed project to affect state listed species and/or state lands. Contact Mike Pettegrew, Acting Environmental Services Administrator, at (614) 265-6387 or at mike.pettegrew@dnr.state.oh.us.

If you have questions, or if we can be of further assistance in this matter, please contact our office at (614) 416-8993 or ohio@fws.gov.

Sincerely,



Patrice M. Ashfield Field Office Supervisor

cc: Nathan Reardon, ODNR-DOW Kate Parsons, ODNR-DOW

Appendix D Ecological Survey Report



INNOVATION 138KV STATION PROJECT LICKING COUNTY, OHIO

WETLAND DELINEATION AND STREAM ASSESSMENT REPORT

Prepared for:

American Electric Power Ohio Transmission Company 8600 Smiths Mill Road New Albany, Ohio 43054



Prepared by:



525 Vine Street, Suite 1800 Cincinnati, Ohio 45202

Project #: 60660544

October 2021



TABLE OF CONTENTS

1.0	METH	HODOLOGY	1
	1.1	WETLAND DELINEATION	1
		1.1.1 SOILS	2
		1.1.2 HYDROLOGY	2
		1.1.3 VEGETATION	3
		1.1.4 WETLAND CLASSIFICATIONS	3
		1.1.5 OHIO RAPID ASSESSMENT METHOD v. 5.0	
	1.2	STREAM ASSESSMENT	5
		1.2.1 OEPA QUALITATIVE HABITAT EVALUATION INDEX	5
		1.2.2 OEPA PRIMARY HEADWATER HABITAT EVALUATION INDEX	6
		1.2.3 OEPA 401 WATER QUALITY CERTIFICATION FOR NATIONWIDE	
		PERMIT ELIGIBILITY	7
	1.3	UPLAND DRAINAGE FEATURE	8
	1.4	RARE, THREATENED, AND ENDANGERED SPECIES	
2.0	RESI	JLTS	9
	2.1	WETLAND DELINEATION	9
		2.1.1 PRELIMINARY SOILS EVALUATION	
		2.1.2 NATIONAL WETLAND INVENTORY MAP REVIEW	
		2.1.3 DELINEATED WETLANDS	
		2.1.4 DELINEATED WETLANDS ASSESSMENT	
	2.2	STREAM DELINEATION	
		2.2.1 OEPA STREAM ELIGIBILITY	11
	2.3	PONDS	
	2.4	VEGETATIVE COMMUNITIES WITHIN THE PROJECT SURVEY AREA	11
	2.5	RARE, THREATENED AND ENDANGERED SPECIES AGENCY	
		COORDINATION	12
3.0	SUMI	MARY	20
<i>4</i> ∩	REFE	FRENCES	21

TABLES (in-text)

TABLE 1: SOIL MAP UNITS AND DESCRIPTIONS WITHIN THE INNOVATION SUBSTATION 138KV PROJECT SURVEY AREA	
TABLE 2: SUMMARY OF WATERSHED 401 WQC ELIGIBILITY WITHIN THE INNOVATION SUBSTATION 138K' PROJECT SURVEY AREA	V
TABLE 3: VEGETATIVE COMMUNITIES WITHIN THE INNOVATION SUBSTATION 138KV PROJECT SURVEY AREA	
TABLE 4: ODNR AND USFWS LISTED SPECIES WITHIN THE INNOVATION SUBSTATION 138KV PROJECT SURVEY AREA.	

FIGURES

Number

FIGURE 1	Overview Map
FIGURE 2	Soil Map Unit and National Wetland Inventory Maps
FIGURE 3	Wetland Delineation and Stream Assessment Maps
FIGURE 4	Stream Eligibility Map
FIGURE 5	Vegetation Communities Maps

APPENDICES

Number APPENDIX A	Project Wetland Table
APPENDIX B	U.S Army Corps of Engineers Wetland Data Forms / OEPA Wetland ORAM Forms / Delineated Features Photographs (combined per wetland and shown in numerical order)
APPENDIX C APPENDIX D	Habitat and Other Identified Features Photographs Agency Correspondence



INTRODUCTION

American Electric Power Ohio Transmission Company (AEP Ohio Transco) proposes to construct a new substation to be called Innovation Station in Licking County, Ohio. The Innovation Substation 138kV Project (Project) will be constructed within an approximately 42.5-acre section of property (Project survey area) located south of Jug Street Rd. NW in Jersey Township, Licking County, Ohio. The proposed Project location is illustrated on Figure 1.

On June 3, 2021, AECOM conducted a field survey to assess the presence of wetlands and other "waters of the United States (WOTUS)" within the Project survey area. Secondarily, land uses were recorded to classify and characterize potential habitat for rare, threatened, and endangered species. This report will be used to assist AEP Ohio Transco's efforts to identify potential WOTUS and rare, threatened and endangered species habitat present within the Project survey area to avoid and/or minimize impacts to those resources during construction activities.

1.0 METHODOLOGY

Prior to conducting field surveys, digital U.S. Department of Agriculture (USDA) Natural Resources Conservation Service (NRCS) soil survey data, U.S. Fish and Wildlife Service (USFWS) National Wetland Inventory (NWI) maps, and U.S. Geological Survey (USGS) National Hydrography Dataset (NHD), and USGS 7.5-minute topographic maps were reviewed as an exercise to identify the occurrence and location of potential wetland areas.

Field survey activities included recording the physical boundaries of observed water features using submeter capable EOS Arrow Global Positioning System (GPS) units in conjunction with ArcCollector application on iPad tablets. The GPS data was imported into ArcMap Geographic Information System (GIS) software, where the data was reviewed, edited for accuracy, and compiled in a format suitable for transfer and use by AEP Ohio Transco. Water features were delineated and assessed based upon the appropriate procedures detailed below. Land uses observed within the Project survey area were assigned a general classification based upon the principal land characteristics and vegetation cover of the location.

1.1 WETLAND DELINEATION

The Project survey area was evaluated according to the procedures outlined in the U.S. Army Corps of Engineers (USACE) 1987 Wetland Delineation Manual (1987 Manual) (USACE, 1987) and the Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Midwest Region (Version 2.0) (Midwest Regional Supplement) (USACE, 2010). The 1987 Manual and Regional Supplement define wetlands as areas that have positive evidence of three environmental parameters: hydric soils, wetland hydrology, and hydrophytic vegetation. Wetland boundaries are placed where one or more of these parameters give way



to upland characteristics. The *Midwest Regional Supplement* was developed to address regional wetland characteristics and improve the accuracy and efficiency of wetland delineation procedures.

During field survey activities AECOM utilized the routine on-site delineation method described in the 1987 Manual and Midwest Regional Supplement that consisted of a pedestrian site reconnaissance, including identifying the vegetation communities, soils identification, a geomorphologic assessment of hydrology, and notation of disturbance. The methodology used to examine each parameter is described in the following sections.

1.1.1 **SOILS**

A hydric soil is a soil that formed under conditions of saturation, flooding, or ponding long enough during the growing season to develop anaerobic conditions in the upper part (*Midwest Regional Supplement*). The presence of hydric soil indicators is positive evidence of the hydric soil parameter. Soils were examined for hydric soil characteristics using a spade shovel to extract soil samples. A *Munsell Soil Color Chart* (Kollmorgen Corporation, 2010) was used to identify the hue, value, and chroma of the matrix and mottles of the soils which describes the soil profile. The completed soil profile was used to determine which, if any, hydric soil indicators were met as detailed in the *Midwest Regional Supplement*.

1.1.2 HYDROLOGY

The 1987 Manual requires that an area be inundated or saturated to the surface for an absolute minimum of five percent of the growing season (areas saturated between five percent and 12.5 percent of the growing season may or may not be wetlands, while areas saturated over five percent and 12.5 percent of the growing season fulfill the hydrology requirements for wetlands). The Midwest Regional Supplement states that the growing season dates are determined through onsite observations of the following indicators of biological activity in a given year: (1) above-ground growth and development of vascular plants, and/or (2) soil temperature (12-inch depth) is 41-degree Fahrenheit (°F) or higher as an indicator of soil microbial activity. Therefore, the beginning of the growing season in a given year is indicated by whichever condition occurs earlier, and the end of the growing season by whichever persists later.

The *Midwest Regional Supplement* also states that if onsite data gathering is not practical, the growing season can be approximated by the number of days between the average (5 of 10 years, or 50 percent probability of recurrence) date of the last and first 28° F air temperature in the spring and fall, respectively. The National Weather Service WETS data obtained from the NRCS National Water and Climate Center reveals for Licking County that in an average year, this period lasts from April 13 to October 28, or 197 days. Thus, for the Project location, five percent of the growing season equates to approximately ten days.

The soils and ground surface were examined for evidence of wetland hydrology in lieu of detailed hydrological data. This is an acceptable approach according to the 1987 Manual and the Midwest Regional



Supplement. Evidence indicating wetland hydrology typically includes primary indicators such as surface water, saturation, water marks, drift deposits, water-stained leaves, sediment deposits and oxidized rhizospheres on living roots; and secondary indicators such as drainage patterns, geomorphic position, micro-topographic relief, and a positive Facultative (FAC)-neutral test (USACE, 2010).

1.1.3 VEGETATION

Dominant vegetation was visually assessed for each stratum (tree, sapling/shrub, herb and woody vine) and an indicator status of obligate wetland (OBL), facultative wetland (FACW), facultative (FAC), facultative upland (FACU), and/or upland (UPL) was assigned to each plant species based on the U.S. Army Corps of Engineers 2018 National Wetland Plant List: Midwest Region (U.S. Army Corps of Engineers, 2018), which encompasses the Project survey area. An area is determined to have a positive indicator for hydrophytic vegetation when, under normal circumstances, more than 50 percent of the composition of the dominant species are OBL, FACW and/or FAC species. Vegetation of an area was determined to be non-hydrophytic when 50 percent or more of the composition of the dominant species was FACU and/or UPL species. In lieu of the dominance test, the prevalence test can be used an indicator of hydrophytic vegetation. Recent USACE guidance indicates that to the extent possible, the hydrophytic vegetation decision should be based on the plant community that is normally present during the wet portion of the growing season in a normal rainfall year (USACE, 2010).

1.1.4 WETLAND CLASSIFICATIONS

Wetlands identified in the field were classified based on the naming convention found in *Classification of Wetlands and Deepwater Habitats of the United States* (Cowardin *et al*, 1979). There are five main classes of wetlands and deepwater habitats, including: marine, estuarine, riverine, lacustrine, and palustrine. Marine and estuarine wetlands are not found in the interior of the U.S. while riverine wetlands are typically delineated as streams (when there is an absence of vegetation within the channel). Lacustrine systems typically include dammed river channels and non-vegetated open water exceeding 20 acres. Palustrine systems, which includes non-tidal wetlands dominated by trees, shrubs, or emergent vegetation, are the primary wetland types which may be identified within the Project survey area. The possible palustrine wetland classification types are as follows:

PEM – Palustrine emergent wetlands are characterized by erect, rooted, herbaceous hydrophytes, excluding mosses and lichens. This vegetation is present for most of the growing season in most years. These wetlands are usually dominated by perennial plants.

PFO – Palustrine forested wetlands are characterized by woody vegetation that is three inches or more diameter at breast height (DBH), regardless of total height. These wetlands generally include an overstory of broad-leaved and needle-leaved trees, an understory of young saplings and shrubs, and an herbaceous layer.



PSS – Palustrine scrub/shrub wetlands are characterized by woody vegetation that is less than three inches DBH, and greater than 3.28 feet tall. The woody angiosperms (i.e., small trees or shrubs) in this broadleaved deciduous community have relatively wide, flat leaves that are shed annually during the cold or dry season.

PUB – Palustrine unconsolidated bottom wetlands includes all open water wetlands and deepwater habitats with at least 25 percent cover of particles smaller than stones, and a vegetative cover less than 30 percent. Palustrine open water wetlands are characterized by the lack of large stable surfaces for plant and animal attachment.

For some wetlands, multiple Cowardin classifications may be present where more than one classification's vegetation is dominant (vegetation covers 30 percent or more of the substrate). Where multiple Cowardin classifications are present, the Cowardin classification of the plants that constitute the uppermost layer of vegetation is listed.

1.1.5 OHIO RAPID ASSESSMENT METHOD v. 5.0

The Ohio Environmental Protection Agency (OEPA) *Ohio Rapid Assessment Method for Wetlands v. 5.0* (ORAM) was developed to determine the relative ecological quality and level of disturbance of a particular wetland in order to meet requirements under Section 401 of the Clean Water Act. Wetlands are scored on the basis of hydrology, upland buffer, habitat alteration, special wetland communities, and vegetation communities. Each of these subject areas is further divided into subcategories under the ORAM resulting in a score that describes the wetland using a range from 0 (low quality and high disturbance) to 100 (high quality and low disturbance). Wetlands scored from 0 to 29.9 are grouped into "Category 1", 30 to 59.9 are "Category 2" and 60 to 100 are "Category 3". Transitional zones exist between "Categories 1 and 2" from 30 to 34.9 and between "Categories 2 and 3" from 60 to 64.9. However, according to the OEPA, if the wetland score falls into the transitional range, it must be given the higher Category unless scientific data can prove it should be in a lower Category (Mack, 2001).

Category 1 Wetlands – Category 1 wetlands support minimal wildlife habitat, hydrological and recreational functions, and do not provide for or contain critical habitats for threatened or endangered species. In addition, Category 1 wetlands are often hydrologically isolated and have some or all of the following characteristics: low species diversity, no significant habitat for wildlife use, limited potential to achieve wetland functions, and/or a predominance of non-native species. These limited quality wetlands are considered to be a resource that has been severely degraded or has a limited potential for restoration, or is of low ecological functionality.

Category 2 Wetlands – support "moderate wildlife habitat, or hydrological or recreational functions," and as wetlands which are "...dominated by native species but generally without the presence of, or habitat for,



rare, threatened or endangered species; and wetlands which are degraded but have a reasonable potential for reestablishing lost wetland functions." Category 2 wetlands constitute the broad middle category of "good" quality wetlands, and can be considered a functioning, diverse, healthy water resource that has ecological integrity and human value. Some Category 2 wetlands are lacking in human disturbance and considered to be naturally of moderate quality; others may have been Category 3 wetlands in the past, but have been degraded to Category 2 status.

Category 3 Wetlands – have "...superior habitat, or superior hydrological or recreational functions." They are typified by high levels of diversity, a high proportion of native species, and/or high functional values. Category 3 wetlands include wetlands which contain or provide habitat for threatened or endangered species, are high quality mature forested wetlands, vernal pools, bogs, fens, or which are scarce regionally and/or statewide. A wetland may be a Category 3 wetland because it exhibits one or all of the above characteristics. For example, a forested wetland located in the flood plain of a river may exhibit "superior" hydrologic functions (e.g., flood retention, nutrient removal), but not contain mature trees or high levels of plant species diversity.

1.2 STREAM ASSESSMENT

Regulatory activities under the Clean Water Act provide authority for states to issue water quality standards and "designated uses" to all waters of the U.S. upstream to the highest reaches of the tributary streams. In addition, the Clean Water Act requires knowledge of the potential fish or biological communities that can be supported in a stream or river, including upstream headwaters. Streams were identified by the presence of a defined bed and bank, and evidence of an ordinary high water mark (OHWM). The USACE defines OHWM as "that line on the shore established by the fluctuations of water and indicated by physical characteristics such as a clear, natural line impressed on the bank, shelving, changes in the character of soil, destruction of terrestrial vegetation, the presence of litter and debris, or other appropriate means that consider the characteristics of the surrounding areas" (USACE, 2005).

Stream assessments were conducted using the methods described in the OEPA's *Methods for Assessing Habitat in Flowing Waters*: *Using OEPA's Qualitative Habitat Evaluation Index* (Rankin, 2006) and in the OEPA's *Field Methods for Evaluating Primary Headwater Streams in Ohio* (OEPA, 2020). Streams assessed in the Project survey area were reviewed for existing OEPA Aquatic Life Use Designations per OEPA's Water Quality Standards (OAC Chapter 3745-1). Those without an existing use designation were assigned a provisional aquatic life use designation based upon habitat assessment results (Rankin, 1989).

1.2.1 OEPA QUALITATIVE HABITAT EVALUATION INDEX

The Qualitative Habitat Evaluation Index (QHEI) is designed to provide a rapid determination of habitat features that correspond to those physical factors that most affect fish communities and which are generally important to other aquatic life (e.g, macroinvertebrates). The quantitative measure of habitat used to



calibrate the QHEI score are Indices (or Index) of Biotic Integrity (IBI) for fish. In most instances the QHEI is sufficient to give an indication of habitat quality, and the intensive quantitative analysis used to measure the IBI is not necessary. It is the IBI, rather than the QHEI, that is directly correlated with the aquatic life use designation for a particular surface water.

The QHEI method is generally considered appropriate for waterbodies with drainage basins greater than one square mile or if natural pools are greater than 40 cm in depth, or if the water feature is shown as blue-line waterway on USGS 7.5-minute topographic quadrangle maps. In order to convey general stream habitat quality to the public, the OEPA has assigned narrative ratings to QHEI scores. The ranges vary slightly for headwater streams ("H" are those with a watershed area less than or equal to 20 square miles) versus larger streams ("L" are those with a watershed area greater than 20 square miles). The Narrative Rating System includes: Very Poor (<30 H and L), Poor (30 to 42 H, 30 to 44 L), Fair (43 to 54 H, 45 to 59 L), Good (55 to 69 H, 60 to 74 L) and Excellent (70+ H, 75+ L).

1.2.2 OEPA PRIMARY HEADWATER HABITAT EVALUATION INDEX

Headwater streams are typically considered to be first-order and second-order streams, meaning streams that have no upstream tributaries (or "branches") and those that have only first-order tributaries, respectively. The stream order concept can be problematic when used to define headwater streams because stream-order designations vary depending upon the accuracy and resolution of the stream delineation. Headwater streams are generally not shown on USGS 7.5-minute topographic quadrangles and are sometimes difficult to distinguish on aerial photographs. Nevertheless, headwater streams are now recognized as useful monitoring units due to their abundance, widespread spatial scale and landscape position (Fritz, et al., 2006). Impacts to headwater streams can have a cascading effect on the downstream water quality and habitat value. The Headwater Habitat Evaluation Index (HHEI) is a rapid field assessment method for physical habitat that can be used to appraise the biological potential of most Primary Headwater (PHW) streams. The HHEI was developed using many of the same techniques as used for QHEI, but has criteria specifically designed for headwater habitats. To use the HHEI, the stream must have a "defined bed and bank, with either continuous or periodically flowing water, with watershed area less than or equal to 1.0 square mile, and a maximum depth of water pools equal to or less than 15.75 inches" (OEPA, 2018). Pool depth and water volume of headwater streams are normally insufficient to fully support the biological criteria associated with other sub-categories of aquatic life described in OAC 3745-1-07.

Headwater streams are scored based on channel substrate composition, bankfull width, and maximum pool depth. Assessment results in a score (0 to 100) that is converted to a specific PHW stream type. Streams that are scored from 0 to 29 are typically identified as "Class I PHW Streams", 30 to 70 are "Class II PHW Streams", and 71 to 100 are "Class III Streams". Technically, a stream can score relatively high, but actually belong in a lower class, and vice-versa. According to the OEPA, if the stream score falls into a class and the scorer feels that based on site observations that score does not reflect the actual stream class, a



biological assessment can be used to determine appropriate PHW stream type using the Level 2 or Level 3 PHW protocol (OEPA, 2020). Evidence of anthropogenic alterations to the natural channel will result in a "Modified" qualifier for the stream type.

Class I PHW Streams: are those that have "have limited or no aquatic life potential, except seasonally when flowing water is present for short time periods following precipitation or snow melt" (OEPA, 2020). These waterways typically exhibit no significant habitat for aquatic fauna, no significant wildlife use, and limited or no potential to achieve higher PHW aquatic biological functions.

Class II PHW Streams: are equivalent to "warmwater habitat" streams and exhibit intermittent or perennial flow. This stream class has a "moderately diverse community of warm water adapted native fauna either present seasonally or year-round" (OEPA, 2020). The species communities are composed of vertebrates (fish and salamanders) and/or benthic macroinvertebrates that are considered pioneering and/or temperature facultative species.

Class III PHW Streams: have prevailing flow and temperature conditions influenced by groundwater, with diverse communities of cold water adapted native fauna present year-round. Class III PHW streams may be further divided into two sub-types based upon a detailed and complete evaluation of the aquatic faunal community, though that level of assessment is outside the scope of the data quality objectives for the proposed project.

1.2.3 OEPA 401 WATER QUALITY CERTIFICATION FOR NATIONWIDE PERMIT ELIGIBILITY

The OEPA has designated each watershed in the state on the basis of whether it may be *ineligible* for coverage under Ohio EPA's 401 Water Quality Certification for Nationwide Permits. Mapping provided by OEPA illustrate the eligibility of streams in the area for a nationwide 401 permit. Three categories are identified: eligible, ineligible, and possibly eligible with additional field screening required. Impacts to streams within each watershed would then have eligibility for 401 Water Quality Certification determined by the watershed category. The three categories are defined as:

Eligible: Streams within the watershed are eligible for coverage under Ohio EPA's water quality certification for the nationwide permits if all other general and regional special terms and conditions are met.

Ineligible: Projects affecting high quality streams and undesignated streams draining directly to high quality streams, as represented in the map, must undergo an individual 401 Water Quality Certification review process.

Possibly Eligible: Additional field screening procedures are required for streams in the watershed to determine appropriate eligibility. Projects affecting undesignated streams within those HUC12 watersheds



that do not directly but eventually drain into high quality waters, might be eligible for coverage under Ohio EPA's 401 Water Quality Certification for Nationwide Permits depending on the results of a field screening assessment. The procedures for determining individual stream eligibility in this scenario are specified in Appendix D "Stream Eligibility Determination Process" of the OEPA Ohio State Water Quality Certification of the 2017 Nationwide Permit Reauthorization.

1.3 UPLAND DRAINAGE FEATURE

An upland drainage feature (UDF) is a non-jurisdictional drainage that does not meet the criteria of either a jurisdictional stream or a wetland. A UDF generally lacks an OWHM (USACE, 2005), and are equivalent to a swale or an erosional feature as described by the USACE: "generally shallow features in the landscape that may convey water across upland areas during and following storm events. Swales usually occur on nearly flat slopes and typically have grass or other low-lying vegetation throughout the swale" (USACE, 2007).

A roadside ditch may also be documented as a UDF if it meets the "not potentially jurisdictional" characterization as described in the Office of Environmental Services *Roadway Ditch Characterization Flowchart* (Ohio Department of Transportation, 2014). This would include a ditch that originates entirely within the roadway right-of-way, has a seasonal flow regime, was not constructed to drain a wetland, and does not have hydrophytic vegetation extending more than an insignificant amount beyond its original configuration.

In addition, UDF's (including swales, ditches, and other erosional features) are generally not "waters of the U.S." except in certain circumstances, such as relocated streams.

1.4 RARE, THREATENED, AND ENDANGERED SPECIES

AECOM conducted a rare, threatened, and endangered species review and general field habitat surveys within the Project survey area. The first phase of the survey involved a review of online lists of federally and state-listed species. In addition to the review of available lists, AECOM submitted a request to Ohio Department of Natural Resources (ODNR) Office of Real Estate – Environmental Review Section as well as the United States Fish and Wildlife Service (USFWS) in October 2020 soliciting comments on the proposed Project.

Agency-identified species of concern and available species-specific information was reviewed to identify the various habitat types that listed species are known to inhabit. AECOM field ecologists conducted a general habitat survey in conjunction with the stream and wetland field surveys as part of the second phase of assessing rare, threatened, and endangered species. Land uses within the Project survey area were assigned a general classification based upon the principal land characteristics and vegetative cover as observed during the field surveys.



2.0 RESULTS

In June 2021, AECOM ecologists walked the Project survey area to conduct the wetland delineation, stream assessment and habitat survey. Within the Project survey area, AECOM delineated two (2) wetlands, no streams and no ponds. The delineated features are discussed in detail in the following sections.

2.1 WETLAND DELINEATION

2.1.1 PRELIMINARY SOILS EVALUATION

Soils in delineated wetlands were observed and documented as part of the delineation methodology. According to the USDA/NRCS Web Soil Survey of Licking County, Ohio (USDA NRCS, 2018), three (3) soil series are mapped within the Project survey area, inclusive of five (5) mapped soil units. All four (4) soil map units are identified as hydric (USDA NRCS, 2019). Table 1 provides a detailed overview of all soil series and soil map units present within the Project survey area. Soil map units located in the Project survey area and vicinity are shown on Figure 2.

TABLE 1: SOIL MAP UNITS AND DESCRIPTIONS WITHIN THE INNOVATION SUBSTATION 138kV PROJECT SURVEY AREA

Soil Series	Symbol	Map Unit Description	Topographic Setting	Hydric	Drainage Class
Ponnington	BeA	Bennington silt loam, 0 to 2 percent slopes	End moraines, ground moraines	Yes	Very Poorly Drained
Bennington	BeB	Bennington silt loam, 2 to 6 percent slopes	End moraines, ground moraines	Yes	Very Poorly Drained
Centerburg	Cen1B1	Centerburg silt loam, 2 to 6 percent slopes	Ground moraines, end moraines, drainage ways	Yes	Poorly Drained
Centerburg	Cen1C2	Centerburg silt loam, 6 to 12 percent slopes, eroded	Ground moraines, end moraines, drainage ways	No	Somewhat Poorly Drained
Pewamo	Pe	Pewamo silty clay loam, low carbonate till, 0 to 2 percent slopes	Depressions, drainageways	Yes	Poorly Drained

 $\underline{USDA, NRCS.\ 2019\ Web\ Soil\ Survey.\ Available\ online\ at: https://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm}$

<u>USDA</u>, NRCS. Accessed September 2021. National Hydric Soils List by State. Available online at: http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/use/hydric/

2.1.2 NATIONAL WETLAND INVENTORY MAP REVIEW

National Wetland Inventory wetlands are areas of potential wetland that have been identified from USFWS aerial photograph interpretation which have typically not been field verified. Forested and heavy scrub/shrub wetlands are often not shown on NWI maps as foliage effectively hides the visual signature that indicates the presence of standing water and moist soils from an aerial view. In addition, small wetlands are typically not identified due to the scale of the aerial photography. The USFWS website states that the NWI maps are not intended or designed for jurisdictional wetland identification or location. As a result, NWI maps do not show all the wetlands found in a particular area nor do they necessarily provide accurate wetland boundaries. NWI maps are useful for providing indications of potential wetland areas, which are often



supported by soil mapping and hydrologic predictions, based upon topographical analysis using USGS topographic maps.

According to NWI data covering the Project location, the Project survey area does not contain any mapped NWI wetlands. The nearest NWI wetland to the Project survey area is a forested wetland with code PFO1C approximately 88 feet south of the southwest corner of the Project survey area (Figure 2).

2.1.3 DELINEATED WETLANDS

During the field survey, AECOM identified two (2) PEM wetlands within the Project survey area. A summary of these delineated wetlands is listed in Appendix A. Of the two (2) wetlands, both have been preliminarily identified as being WOTUS due to their apparent hydrologic connection to another WOTUS outside the Project survey area. Therefore, Wetland 1 and Wetland 2 are assumed to be "adjacent". Final jurisdictional status can only be determined by the USACE.

The locations and approximate extent of the wetlands identified within the Project survey area are shown on Figure 3. Completed USACE and ORAM wetland delineation forms and photographs of the wetlands are provided in Appendix B.

2.1.4 DELINEATED WETLANDS ASSESSMENT

Within the Project survey area, both of the delineated wetlands were identified as Category 1 wetlands with ORAM scores of 23.5 (Wetland 01) and 27.5 (Wetland 02). Wetland assessment results (ORAM score) are provided in the Project Wetland Table in Appendix A.

Category 1 Wetlands

The two Category 1 wetlands delineated within the Project survey area both consist of PEM habitat. The Category 1 wetlands generally exhibited narrow to wide, low to high intensive surrounding land uses (e.g., residential, urban, row cropping), nearly absent to moderate percentage of invasive species, and recovering hydrology from previous manipulation due to tile installation/blowout, stormwater input, ditches, and filling and grading. The wetlands also generally exhibited recent to recovered habitat from previous manipulation due to mowing, clearcutting, dredging and farming.

2.2 STREAM DELINEATION

During the field survey, no streams were identified within the Project survey area.



2.2.1 OEPA STREAM ELIGIBILITY

OEPA stream eligibility for 401 Water Quality Certification mapping was reviewed for the Project survey area. The Project Survey Area is encompassed by two watersheds designated by 401 WQC eligibility, as listed in Table 2. The sub-watershed is designated as Eligible. OEPA stream eligibility mapping for the Project vicinity is provided on Figure 4.

TABLE 2: SUMMARY OF WATERSHED 401 WQC ELIGIBILITY WITHIN THE INNOVATION SUBSTATION 138kV PROJECT SURVEY AREA

HUC-12	Watershed	401 WQC Eligibility	Number of Streams Delineated
050600011503	Headwaters Blacklick Creek	Possibly Eligible	0
050400060402	Headwaters South Fork Licking River	0	
		Total	0

2.3 PONDS

No ponds were observed within the Project survey area.

2.4 VEGETATIVE COMMUNITIES WITHIN THE PROJECT SURVEY AREA

AECOM ecologists conducted a general habitat survey in conjunction with the stream and wetland field surveys in June 2021. Three vegetative communities, as described below in Table 3, are present within the Project survey area. Portions of the Project survey area mainly include agricultural land, with smaller areas consisting of wetland areas and shrub lands. Habitat descriptions applicable to the Project as well as details on the expected impacts of construction are provided below. Photographs of vegetated land cover of the Project are displayed in Appendix C and can be seen visually from aerial photography provided on Figure 5.

TABLE 3: VEGETATIVE COMMUNITIES WITHIN THE INNOVATION SUBSTATION 138 kV PROJECT SURVEY AREA

Vegetative Community	Description	Approximate Acreage Within the Project Survey Area	Approximate Percentage Within the Project Survey Area
Old Field	Herbaceous cover exhibiting the earliest stages of recolonization by plants following disturbance, typically short-lived, giving way progressively to shrub and forest communities unless periodically redisturbed. Old field areas identified were infrequently maintained areas of grasses and forbs with occasional shrubs.	34.3	80.7%
Scrub-Shrub	Scrub-shrub habitats represent the successional stage between old-field and second growth forest, and often emerge in recently harvested forests responding to the lightness of the removed canopy. Dominant species consist of herbaceous communities similar to that of old field habitat with a few woody species, to a community dominated by forest herbs and woody species.	7.6	17.9%

Vegetative Community	Description	Approximate Acreage Within the Project Survey Area	Approximate Percentage Within the Project Survey Area
Streams/Wetlands	Palustrine emergent wetlands were observed within the Project survey area, interspersed through the row crops.	0.6	1.4%
Totals:		42.5	100%

2.5 RARE, THREATENED AND ENDANGERED SPECIES AGENCY COORDINATION

Protected Species Agency Consultation -

AECOM conducted a rare, threatened, and endangered species review for areas within the Project survey area. A summary of agency coordination is provided below. Correspondence letters from the USFWS and ODNR for the proposed Project are included as Appendix D. Table 4 provides a summary of the rare, threatened, and endangered species as well as potential habitat identified during the site visit.



TABLE 4
ODNR AND USFWS LISTED SPECIES WITHIN THE INNOVATION SUBSTATION 138kV PROJECT SURVEY AREA

Common Name (Scientific Name)	State Status	Federal Status	Habitat Description	Potential Habitat Observed in the Project Survey Area	Agency Comments	Potential Impacts and Avoidance Dates					
	Mammals										
Indiana Bat (<i>Myotis sodalis</i>)	Endangered	Endangered	Winter Indiana bat hibernacula include caves and mines, while summer habitat typically includes tree species exhibiting exfoliating bark or cavities that can be used for roosting. The 8- to 10-inch diameter size classes of several species of hickory (Carya spp.), oak (Quercus spp.), ash (Fraxinus spp.), birch (Betula spp.), and elm (Ulmus spp.) have been found to be utilized by the Indiana bat. These tree species and many others may be used when dead, if there are adequately sized patches of loosely-adhering bark or open cavities. The structural configuration of forest stands favored for roosting includes a mixture of loose-barked trees with 60 to 80 percent canopy closure and a low-density sub-canopy (less than 30 percent between about 6 feet high and the base canopy). The suitability of roosting habitat for foraging or the proximity to suitable foraging habitat is critical to the evaluation of a particular tree stand. An open subcanopy zone, under a moderately dense canopy, is important to allow maneuvering while catching insect prey.	No- No wooded areas were identified within the Project survey area.	USFWS and ODNR commented that if no caves or abandoned mines are present and trees >3 inches dbh cannot be avoided, USFWS and ODNR recommend that any cutting of trees ≥3 inches DBH occur between October 1 and March 31. ODNR similarly requested that suitable Indiana bat habitat should be conserved or cut between October 1 and March 31.	No potential suitable habitat (woodlands) observed during the field survey, and therefore, no impacts to this species or its habitat are anticipated.					



TABLE 4
ODNR AND USFWS LISTED SPECIES WITHIN THE INNOVATION SUBSTATION 138kV PROJECT SURVEY AREA

Common Name (Scientific Name)	State Status	Federal Status	Habitat Description	Potential Habitat Observed in the Project Survey Area	Agency Comments	Potential Impacts and Avoidance Dates
Northern Long- eared Bat (Myotis septentrionalis)	Threatened	Threatened	Winter hibernacula include caves and mines, while summer habitat typically includes tree species exhibiting exfoliating bark or cavities that can be used for roosting. The 8-to 10-inch diameter size classes of several species of hickory (Carya spp.), oak (Quercus spp.), ash (Fraxinus spp.), birch (Betula spp.), and elm (Ulmus spp.) have been found to be utilized by northern long-eared bats. These tree species and many others may be used when dead, if there are adequately sized patches of loosely-adhering bark or open cavities. The structural configuration of forest stands favored for roosting includes a mixture of loose-barked trees with 60 to 80 percent canopy closure and a low-density sub-canopy (less than 30 percent between about 6 feet high and the base canopy). The suitability of roosting habitat for foraging or the proximity to suitable foraging habitat is critical to the evaluation of a particular tree stand. An open subcanopy zone, under a moderately dense canopy, is important to allow maneuvering while catching insect prey. Northern long-eared bats have also been found, albeit rarely, roosting in structures like barns and sheds.	No - No wooded areas were identified within the Project survey area.	USFWS commented that if no caves or abandoned mines are present and trees >3 inches dbh cannot be avoided, USFWS recommend that any cutting of trees ≥3 inches DBH occur between October 1 and March 31. ODNR commented that because presence of state endangered bat species has been established in the area, summer tree cutting is not recommended, and additional summer surveys would not constitute presence/absence in the area. However, limited summer tree cutting inside this buffer may be acceptable after further consultation with DOW.	No potential suitable habitat (woodlands), barns, and/or sheds were observed during the field survey, and therefore, no impacts to this species or its habitat are anticipated. According the ODNR Division of Mineral Resources data, no mines or caves are mapped in the Project Survey Area.



TABLE 4
ODNR AND USFWS LISTED SPECIES WITHIN THE INNOVATION SUBSTATION 138kV PROJECT SURVEY AREA

			TED SI ESIES WITHIN THE INNO			7.1.1.2.1
Common Name (Scientific Name)	State Status	Federal Status	Habitat Description	Potential Habitat Observed in the Project Survey Area	Agency Comments	Potential Impacts and Avoidance Dates
Little brown bat (Myotis lucifugus)	Endangered	NA	The little brown bat shares similar habitat requirements as other Myotis species including the Indiana bat and northern long-eared bat. This species may roost in trees, attics, or other man-made structures during the summer season. In winter, they may hibernate in caves, mines, or man-made structures with appropriate temperature regimes.	No - No wooded areas were identified within the Project survey area. Additionally, during the field survey, no caves or mines were identified in the Project Survey Area.	ODNR recommends tree cutting only occur from October 1 through March 31, conserving trees with loose, shaggy bark and/or crevices, holes, or cavities, as well as trees with DBH ≥ 20 if possible.	No potential suitable habitat (woodlands) observed during the field survey, and therefore, no impacts to this species or their habitat are anticipated. According the ODNR Division of Mineral Resources data, no mines or caves are mapped in the Project Survey Area.
Tricolored bat (Perimyotis subflavus)	Endangered	NA	The tricolored bat primarily roosts in trees during the summer months. During winter, this species hibernates in humid mines, caves, and occasionally man-made structures.	No - No wooded areas were identified within the Project survey area. During the field survey, no caves or mines were identified in the Project Survey Area	ODNR recommends tree cutting only occur from October 1 through March 31, conserving trees with loose, shaggy bark and/or crevices, holes, or cavities, as well as trees with DBH ≥ 20 if possible.	No potential suitable habitat (woodlands), barns, and/or sheds observed during the field survey, and therefore, no impacts to this species or their habitat are anticipated. According the ODNR Division of Mineral Resources data, no mines or caves are mapped in the Project Survey Area.
			Mus	sels		
Fawnsfoot (<i>Truncilla</i> donaciformis)	Threatened	None	This species can be found in medium to large rivers at depths between less than three feet to 18 feet. It prefers sand or mud substrates. It is also adapted to lakes and embankments.	No	ODNR stated that due to the location, and that there is no in-water work proposed in a perennial stream of sufficient size, this project is not likely to impact these species.	No potentially suitable habitat was observed within the Project survey area. No impacts to mussel species and their habitat are anticipated



TABLE 4
ODNR AND USFWS LISTED SPECIES WITHIN THE INNOVATION SUBSTATION 138kV PROJECT SURVEY AREA

	GD 111(71)	D 001 110 210	TED SPECIES WITHIN THE INNO	I STATE OF STATE OF THE STATE O	55KT - KCC2CT GGKTE					
Common Name (Scientific Name)	State Status	Federal Status	Habitat Description	Potential Habitat Observed in the Project Survey Area	Agency Comments	Potential Impacts and Avoidance Dates				
	Fish									
Lake chubsucker (Erimyzon sucetta)	Threatened	None	This species is found mainly in lakes, ponds, swamps, and streams.	No	The DOW recommends no in water work in perennial streams from March 15 through June 30 to reduce impacts to indigenous aquatic species and their habitat. If no in-water work is proposed in a perennial stream, this project is not likely to impact this or other aquatic species	No potentially suitable habitat was observed within the Project survey area. No impacts to these fish species and their habitat are anticipated				
			Bir	ds						
Upland Sandpiper (<i>Bartramia</i> <i>longicauda</i>)	Endangered	None	This species utilizes dry grasslands including native grasslands, seeded grasslands, grazed and ungrazed pasture, hayfields, and sometimes the grassy extensions of airports.	No-No potentially suitable habitat was observed for this species	If grassland habitat will be impacted, ODNR requests construction should be avoided in this habitat during the species' nesting period of April 15 to July 31. If this type of habitat will not be impacted, this project is not likely to impact this species.	The Project Survey Area does contain former agricultural lands including old field and shrub/scrub areas. However, the vegetation within the Project Survey Area, such as goldenrod, ragweed, curly dock and shrub layers are too tall and/or advanced in succession to be suitable for Upland Sandpiper. Furthermore, adjacent land use consists of a large dog day care facility (Kennel Club) which may effectively disturb or deter sensitive species from using the area. Timing restrictions or other measures are not recommended for Upland Sandpiper.				



TABLE 4
ODNR AND USFWS LISTED SPECIES WITHIN THE INNOVATION SUBSTATION 138kV PROJECT SURVEY AREA

Common Name (Scientific Name)	State Status	Federal Status	Habitat Description	Potential Habitat Observed in the Project Survey Area	Agency Comments	Potential Impacts and Avoidance Dates
Least bittern (Ixobrychus exilis)	Threatened	None	Dense emergent wetlands with dense, tall growths of aquatic or semi aquatic vegetation interspersed with cluims of woody vegetation and open water.	No- No potentially suitable habitat was observed for this species	If this type of habitat will be impacted, construction should be avoided during the nesting period of May 1 through July 31.	Wetlands within the Project Survey Area do not provide the necessary mosaic of vegetative and water depth conditions for Least Bittern. Therefore, no timing restrictions or other measures are recommended for Least Bittern.
Northern harrier (Circus hudsonius)	Endangered	None	This species hunts over grasslands and nests can be found in large marshes and grasslands.	No-No potentially suitable habitat was observed for this species	If grassland habitat will be impacted, construction should be avoided during the nesting period of April 15 through July 31.	No potential suitable habitat was observed. The wetlands evaluated in the area are small wetlands which do not provide adequate protection from predators and the vegetation structure within the area is dominated by such species as ragweed, goldenrod, and curly dock and/or scrub/shrub. The adjacent land use consisting of a large dog day care operation also likely would deter Northern Harrier use of the Project Survey Area for breeding. Timing restrictions or other measures are not recommended for Northern Harrier.



ODNR Coordination – Coordination with the ODNR was initiated during the planning stages of the Project to obtain technical assistance regarding state listed species that may occur within the project vicinity. On October 21, 2021, the ODNR Office of Real Estate Environmental Review Section replied to an emailed request for records for protected species within an extended area around the Project site. The Ohio Natural Heritage Database (ONHD), Division of Wildlife (DOW), and the Division of Water Resources (DWR) provided comments regarding their respective regulatory authorities.

ONHD indicated that there are no records of state or federally protected plant or animal species within a one-mile radius of the Project Survey Area. Additionally, ONHD indicated that there are no records of any unique or protected areas within a one-mile radius of the Project Survey Area.

The DOW noted that the Project is within the range of the Indiana bat, the northern long-eared bat, the little brown bat and the tricolored bat. If suitable habitat occurs within the Project Survey Area and the trees must be cut, the DOW recommends cutting occur between October 1 to March 31. ODNR also recommended that a desktop habitat assessment, followed by a field assessment (if needed), be conducted to determine if there are potential hibernaculum(a) present within the Project Survey Area. According the ODNR Division of Mineral Resources data, no mines or caves are mapped in the Project Survey Area. No mines or caves were identified in the Project Survey Area during the field survey. No impacts to these bat species or their habitat is anticipated.

The DOW noted that the Project location is within the range of several state-protected aquatic species. The DOW stated that due to the location, and that there is no in-water work proposed in a perennial stream of sufficient size, that the Project was not likely to impact these species.

The DOW noted that the Project is within the range of the upland sandpiper, a state endangered bird. ODNR-DOW has also indicated that at least 19 acres of grassland habitat would be needed to be considered suitable habitat for the upland sandpiper. ODNR indicated that construction should be avoided during the upland sandpiper's nesting period (April 15 to July 31) to avoid impacts to grasslands, pasture and hayfield habitats. There are no documented occurrences of Upland Sandpiper within a one-mile radius of the Project Survey Area or vicinity and the habitat within the Project Survey Area is not suitable for breeding or nesting Upland Sandpiper. The Project Survey Area does contain former agricultural lands that have been retired and are in varied states of succession including old field and shrub/scrub areas. However, the vegetation within the Project Survey Area, such as goldenrod, ragweed, curly dock and shrub layers are too tall and/or advanced in succession to be suitable for Upland Sandpiper. Furthermore, adjacent land use consists of a large dog day care facility (Kennel Club) which may effectively disturb or deter sensitive species from using the area. Timing restrictions or other measures are not recommended for Upland Sandpiper.



The DOW noted that the Project is within the range of the northern harrier, a state endangered bird. There are no documented occurrences of Northern Harrier within a one-mile radius of the Project Survey Area or vicinity and the Project Survey Area is not suitable for breeding or nesting Northern Harrier. The wetlands evaluated in the area are small wetlands which do not provide adequate protection from predators and the vegetation structure within the area is dominated by such species as ragweed, goldenrod, and curly dock and/or scrub/shrub. The adjacent land use consisting of a large dog day care operation also likely would deter Northern Harrier use of the Project Survey Area for breeding. Timing restrictions or other measures are not recommended for Northern Harrier.

The DOW noted that the Project is within the range of the least bittern, a state endangered bird. There are no documented Least Bittern occurrences within a one-mile radius of the Project Survey Area or vicinity and habitat within the Project Survey Area is not suitable for Least Bittern. Wetlands within the Project Survey Area do not provide the necessary mosaic of vegetative and water depth conditions for Least Bittern. Therefore, no timing restrictions or other measures are recommended for Least Bittern.

USFWS Coordination – Coordination with the USFWS was initiated during the planning stages of the Project to obtain technical assistance regarding federally listed species that may occur within the Project vicinity. In a letter dated October 7, 2021,the USFWS indicated that the Project is located within the range of the federally endangered Indiana bat, and the federally threatened Northern long-eared bat. USFWS commented that if no caves or abandoned mines are present and trees >3 inches dbh cannot be avoided, USFWS recommend that any cutting of trees ≥3 inches DBH occur between October 1 and March 31 to avoid adverse effects to Indiana bats and Northern long-eared bats during the brood-rearing months.

3.0 SUMMARY

The ecological survey of the Project survey area identified a total of two wetlands, no streams and no ponds. The wetlands identified in the Project survey area are both palustrine emergent (PEM) wetlands and were both identified as Category 1 wetlands. Both wetlands have provisionally been classified as adjacent wetlands and are presumed to be Waters of the U.S. (WOTUS) under the CWA 40 CFR 230.3(s). Final jurisdictional status can only be determined by the USACE.

ODNR and/or USFWS reported that the Project Survey Area is within the range of nine (9) state and/or federally listed threatened or endangered species, but the Natural Heritage Database has no records of any of those species at or within one-mile radius of the Project Survey Area.

Based on the lack of suitable habitat observed during the field survey, no impacts to the Indiana bat, northern long-eared bat, little brown bat and tricolored bat are anticipated.

There are no documented occurrences of upland sandpiper, northern harrier or least bittern within the Project Survey Area and vicinity. Based on the lack of suitable habitat observed during the field survey,



timing restrictions or other measures are not recommended avoidance of nesting habitat for the upland sandpiper, northern harrier or least bittern.

The reported results of the ecological survey conducted by AECOM on this Project are limited to the areas within the Project survey boundary provided in Figure 3. Areas that fall outside of the Project survey boundary were not evaluated in the field and are not included in the reporting of this survey.

The information contained in this wetland delineation report is for a study area that may be much larger than the actual Project limits-of-disturbance; therefore, lengths and acreages listed in this report may not constitute the actual impacts of the Project defined in subsequent permit applications. If necessary, a separate report that identifies the actual Project impacts will be provided with agency submittals.


The field survey results presented herein apply to the existing and reasonably foreseeable site conditions at the time of our assessment. They cannot apply to site changes of which AECOM is unaware and has not had the opportunity to review. Changes in the condition of a property may occur with time due to natural processes or human impacts at the project site or on adjacent properties. Changes in applicable standards may also occur as a result of legislation or the expansion of knowledge over time. Accordingly, the findings of this report may be invalidated, wholly or in part, by changes beyond the control of AECOM.


4.0 REFERENCES


- Cowardin, L.M., V. Carter, F.C. Golet and E.T. LaRoe. 1979. *Classification of Wetlands and Deepwater Habitats of the United States*. Office of Biological Services, U.S. Fish and Wildlife Service, Washington, D.C.
- Fritz, K.M., B.R. Johnson, and D.M. Walters. 2006. Field Operations Manual for Assessing the Hydrologic Permanence and Ecological Condition of Headwater Streams. EPA/600/ R-06/126. U.S. Environmental Protection Agency, Office of Research and Development, Washington DC.
- Kollmorgen Corporation. 2010. Munsell Soil Color Charts. Baltimore, Maryland.
- Lichvar, R.W., D.L. Banks, W.N. Kirchner, and N.C. Melvin. 2016. The National Wetland Plant List: 2016 wetland ratings. Phytoneuron 2016-30: 1-17. Published 28 April 2016. ISSN 2153 733X
- Mack, John J. 2001. *Ohio Rapid Assessment Method for Wetlands v. 5.0, User's Manual and Scoring Forms. OEPA Technical Report WET/2001-1.* Ohio Environmental Protection Agency, Division of Surface Water, 401/Wetland Ecology Unit, Columbus, Ohio.
- Ohio Administrative Code Chapter 3745-1. Water Quality Standards. https://epa.ohio.gov/Portals/35/rules/01-all.pdf. Effective July 30, 2018.
- Ohio DNR. 2018. Ohio Mussel Survey Protocol. April 2018. Ohio Department of Natural Resources (ODNR), Division of Wildlife and U.S. Fish and Wildlife Service (USFWS), Ohio Ecological Services Field Office. 47 pp.
- Ohio EPA. 2017. Section 401 Water Quality Certification for the 2017 Nationwide Permits. Effective March 17, 2017. Ohio Environmental Protection Agency, Division of Surface Water, 401 Water Quality Certification and Isolated Wetland Permitting Section, Columbus, Ohio.
- Ohio EPA. 2017. 401 Water Quality Certification for the Nationwide Permits Stream Eligibility Web Map (2017 Reissuance). https://data-oepa.opendata.arcgis.com/datasets/401-water-quality-certification-for-nationwide-permits.
- Ohio EPA, 2020. Field Methods for Evaluating Primary Headwater Streams in Ohio. Version 4.1. Ohio EPA Division of Surface Water, Columbus, Ohio. 130 pp.
- Rankin, Edward T. 1989. The Qualitative Habitat Evaluation Index (QHEI): Rationale, Methods, and Application. Ohio EPA Ecological Assessment Section, Division of Surface Water, Columbus, Ohio.
- Rankin, Edward T. 2006. *Methods for Assessing Habitat in Flowing Waters: Using the Qualitative Habitat Evaluation Index (QHEI)*. OEPA Ecological Assessment Section, Division of Surface Water, Columbus, Ohio.
- U.S. Army Corps of Engineers. 2005. Regulatory Guidance Letter No. 05-05: Guidance on Ordinary High Water Mark Identification.
- U.S. Army Corps of Engineers. 2010. Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Midwest Region (Version 2.0), ed. J. S. Wakeley, R. W. Lichvar, J. F. Berkowitz, and C. V. Noble. ERDC/EL TR-12-9. Vicksburg, MS: U.S. Army Engineer Research and Development Center.
- U.S. Army Corps of Engineers. 2018. National Wetland Plant List, version 3.3. Engineer Research and




- Development Center. Cold Regions Research and Engineering Laboratory, Hanover, NH. http://wetland_plants.usace.army.mil/
- U.S. Army Corps of Engineers. 1987. *U.S. Corps of Engineers Wetlands Delineation Manual.* Technical Report Y-87-1, U.S. Army Engineer Waterways Experiment Station: Vicksburg, Mississippi.
- U.S. Department of Agriculture, Natural Resources Conservation Service. 2018. National Weather Service- Wetland Climate Evaluation Database (WETS Table). http://agacis.rcc-acis.org/ Accessed September 2021.
- U.S. Department of Agriculture, Natural Resources Conservation Service. 2018. Soil Survey Geographic (SSURGO) Database. Available online at: https://catalog.data.gov/dataset/soil-survey-geographic-surgo-database-for-various-soil-survey-areas-in-the-united-.
- U.S. Department of Agriculture, Natural Resources Conservation Service. 2019. National Hydric Soils List. http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/use/hydric/. Accessed September 2021.
- U.S. Department of Agriculture, Natural Resources Conservation Service. 2019. Web Soil Survey. http://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm. Accessed September 2021.
- U.S. Fish and Wildlife Service. 2018. National Wetlands Inventory Geodatabase for Ohio. Available online at http://www.fws.gov/wetlands/Data/Mapper.html. Accessed September 2021.
- U.S. Geological Survey. 2016. National Hydrography Dataset, Ohio Statewide Geodatabase. Published August 2016. Earth Science Information Center, USGS, Reston, VA.













APPENDIX A

PROJECT WETLAND TABLE

	Loc	ation			Delinerated	C	RAM	Named	Fulation	Burnered	Ott	Propose	d Impacts	
Wetland ID	Latitude	Longitude	Isolated?	Habitat Type	Delineated Area (acre)	Score	Category	Nearest Structure # (Existing / Proposed)	Existing Structure # in Wetland	Proposed Structure # in Wetland	Structure Installation Method	Temporary Matting Area (acre)	Permanent Impact Area (acre)	
Wetland 1	40.091510	-82.728780	No	PEM	0.265	23.5	1	None/4	None	TBD	TBD	TBD	TBD	
Wetland 2	40.093420	-82.728780	No	PEM	0.436	27.5	1	None/None	None	TBD	TBD	TBD	TBD	
				Total:	0.701							0.000 0.000		



APPENDIX B

 $\hbox{ U.S. ARMY CORPS OF ENGINEERS WETLAND DATA FORMS }$

OEPA WETLAND ORAM FORMS

DELINEATED FEATURES PHOTOGRAPHS (WETLANDS)

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Innovation Station Project		City/Cou	ınty: Licking	County	San	npling Da	nte: 06/0	3/2021
Applicant/Owner: AEP				State: O	H Sam	npling Po	int: w-JBL-	20210603-01
Investigator(s): JBL,SKM		Section,	Township, Ra	nge: Q/T2N/R	15W			
Landform (hillside, terrace, etc.): depression				concave, convex, r		ve		
Slope (%): 1 Lat: 40.09151			-82.72878			n: NAD 8	3	
Soil Map Unit Name: BeB - Bennington silt loam, 2 to 6	nercent slo		02.72070	NWI	classification			
Are climatic / hydrologic conditions on the site typical for			Vos	No x (If r			·c)	
		-						
Are Vegetation, Soil, or Hydrologys							NO	-
Are Vegetation, Soil, or Hydrologyn			•	plain any answers		•		
SUMMARY OF FINDINGS – Attach site ma	p showi	ng samplir	ng point lo	cations, trans	ects, imp	ortant	features	s, etc.
Hydrophytic Vegetation Present? Yes X No		Is the	e Sampled A	rea				
		withi	n a Wetland	? Yes	X N	۰		
Wetland Hydrology Present? Yes X No								
Remarks:		•						
Depressional area W-JBL-20210603-01 near woodlot. which appears to flow towards an UNT of South Fork I			of suvey area	to east towards a	drainage sy	/stem		
		· · · · · · · · · · · · · · · · · · ·						
VEGETATION – Use scientific names of plan	nts.							
<u>Tree Stratum</u> (Plot size: 30' radius)	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Te	et workeho	at·		
1. N/A	70 COVE	Оресіез:	Otatus	Number of Dom				
2.				Are OBL, FACV	•	es IIIal	5	(A)
3.				Total Number o	f Dominant S	- Species		_
4.				Across All Strat		_	5	_(B)
5				Percent of Dom	inant Specie	s That		
		=Total Cover		Are OBL, FACV	V, or FAC:	_	100.0%	_(A/B)
Sapling/Shrub Stratum (Plot size: 15' radius)								
1. Rosa virginiana	10	Yes	FAC	Prevalence Ind			14:	
2. 3.				Total % Co	60	x 1 =	Itiply by: 60	-
4.				FACW species		x 2 =	100	-
5.				FAC species	10	x 3 =	30	_
	10	=Total Cover		FACU species		x 4 =	0	-
Herb Stratum (Plot size: 5' radius)				UPL species	0	x 5 =	0	_
1. Juncus effusus	40	Yes	OBL	Column Totals:	120	(A)	190	_ (B)
2. Scirpus atrovirens	20	Yes	OBL	Prevalence I	ndex = B/A	=	1.58	_
3. Carex vulpinoidea	20	Yes	FACW					
4. Lysimachia nummularia	20	Yes	FACW_	Hydrophytic Ve	_			
5. Leersia virginica	10	<u>No</u>	<u>FACW</u>		est for Hydro		egetation	
6.				X 2 - Dominar				
7				X 3 - Prevaler	nce Index is ogical Adapt		Dravida av	nnartina
8 9.					ogicai Adapi lemarks or o			
10.					c Hydrophyti			
10	110	=Total Cover		¹ Indicators of hy		•	, ,	•
Woody Vine Stratum (Plot size: 30' radius)		50.51		be present, unle				must
1. <i>N/A</i>				Hydrophytic		•		
2.				Vegetation				
		=Total Cover		Present?	Yes X	No_		
Remarks: (Include photo numbers here or on a separa	ate sheet.)							
Wetland Vegetation indicators present, dominance tes	t is >50%, _I	oreveleance in	ndex is less th	nan or equal to 3.0	. Dominant s	species a	re OBL, F	ACW,

US Army Corps of Engineers

SOIL Sampling Point: IBL-20210603

Profile Des	cription: (Describe	to the dep	th needed to doc	ument t	he indica	tor or c	onfirm the absence of	of indicators.)
Depth	Matrix		Redo	x Featu	res			
(inches)	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²	Texture	Remarks
0-8	10YR 4/2	95	10YR 4/6	5	<u> </u>	PL/M	Loamy/Clayey	Prominent redox concentrations
8-17	10YR 4/1	95	10yr 4/6	5	С	М	Loamy/Clayey	Prominent redox concentrations
			•					
		. — -					-	
<u> </u>								
	concentration, D=Dep	oletion, RM=	Reduced Matrix, I	MS=Mas	ked Sand	Grains		PL=Pore Lining, M=Matrix.
Hydric Soil								s for Problematic Hydric Soils ³ :
— Histosol	` '		Sandy Gle					t Prairie Redox (A16)
I —	pipedon (A2)		Sandy Re					Manganese Masses (F12)
l —	istic (A3)		Stripped N	,	,			Parent Material (F21)
I — ·	en Sulfide (A4)		Dark Surfa	` '			·	Shallow Dark Surface (F22)
l —	d Layers (A5) uck (A10)		Loamy Mu	•	. ,		Otner	(Explain in Remarks)
	dck (ATU) d Below Dark Surfac	ρ (Δ11)	X Depleted					
I —	ark Surface (A12)	e (ATT)	Redox Da				³ Indicators	s of hydrophytic vegetation and
l —	Mucky Mineral (S1)		Depleted		, ,			nd hydrology must be present,
	ucky Peat or Peat (S	3)	? Redox De		٠,			s disturbed or problematic.
	Layer (if observed):				(- ()	Т		
Type:	Layer (ii observea).	1						
Depth (i	nches):						Hydric Soil Present	? Yes X No
							,	
Remarks:	rm is revised from M	idwest Regi	onal Supplement	Version	2 0 to inc	lude the	NRCS Field Indicators	of Hydric Soils in the United States,
	2018. (https://www.r							, ,
Hydric soil ir	ndicators present ind	icated by pr	rominent redox co	ncentrati	ons			
HYDROLO	OGY							
r	drology Indicators:							
1	cators (minimum of		red: check all that	annly)			Secondari	y Indicators (minimum of two required)
	Water (A1)	one is requi	Water-Sta		aves (RQ)			ce Soil Cracks (B6)
	ater Table (A2)		Aquatic F					age Patterns (B10)
x Saturation			True Aqua					leason Water Table (C2)
I —	farks (B1)		Hydrogen		, ,)		ish Burrows (C8)
	nt Deposits (B2)		x Oxidized F					ation Visible on Aerial Imagery (C9)
	posits (B3)		Presence			-	` ' 	ed or Stressed Plants (D1)
	at or Crust (B4)		Recent Iro					norphic Position (D2)
	posits (B5)		Thin Muck					Neutral Test (D5)
Inundati	on Visible on Aerial I	magery (B7	') Gauge or	Well Da	ta (D9)			
Sparsely	y Vegetated Concave	e Surface (E	38) Other (Ex	olain in F	Remarks)			
Field Obser	rvations:							
Surface Wa	ter Present? Ye	es	No x	Depth (inches):			
Water Table	Present? Ye	es —	No x	Depth (inches):			
Saturation P	Present? Ye	es x	No	Depth (inches):	12	Wetland Hydrolog	y Present? Yes X No
(includes ca	pillary fringe)							
Describe Re	ecorded Data (stream	gauge, mo	onitoring well, aeria	al photos	, previous	s inspec	tions), if available:	
Remarks:	rocont indicates	and budget	and propert 14/54	and d==!	on offeite	to the -	aat	
Saturation p	resent indicates wetl	and nydrold	ogy present. Wetla	and drair	is ottsite	to the ea	สธเ	
US Army Cor	ps of Engineers							Midwest Region Version 2

	Ohio Rapid Assessment Method for Wetlands 10 Page Form for Wetland Categorization							
Version 5.0	Background Information Scoring Boundary Worksheet Narrative Rating Field Form Quantitative Rating ORAM Summary Worksheet Wetland Categorization Worksheet	Ohio EPA, Division of Surface Water Final: February 1, 2001						

Instructions

The investigator is *STRONGLY URGED* to read the Manual for Using the Ohio Rapid Assessment Method for Wetlands for further elaboration and discussion of the questions below prior to using the rating forms.

The Narrative Rating is designed to categorize a wetland or to provide alerts to the Rater based on the presence or possible presence of threatened or endangered species. The presence or proximity of such species is often an indicator of the quality and lack of disturbance of the wetland being evaluated. In addition, it is designed to categorize certain wetlands as presence or possible presence of threatened or endangered species. The presence or proximity of such species is often an indicator of the quality and lack of disturbance of the wetland being evaluated. In addition, it is designed to categorize certain wetlands as very low quality (Category 1) or very high quality (Category 3) regardless of the wetland's score on the Quantitative Rating. In addition, the Narrative Rating also alerts the investigator that a particular wetland may be a Category 3 wetland, again, regardless of the wetland's score on the Quantitative Rating.

It is *VERY IMPORTANT* to properly and thoroughly answer each of the questions in the ORAM in order to properly categorize a wetland. To properly answer all the questions, the boundaries of the wetland being assessed must be correctly identified. Refer to Scoring Boundary worksheet and the User's Manual for a discussion of how to determine the "scoring boundaries." In some instances, the scoring boundaries may differ from the "jurisdictional boundaries."

Refer to the most recent ORAM Score Calibration Report for the scoring breakpoints between wetland categories. The most recent version of this document is posted on Ohio EPA's Division of Surface Water web page at: http://www.epa.ohio.gov/dsw/wetlands/WetlandEcologySection.aspx

Background Information		
Name:	Jake Lubbers	
Date:	6/3/2021	
Affiliation:	AECOM	
Address:	525 Vine Street, Suite 1800, Cincinnati, Ohio 45202	
Phone Number:	513-419-3506	
e-mail address:	jake.lubbers@aecom.com	
Name of Wetland:	Wetland 01	
Vegetation Communit(ies):	РЕМ	
HGM Class(es):	Depressional	
Location of Wetland: include map	, address, north arrow, landmarks, distances, roads, etc.	

See Figures 1, 2, and 3 of Wetland Delineation and Stream Assessment Report.

Lat/Long or UTM Coordinate:	40.09153, -82.72839
USGS Quad Name:	Jersey
County:	Licking County
Township:	T2N
Section and Subsection:	R15W
Hydrologic Unit Code:	50400060402
Site Visit:	6/3/2021
National Wetland Inventory Map:	See Figure 2
Ohio Wetland Inventory Map:	N/A
Soil Survey:	See Figure 2
Delineation report/map:	See Figure 3

Name of Wetland:	Wetland 01		
Wetland Size (delineated acres):	0.27	Wetland Size (Estimated total	Approx. 0.3
Sketch: Include north arrow, relationshi		acres):	
, , , , , , , , , , , , , , , , , , , ,	F ,g		
Comments, Narrative Discussion, Justif Wetland 01 is a PEM wetland ne	ar the southeast corner of the	project survey area. Wetland	is in a donrossed landform
and drains outside of suvey area	a to east towards a drainage s	system which appears to now	towards an ONT of South
Fork Licking River.			
		<u></u>	
Final score:	23.5	Category:	1

Wetland ID:	Wetland 01
-------------	------------

Scoring Boundary Worksheet

INSTRUCTIONS. The initial step in completing the ORAM is to identify the "scoring boundaries" of the wetland being rated. In many instances this determination will be relatively easy and the scoring boundaries will coincide with the "jurisdictional boundaries." For example, the scoring boundary of an isolated cattail marsh located in the middle of a farm field will likely be the same as that wetland's jurisdictional boundaries. In other instances, however, the scoring boundary will not be as easily determined. Wetlands that are small or isolated from other surface waters often form large contiguous areas or heterogeneous complexes of wetland and upland. In separating wetlands for scoring purposes, the hydrologic regime of the wetland is the main criterion that should be used. Boundaries between contiguous or connected wetlands should be established where the volume, flow, or velocity of water moving through the wetland changes significantly. Areas with a high degree of hydrologic interaction should be scored as a single wetland. In determining a wetland's scoring boundaries, use the guidelines in the ORAM Manual Section 5.0. In certain instances, it may be difficult to establish the scoring boundary for the wetland being rated. These problem situations include wetlands that form a patchwork on the landscape, wetlands divided by artificial boundaries like property fences, roads, or railroad embankments, wetlands that are contiguous with streams, lakes, or rivers, and estuarine or coastal wetlands. These situations are discussed below, however, it is recommended that Rater contact Ohio EPA, Division of Surface Water, 401/Wetlands Section if there are additional questions or a need for further clarification of the appropriate scoring boundaries of a particular wetland.

#	Steps in properly establishing scoring boundaries	done?	not applicable
Step 1	Identify the wetland area of interest. This may be the site of a proposed impact, a reference site, conservation site, etc.	X	
Step 2	Identify the locations where there is physical evidence that hydrology changes rapidly. Such evidence includes both natural and human- induced changes including, constrictions caused by berms or dikes, points where the water velocity changes rapidly at rapids or falls, points where significant inflows occur at the confluence of rivers, or other factors that may restrict hydrologic interaction between the wetlands or parts of a single wetland.	x	
Step 3	Delineate the boundary of the wetland to be rated such that all areas of interest that are contiguous to and within the areas where the hydrology does not change significantly, i.e. areas that have a high degree of hydrologic interaction are included within the scoring boundary.	X	
Step 4	Determine if artificial boundaries, such as property lines, state lines, roads, railroad embankments, etc., are present. These should not be used to establish scoring boundaries unless they coincide with areas where the hydrologic regime changes.	Х	
Step 5	In all instances, the Rater may enlarge the minimum scoring boundaries discussed here to score together wetlands that could be scored separately.		X
Step 6	Consult ORAM Manual Section 5.0 for how to establish scoring boundaries for wetlands that form a patchwork on the landscape, divided by artificial boundaries, contiguous to streams, lakes or rivers, or for dual classifications.		X

End of Scoring Boundary Determination. Begin Narrative Rating on next page.

Narrative Rating

INSTRUCTIONS. Answer each of the following questions. Questions 1, 2, 3 and 4 should be answered based on information obtained from the site visit or the literature and by submitting a Data Services Request to the Ohio Department of Natural Resources, Division of Natural Areas and Preserves, Natural Heritage Data Services, 1889 Fountain Square Court, Building F-1, Columbus, Ohio 43224, 614-265-6453 (phone), 614-265-3096 (fax), http://www.dnr.state.oh.us/dnap. The remaining questions are designed to be answered primarily by the results of the site visit. Refer to the User's Manual for descriptions of these wetland types. Note: "Critical habitat" is legally defined in the Endangered Species Act and is the geographic area containing physical or biological features essential to the conservation of a listed species or as an area that may require special management considerations or protection. The Rater should contact the Region 3 Headquarters or the Columbus Ecological Services Office for updates as to whether critical habitat has been designated for other federally listed threatened or endangered species. "Documented" means the wetland is listed in the appropriate State of Ohio database.

#	Question	Circle one	
1	Critical Habitat. Is the wetland in a township, section, or subsection of a	YES	*NO
	United States Geological Survey 7.5 minute Quadrangle that has been designated by the U.S. Fish and Wildlife Service as "critical habitat" for any threatened or endangered plant or animal species? Note: as of January 1, 2001, of the federally listed endangered or threatened species which can be found in Ohio, the Indiana Bat has had critical habitat designated (50 CFR 17.95(a)) and the piping plover has had critical habitat proposed (65 FR 41812 July 6, 2000).	Wetland should be evaluated for possible Category 3 status Go to Question 2	Go to Question 2
2	Threatened or Endangered Species. Is the wetland known to contain an individual of,	YES	*NO
	or documented occurrences of federal or state-listed threatened or endangered plant or animal species?	Wetland is a Category 3 wetland. Go to Question 3	Go to Question 3
3	Documented High Quality Wetland. Is the wetland on record in Natural Heritage	YES	*NO
	Database as a high quality wetland?	Wetland is a Category 3 wetland Go to Question 4	Go to Question 4
4	Significant Breeding or Concentration Area. Does the wetland contain documented	YES	*NO
	regionally significant breeding or nonbreeding waterfowl, neotropical songbird, or shorebird concentration areas?	Wetland is a Category 3 wetland Go to Question 5	Go to Question 5
5	Category 1 Wetlands. Is the wetland less than 0.5 hectares (1 acre) in size and	YES	*NO
	hydrologically isolated and either 1) comprised of vegetation that is dominated (greater than eighty per cent areal cover) by <i>Phalaris arundinacea, Lythrum salicaria,</i> or <i>Phragmites australis</i> , or 2) an acidic pond created or excavated on mined lands that has little or no vegetation?	Wetland is a Category 1 wetland Go to Question 6	Go to Question 6
	Bogs. Is the wetland a peat-accumulating wetland that 1) has no significant inflows or	YES	*NO
	outflows, 2) supports acidophilic mosses, particularly <i>Sphagnum</i> spp., 3) the acidophilic mosses have >30% cover, 4) at least one species from Table 1 is present, and 5) the cover of invasive species (see Table 1) is <25%?	Wetland is a Category 3 wetland Go to Question 7	Go to Question 7
7	Fens. Is the wetland a carbon accumulating (peat, muck) wetland that is saturated	YES	*NO
	during most of the year, primarily by a discharge of free flowing, mineral rich, ground water with a circumneutral ph (5.5-9.0) and with one or more plant species listed in Table 1 and the cover of invasive species listed in Table 1 is <25%?	Wetland is a Category 3 wetland Go to Question 8a	Go to Question 8a
8a	"Old Growth Forest." Is the wetland a forested wetland and is the forest characterized	YES	*NO
	by, but not limited to, the following characteristics: overstory canopy trees of great age (exceeding at least 50% of a projected maximum attainable age for a species); little or no evidence of human-caused understory disturbance during the past 80 to 100 years; an allaged structure and multilayered canopies; aggregations of canopy trees interspersed with canopy gaps; and significant numbers of standing dead snags and downed logs?	Wetland is a Category 3 wetland. Go to Question 8b	Go to Question 8b

Wetland ID: Wetland 01

01:	Material Secretaria and a lateral and a lateral and a lateral secretaria	T	
8b	Mature forested wetlands . Is the wetland a forested wetland with 50% or more of the cover of upper forest canopy consisting of deciduous trees with large diameters at breast height (dbh), generally diameters greater than 45cm (17.7in) dbh?	YES Wetland should be evaluated for possible Category 3 status. Go to Question 9a	*NO Go to Question 9a
9a	Lake Erie coastal and tributary wetlands. Is the wetland located at an elevation less	YES	*NO
	than 575 feet on the USGS map, adjacent to this elevation, or along a tributary to Lake Erie that is accessible to fish?	Go to Question 9b	Go to Question 10
9b	Does the wetland's hydrology result from measures designed to prevent erosion and the loss of aquatic plants, i.e. the wetland is partially hydrologically restricted from Lake Erie due to lakeward or landward dikes or other hydrological controls?	YES Wetland should be evaluated for possible Category 3 status Go to Question 10	*NO Go to Question 9c
9с	Are Lake Erie water levels the wetland's primary hydrological influence,	YES	*NO
	i.e. the wetland is hydrologically unrestricted (no lakeward or upland border alterations), or the wetland can be characterized as an "estuarine" wetland with lake and river influenced hydrology. These include sandbar deposition wetlands, estuarine wetlands, river mouth wetlands, or those dominated by submersed aquatic vegetation.		Go to Question 10
9d	Does the wetland have a predominance of native species within its vegetation	YES	*NO
	communities, although non-native or disturbance tolerant native species can also be present?	Wetland is a Category 3 wetland Go to Question 10	Go to Question 9e
9e	Does the wetland have a predominance of non-native or disturbance tolerant native plant	YES	*NO
	species within its vegetation communities?	Wetland should be evaluated for possible Category 3 status Go to Question 10	Go to Question 10
10	Lake Plain Sand Prairies (Oak Openings) Is the wetland located in Lucas, Fulton,	YES	*NO
	Henry, or Wood Counties and can the wetland be characterized by the following description: the wetland has a sandy substrate with interspersed organic matter, a water table often within several inches of the surface, and often with a dominance of the gramineous vegetation listed in Table 1 (woody species may also be present). The Ohio Department of Natural Resources Division of Natural Areas and Preserves can provide assistance in confirming this type of wetland and its quality.	Wetland is a Category 3 wetland. Go to Question 11	Go to Question 11
1		YES	*NO
11	Relict Wet Prairies. Is the wetland a relict wet prairie community dominated by some or		110
11	Relict Wet Prairies. Is the wetland a relict wet prairie community dominated by some or all of the species in Table 1. Extensive prairies were formerly located in the Darby Plains (Madison and Union Counties), Sandusky Plains (Wyandot, Crawford, and Marion Counties), northwest Ohio (e.g. Erie, Huron, Lucas, Wood Counties), and portions of western Ohio Counties (e.g. Darke, Mercer, Miami, Montgomery, Van Wert etc.).	Wetland should be evaluated for possible Category 3 status Complete Quantitative Rating	Complete Quantitative Rating

Wetland ID: Wetland 01

invasive/exotic spp	fen species	bog species	oak opening species	wet prairie species
Lythrum salicaria	Zygadenus elegans var. glaucus	Calla palustris	Carex cryptolepis	Calamagrostis canadensis
Myriophyllum spicatum	Cacalia plantaginea	Carex atlantica var. capillacea	Carex lasiocarpa	Calamogrostis stricta
Najas minor	Carex flava	Carex echinata	Carex stricta	Carex atherodes
Phalaris arundinacea	Carex sterilis	Carex oligosperma	Cladium mariscoides	Carex buxbaumii
Phragmites australis	Carex stricta	Carex trisperma	Calamagrostis stricta	Carex pellita
Potamogeton crispus	Deschampsia caespitosa	Chamaedaphne calyculata	Calamagrostis canadensis	Carex sartwellii
Ranunculus ficaria	Eleocharis rostellata	Decodon verticillatus	Quercus palustris	Gentiana andrewsii
Rhamnus frangula	Eriophorum viridicarinatum	Eriophorum virginicum		Helianthus grosseserratus
Typha angustifolia	Gentianopsis spp.	Larix laricina		Liatris spicata
Typha xglauca	Lobelia kalmii	Nemopanthus mucronatus		Lysimachia quadriflora
	Parnassia glauca	Schechzeria palustris		Lythrum alatum
	Potentilla fruticosa	Sphagnum spp.		Pycnanthemum virginianum
	Rhamnus alnifolia	Vaccinium macrocarpon		Silphium terebinthinaceum
	Rhynchospora capillacea	Vaccinium corymbosum		Sorghastrum nutans
	Salix candida	Vaccinium oxycoccos		Spartina pectinata
	Salix myricoides	Woodwardia virginica		Solidago riddellii
	Salix serissima	Xyris difformis		
	Solidago ohioensis			
	Tofieldia glutinosa			
	Triglochin maritimum			
	Triglochin palustre			

End of Narrative Rating. Begin Quantitative Rating on next page.

etland ID: Wetland 01		
: Innovation Station Rater(s): Jake Lubber	s	Date: 6/3/2021
		'
	Field ID:	
1.0 1.0 Metric 1. Wetland Area (size).	w-jbl-20210603-01	
pts subtotal Select one size class and assign score.		
>50 acres (>20.2ha) (6 pts) 25 to <50 acres (10.1 to <20.2ha) (5 pts)	Delineated acres:	0.27
10 to <25 acres (4 to <10.1ha) (4 pts) 3 to <10 acres (1.2 to <4ha) (3 pts)		
0.3 to <3 acres (0.12 to <1.2ha) (2pts) x 0.1 to <0.3 acres (0.04 to <0.12ha) (1 pt) <0.1 acres (0.04ha) (0 pts)	Total acres:	approx. 0.3
4.0 5.0 Metric 2. Upland buffers and surroun	ding land use.	
ts. subtotal 2a. Calculate average buffer width. Select only one and	assign score. Do not double check.	
WIDE. Buffers average 50m (164ft) or more around wetland MEDIUM. Buffers average 25m to <50m (82 to <164ft) around X NARROW. Buffers average 10m to <25m (32ft to <82ft) around very VERY NARROW. Buffers average 10m (<32ft) around very 2b. Intensity of surrounding land use. Select one or do	d perimeter (7) Ind wetland perimeter (4) Ind wetland perimeter (1) Itand perimeter (0)	
VERY LOW. 2nd growth or older forest, prairie, savannah,		
x LOW. Old field (>10 years), shrubland, young second grow MODERATELY HIGH. Residential, fenced pasture, park, or		
x HIGH. Urban, industrial, open pasture, row cropping, mining	- ' '	
6.0 11.0 Metric 3. Hydrology.		
pts. subtotal 3a. Sources of Water. Score all that apply.	3b. Connectivity. Score all that a	oply.
High pH groundwater (5)	100 year floodplain (1)	(4)
Other groundwater (3) x Precipitation (1)	Between stream/lake and other hun Part of wetland/upland (e.g. forest),	
Seasonal/Intermittent surface water (3)	Part of riparian or upland corridor (1)
Perennial surface water (lake or stream) (5) 3c. Maximum water depth. Select one.	3d. Duration inundation/saturation Semi- to permanently inundated/sat	
>0.7 (27.6in) (3)	x Regularly inundated/saturated (3)	()
0.4 to 0.7m (15.7 to 27.6in) (2) x <0.4m (<15.7in) (1)	Seasonally inundated (2) x Seasonally saturated in upper 30cm	(12in) (1)
3e. Modifications to natural hydrologic regime. Score of	ne or double check and average.	. (. 2) (.)
None or none apparent (12) Recovered (7)	Check all disturbances observed	point source (nonstormwater)
x Recovering (3)	x tile x f	illing/grading
x Recent or no recovery (1)		oad bed/RR track Iredging
		Other:
7.5 18.5 Metric 4. Habitat Alteration and Deve	anmant	
is. subtotal 4a. Substrate disturbance. Score one or double check	•	
None or none apparent (4)		
x Recovered (3) x Recovering (2)		
Recent or no recovery (1)		
4b. Habitat development. Select only one and assign se	core.	
Very good (6)		
Good (5) Moderately good (4)		
x Fair (3)		
Poor to fair (2)		
4c. Habitat alteration. Score one or double check and a	•	
None or none apparent (9) Recovered (6)	Check all disturbances observed mowing x	shrub/sapling removal
x Recovering (3)	grazing	nerbaceous/aquatic bed removal
x Recent or no recovery (1)		sedimentation dredging
	x woody debris removal f	arming
	toxic pollutants r	nutrient enrichment
40.5		
18.5		
subtotal this page ORAM v. 5.0 Field Form Quantitative Rating		

w-jbl-20210603-01 ORAM.xlsx | Quantitative Form

Wetla	and ID:	Wetland 01				_
Site:	Innovation	n Station	Rater(s):	Jake Lubbers	Date:	6/3/2021
Oito.	mnovado	- Ctation	rtator(o).	ound Eubbold	Dute.	0/0/2021
				Field ID:		
	18.5			w-jbl-20210603-	-01	
	subtotal this page					
	0.0 18.5	Metric 5. Special We	otlande			
		· ·				
max 10 pts.	subtotal	Check all that apply and Bog (10) Fen (10) Old growth forest (10) Mature forested wetland (5) Lake Erie coastal/tributary wetla Lake Plain Sand Prairies (Oak C Relict Wet Praires (10) Known occurrence state/federal Significant migratory songbird/w Category 1 Wetland. See Ques'	and-unrestricted hydrology (10 and-restricted hydrology (5) Openings) (10) I threatened or endangered s vater fowl habitat or usage (10	pecies (10)		
		<u> </u>				
,	5.0 23.5		•		• •	
max 20pts.	subtotal	6a. Wetland Vegetation 9 Score all present using 0 to 3 so			mmunity Cover Scale s <0.1ha (0.2471 acres) contiguous area	
		Aquatic bed	cale.		comprises small part of wetland's 1	
		2 Emergent			moderate quality, or comprises a	
		Shrub		significant part but is		
		Forest Mudflats			comprises significant part of wetland's 2	
		Open water		part and is of high qu	moderate quality or comprises a small	
		Other			ses significant part, or more, of wetland's 3	
		6b. horizontal (plan view) Inte	erspersion.	vegetation and is of		
		Select only one.				
		High (5)			on of Vegetation Quality	
		Moderately high(4) Moderate (3)		disturbance tolerant	nd/or predominance of nonnative or low	
		Moderately low (2)			nant component of the vegetation, mod	
		x Low (1)			and/or disturbance tolerant native spp	
		None (0)			and species diversity moderate to	
		6c. Coverage of invasive plan Table 1 ORAM long form for list		threatened or endan	t generallyw/o presence of rare	
		or deduct points for coverage	. Add		native species, with nonnative spp high	
		Extensive >75% cover (-5)			olerant native spp absent or virtually	
		Moderate 25-75% cover (-3)			p diversity and often, but not always,	
		Sparse 5-25% cover (-1)		the presence of rare	, threatened, or endangered spp	
		x Nearly absent <5% cover (0) Absent (1)		Mudflat and Open	Water Class Quality	
		6d. Microtopography.		0 Absent < 0.1ha (0.24		
		Score all present using 0 to 3 so	cale.	1 Low 0.1 to <1ha (0.2		
		Vegetated hummucks/tussucks		2 Moderate 1 to <4ha	(2.47 to 9.88 acres)	
		1 Coarse woody debris >15cm (6i		3 High 4ha (9.88 acres	s) or more	
		0 Standing dead >25cm (10in) db 1 Amphibian breeding pools	n	Microtopography C	Cover Scale	
		T VIIIbuiniau preeding boois		0 Absent	JOVE: OCAIE	
					amounts or if more common	
				of marginal quality		
		•		2 Present in moderate	amounts, but not of highest	
	23.5	TOTAL (Max 100 pts)		quality or in small an	nounts of highest quality	
	1	Category		3 Present in moderate	or greater amounts	
		•		and of highest qualit	у	

Wetland ID: Wetland 01

ORAM Summary Worksheet

		answ	cle /er or score	Result
Narrative Rating	Question 1 Critical Habitat	YES	*NO	If yes, Category 3.
	Question 2. Threatened or Endangered Species	YES	*NO	If yes, Category 3.
	Question 3. High Quality Natural Wetland	YES	*NO	If yes, Category 3.
	Question 4. Significant bird habitat	YES	*NO	If yes, Category 3.
	Question 5. Category 1 Wetlands	YES	*NO	If yes, Category 1.
	Question 6. Bogs	YES	*NO	If yes, Category 3.
	Question 7. Fens	YES	*NO	If yes, Category 3.
	Question 8a. Old Growth Forest	YES	*NO	If yes, Category 3.
	Question 8b. Mature Forested Wetland	YES	*NO	If yes, evaluate for Category 3; may also be 1 or 2.
	Question 9b. Lake Erie Wetlands - Restricted	YES	*NO	If yes, evaluate for Category 3; may also be 1 or 2.
	Question 9d. Lake Erie Wetlands – Unrestricted with native plants	YES	*NO	If yes, Category 3
	Question 9e. Lake Erie Wetlands - Unrestricted with invasive plants	YES	*NO	If yes, evaluate for Category 3; may also be 1 or 2.
	Question 10. Oak Openings	YES	*NO	If yes, Category 3
	Question 11. Relict Wet Prairies	YES	*NO	If yes, evaluate for Category 3; may also be 1 or 2.
Quantitative Rating	Metric 1. Size		1	
	Metric 2. Buffers and surrounding land use	4	4	
	Metric 3. Hydrology	(6	
	Metric 4. Habitat	7	.5	
	Metric 5. Special Wetland Communities	(0	
	Metric 6. Plant communities, interspersion, microtopography	:	5	
	TOTAL SCORE	23	3.5	Category based on score breakpoints

Complete Wetland Categorization Worksheet.

Wetland ID: Wetland 01

Wetland Categorization Worksheet

Choices	Circle one		Evaluation of Categorization Result of ORAM
Did you answer "Yes" to any of the following questions: Narrative Rating Nos. 2, 3, 4, 6, 7, 8a, 9d, 10	YES Wetland is categorized as a Category 3 wetland	*NO	Is quantitative rating score <i>less</i> than the Category 2 scoring threshold (excluding gray zone)? If yes, reevaluate the category of the wetland using the narrative criteria in OAC Rule 3745-1-54(C) and biological and/or functional assessments to determine if the wetland has been over- categorized by the ORAM
Did you answer "Yes" to any of the following questions: Narrative Rating Nos. 1, 8b, 9b, 9e, 11	YES Wetland should be evaluated for possible Category 3 status	*NO	Evaluate the wetland using the 1) narrative criteria in OAC Rule 3745-1-54(C) and 2) the quantitative rating score. If the wetland is determined to be a Category 3 wetland using either of these, it should be categorized as a Category 3 wetland. Detailed biological and/or functional assessments may also be used to determine the wetland's category.
Did you answer "Yes" to Narrative Rating No. 5	YES Wetland is categorized as a Category 1 wetland	*NO	Is quantitative rating score <i>greater</i> than the Category 2 scoring threshold <i>(including</i> any gray zone)? If yes, reevaluate the category of the wetland using the narrative criteria in OAC Rule 3745-1-54(C) and biological and/or functional assessments to determine if the wetland has been under-categorized by the ORAM
Does the quantitative score fall within the scoring range of a Category 1, 2, or 3 wetland?	*YES Wetland is assigned to the appropriate category based on the scoring range	NO	If the score of the wetland is located within the scoring range for a particular category, the wetland should be assigned to that category. In all instances however, the narrative criteria described in OAC Rule 3745-1-54(C) can be used to clarify or change a categorization based on a quantitative score.
Does the quantitative score fall with the "gray zone" for Category 1 or 2 or Category 2 or 3 wetlands?	YES Wetland is assigned to the higher of the two categories or assigned to a category based on detailed assessments and the narrative criteria	*NO	Rater has the option of assigning the wetland to the higher of the two categories or to assign a category based on the results of a nonrapid wetland assessment method, e.g. functional assessment, biological assessment, etc, and a consideration of the narrative criteria in OAC rule 3745-1-54(C).
Does the wetland otherwise exhibit moderate OR superior hydrologic OR habitat, OR recreational functions AND the wetland was not categorized as a Category 2 wetland (in the case of moderate functions) or a Category 3 wetland (in the case of superior functions) by this method?	YES Wetland was undercategorized by this method. A written justification for recategorization should be provided on Background Information Form	*NO Wetland is assigned to category as determined by the ORAM.	A wetland may be undercategorized using this method, but still exhibit one or more superior functions, e.g. a wetland's biotic communities may be degraded by human activities, but the wetland may still exhibit superior hydrologic functions because of its type, landscape position, size, local or regional significance, etc. In this circumstance, the narrative criteria in OAC Rule 3745-1-54(C)(2) and (3) are controlling, and the under-categorization should be corrected. A written justification with supporting reasons or information for this determination should be provided.
		Final Category	!

AECOM

PHOTOGRAPHIC RECORD

WETLAND 01

Client Name:

Site Location:

Project No.

AEP

Innovation 138kV Station Project

60660544

Wetland 01

Date:


June 3, 2021

Description:

PEM

Category 1

Facing North



Wetland 01

Date:

June 3, 2021

Description:

PEM

Category 1

Facing East



AECOM

PHOTOGRAPHIC RECORD

WETLAND 01

Client Name:

Site Location:

Project No.

AEP

Innovation 138kV Station Project

60660544

Wetland 01

Date:

June 3, 2021

Description:

PEM

Category 1

Facing South



Wetland 01

Date:

June 3, 2021

Description:

PEM

Category 1

Facing West



A	-	-	AA	
4			M	

WETLAND 01

Client Name: Site Location: Project No.

AEP Innovation 138kV Station Project 60660544

Wetland 01

Date:

June 3, 2021

Description:

PEM

Category 1

Soil Pit



WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Innovation Station Project		City/Cou	nty: Licking	County Sampling Date: 06/03/202
Applicant/Owner: AEP				State: OH Sampling Point: W-JBL-20210603
Investigator(s): JBL, SKM		Section, T	ownship, Rai	nge: Q / T2N / R15W
Landform (hillside, terrace, etc.): depression		l	_ocal relief (c	concave, convex, none): concave
Slope (%):1_ Lat: 40.09342		Long:	82.72878	Datum: NAD 83
Soil Map Unit Name: Pe - Pewamo silty clay loam, low	carbonate t	ill, 0 to 2 perce	nt slopes	NWI classification: N/A
Are climatic / hydrologic conditions on the site typical fo	or this time o	of year?	Yes	No x (If no, explain in Remarks.)
Are Vegetation , Soil , or Hydrology	significantly		·	Circumstances" present? Yes x No
Are Vegetation, Soil, or Hydrology	naturally pro	blematic? (I	f needed, ex	plain any answers in Remarks.)
			g point lo	cations, transects, important features, etc.
Hydrophytic Vegetation Present? Yes X No)	Is the	Sampled Ar	rea
	<u> </u>	l l	n a Wetland?	
	<u> </u>			<u> </u>
Remarks: Depressional area W-JBL-20210603-02. Wetland ext which appear to have a hydrological connection to UN VEGETATION – Use scientific names of pla	IT to South F			e NWI wetlands,
·	Absolute	Dominant	Indicator	
<u>Tree Stratum</u> (Plot size: <u>30' radius</u>)	% Cover	Species?	Status	Dominance Test worksheet:
1				Number of Dominant Species That Are OBL, FACW, or FAC: 2 (A)
2				(/
4				Total Number of Dominant Species Across All Strata: 2 (B)
5.				Percent of Dominant Species That
		=Total Cover		Are OBL, FACW, or FAC:100.0%_ (A/B
Sapling/Shrub Stratum (Plot size: 15' radius				
1. Fraxinus pennsylvanica	10	Yes	FACW	Prevalence Index worksheet:
2				Total % Cover of: Multiply by:
3				OBL species85 x 1 =85
4				FACW species 35 x 2 = 70
5				FAC species 0 x 3 = 0
Herb Stratum (Plot size: 5' radius)	10	=Total Cover		FACU species 0 x 4 = 0 UPL species 0 x 5 = 0
Herb Stratum (Plot size: 5' radius) 1. Juncus effusus	70	Yes	OBL	UPL species 0 x 5 = 0 Column Totals: 120 (A) 155 (B)
Typha X glauca	15	No	OBL	Prevalence Index = B/A = 1.29
3. Persicaria pensylvanica	10	No	FACW	1.25
Lysimachia nummularia	10	No	FACW	Hydrophytic Vegetation Indicators:
5. Packera glabella	5	No	FACW	1 - Rapid Test for Hydrophytic Vegetation
6.				X 2 - Dominance Test is >50%
7.				X 3 - Prevalence Index is ≤3.0 ¹
8.				4 - Morphological Adaptations ¹ (Provide supportir
9				data in Remarks or on a separate sheet)
10				Problematic Hydrophytic Vegetation ¹ (Explain)
	110	=Total Cover		¹ Indicators of hydric soil and wetland hydrology must
Woody Vine Stratum (Plot size: 30' radius)			be present, unless disturbed or problematic.
1.				Hydrophytic
2		-Total Carra		Vegetation
		=Total Cover		Present?
Remarks: (Include photo numbers here or on a separal Hydrophytic Vegetation present, dominance test >50%	,	e index is <3.0	%. Dominant	species OBL, FACW

SOIL Sampling Point: IBL-20210603

Profile Desc	ription: (Describe	to the dept	h needed to doc	ument th	ne indica	ator or c	onfirm the absence o	f indicators.)
Depth	Matrix		Redo	x Featur	es			
(inches)	Color (moist)		Color (moist)	%	Type ¹	Loc ²	Texture	Remarks
0-4	10YR 2/2	98	10YR 4/4	2	C	PL/M	Loamy/Clayey	Distinct redox concentrations
4-17	10YR 3/1	90	10YR 4/4	10	С	М	Loamy/Clayey	Distinct redox concentrations
¹ Type: C=Co	oncentration, D=De	pletion, RM=	Reduced Matrix, I	MS=Masl	ked Sand	d Grains	. ² Location:	PL=Pore Lining, M=Matrix.
Hydric Soil I	Indicators:						Indicators	s for Problematic Hydric Soils ³ :
Histosol	(A1)		Sandy Gle	yed Mati	rix (S4)		? Coast	Prairie Redox (A16)
Histic Ep	ipedon (A2)		Sandy Re	dox (S5)			Iron-N	Manganese Masses (F12)
Black His	stic (A3)		Stripped N	/latrix (S6	5)		Red F	Parent Material (F21)
Hydroger	n Sulfide (A4)		Dark Surfa	ace (S7)			Very S	Shallow Dark Surface (F22)
Stratified	Layers (A5)		Loamy Mu	icky Mine	eral (F1)		Other	(Explain in Remarks)
2 cm Mu	ck (A10)		Loamy Gl	eyed Mat	rix (F2)			
Depleted	Below Dark Surfac	e (A11)	Depleted I	Matrix (F	3)			
Thick Da	rk Surface (A12)		X Redox Da	rk Surfac	e (F6)		³ Indicators	s of hydrophytic vegetation and
Sandy M	ucky Mineral (S1)		Depleted I	Dark Sur	face (F7))	wetlar	nd hydrology must be present,
5 cm Mu	cky Peat or Peat (S	3)	? Redox De	pressions	s (F8)		unless	s disturbed or problematic.
Restrictive L	_ayer (if observed)	:						
Type:								
Depth (in	nches):						Hydric Soil Present	? Yes X No
Remarks:			<u> </u>					
	m is revised from M	lidwest Regio	onal Supplement	Version 2	2.0 to incl	lude the	NRCS Field Indicators	of Hydric Soils in the United States,
	2018. (https://www.							•
Hydric soil in	dicators present, di	stinct redox	concentrations					
HYDROLO	GY							
	drology Indicators							
1	cators (minimum of		ed: check all that	annly)			Secondar	y Indicators (minimum of two required
	Water (A1)	one is requir	Water-Sta		ves (R9)			ce Soil Cracks (B6)
	ter Table (A2)		Aquatic Fa					age Patterns (B10)
x Saturatio			True Aqua	•	-			eason Water Table (C2)
Water Ma	` '		Hydrogen)		sh Burrows (C8)
	t Deposits (B2)		x Oxidized F		• •	•		ation Visible on Aerial Imagery (C9)
	osits (B3)		Presence			_	· · ·	ed or Stressed Plants (D1)
	t or Crust (B4)		Recent Iro		`	. ,		norphic Position (D2)
_	osits (B5)		Thin Muck					Neutral Test (D5)
·	on Visible on Aerial	Imagery (B7			` '			(- /
	Vegetated Concav							
Field Observ		•	<u> </u>		,			
Surface Water		es	No x	Depth (i	nches).			
Water Table		es ——	No x	Depth (i	· -			
Saturation Pr		es x	No X	Depth (i	-	14	Wetland Hydrolog	y Present? Yes X No
(includes cap				(_			
	corded Data (strear	n gauge. mo	nitoring well. aeria	al photos.	previous	s inspec	tions), if available:	
	(2 53	5 5-,	J,	,		.	,,	
Remarks:								
Saturation pr	resent at 14 inches,	wetland hyd	rology present, co	nnectivit	y with an	offsite l	NWI	
HS Army Corr	os of Engineers							Midwest Region Version
	esent at 14 inches,	wetland hyd	rology present, co	onnectivit	y with an	offsite l	NWI	
US Army Corp	os of Engineers							Midwest Region Version

	Ohio Rapid Assessment Method for Wetlands 10 Page Form for Wetland Categorization			
Version 5.0	Background Information Scoring Boundary Worksheet Narrative Rating Field Form Quantitative Rating ORAM Summary Worksheet Wetland Categorization Worksheet	Ohio EPA, Division of Surface Water Final: February 1, 2001		

Instructions

The investigator is *STRONGLY URGED* to read the Manual for Using the Ohio Rapid Assessment Method for Wetlands for further elaboration and discussion of the questions below prior to using the rating forms.

The Narrative Rating is designed to categorize a wetland or to provide alerts to the Rater based on the presence or possible presence of threatened or endangered species. The presence or proximity of such species is often an indicator of the quality and lack of disturbance of the wetland being evaluated. In addition, it is designed to categorize certain wetlands as presence or possible presence of threatened or endangered species. The presence or proximity of such species is often an indicator of the quality and lack of disturbance of the wetland being evaluated. In addition, it is designed to categorize certain wetlands as very low quality (Category 1) or very high quality (Category 3) regardless of the wetland's score on the Quantitative Rating. In addition, the Narrative Rating also alerts the investigator that a particular wetland may be a Category 3 wetland, again, regardless of the wetland's score on the Quantitative Rating.

It is *VERY IMPORTANT* to properly and thoroughly answer each of the questions in the ORAM in order to properly categorize a wetland. To properly answer all the questions, the boundaries of the wetland being assessed must be correctly identified. Refer to Scoring Boundary worksheet and the User's Manual for a discussion of how to determine the "scoring boundaries." In some instances, the scoring boundaries may differ from the "jurisdictional boundaries."

Refer to the most recent ORAM Score Calibration Report for the scoring breakpoints between wetland categories. The most recent version of this document is posted on Ohio EPA's Division of Surface Water web page at: http://www.epa.ohio.gov/dsw/wetlands/WetlandEcologySection.aspx

Background Information			
Name:	Jake Lubbers		
Date:	6/03/2020		
Affiliation:	AECOM		
Address:	525 Vine Street, Suite 1800, Cincinnati, Ohio 45202		
Phone Number:	513-419-3506		
e-mail address:	jake.lubbers@aecom.com		
Name of Wetland:	Wetland 02		
Vegetation Communit(ies):	РЕМ		
HGM Class(es):	Depressional		
Location of Wetland: include map	, address, north arrow, landmarks, distances, roads, etc.		

See Figures 1, 2, and 3 of Wetland Delineation and Stream Assessment Report.

Lat/Long or UTM Coordinate:	40.09342, -82.72878
USGS Quad Name:	Jersey
County:	Licking County
Township:	T2N
Section and Subsection:	Q
Hydrologic Unit Code:	50400060402
Site Visit:	
National Wetland Inventory Map:	See Figure 2
Ohio Wetland Inventory Map:	N/A
Soil Survey:	See Figure 2
Delineation report/map:	See Figure 3

Name of Wetland:	Wetland			
Wetland Size (delineated acres):	0.44	Wetland Size (Estimated total acres):	Approx. 2.69	
Sketch: Include north arrow, relationshi	p with other surface waters, vegetation	on zones, etc.		
Comments, Narrative Discussion, Justif	fication of Category Changes:			
Field Wetland Point W-JBL-2021				
tiple NWI wetlands, which appea	ar to have a hydrological conn	ection to UNT to South Fork I	icking River.	
		1		
Final score:	27.5	Category:	1	

Wetland ID: V	Wetland
---------------	---------

Scoring Boundary Worksheet

INSTRUCTIONS. The initial step in completing the ORAM is to identify the "scoring boundaries" of the wetland being rated. In many instances this determination will be relatively easy and the scoring boundaries will coincide with the "jurisdictional boundaries." For example, the scoring boundary of an isolated cattail marsh located in the middle of a farm field will likely be the same as that wetland's jurisdictional boundaries. In other instances, however, the scoring boundary will not be as easily determined. Wetlands that are small or isolated from other surface waters often form large contiguous areas or heterogeneous complexes of wetland and upland. In separating wetlands for scoring purposes, the hydrologic regime of the wetland is the main criterion that should be used. Boundaries between contiguous or connected wetlands should be established where the volume, flow, or velocity of water moving through the wetland changes significantly. Areas with a high degree of hydrologic interaction should be scored as a single wetland. In determining a wetland's scoring boundaries, use the guidelines in the ORAM Manual Section 5.0. In certain instances, it may be difficult to establish the scoring boundary for the wetland being rated. These problem situations include wetlands that form a patchwork on the landscape, wetlands divided by artificial boundaries like property fences, roads, or railroad embankments, wetlands that are contiguous with streams, lakes, or rivers, and estuarine or coastal wetlands. These situations are discussed below, however, it is recommended that Rater contact Ohio EPA, Division of Surface Water, 401/Wetlands Section if there are additional questions or a need for further clarification of the appropriate scoring boundaries of a particular wetland.

#	Steps in properly establishing scoring boundaries	done?	not applicable
Step 1	Identify the wetland area of interest. This may be the site of a		
	proposed impact, a reference site, conservation site, etc.		
		X	
Ot 0	Identify the locations where there is physical evidence that		
Step 2	hydrology changes rapidly. Such evidence includes both		
	natural and human- induced changes including, constrictions		
	caused by berms or dikes, points where the water velocity		
	changes rapidly at rapids or falls, points where significant		
	inflows occur at the confluence of rivers, or other factors that		
	may restrict hydrologic interaction between the wetlands or	X	
	parts of a single wetland.		
	parte of a onigio wonaria.		
Step 3	Delineate the boundary of the wetland to be rated such that all		
	areas of interest that are contiguous to and within the areas		
	where the hydrology does not change significantly, i.e. areas		
	that have a high degree of hydrologic interaction are included		
	within the scoring boundary.	^	
Step 4	Determine if artificial boundaries, such as property lines, state		
Clop 4	lines, roads, railroad embankments, etc., are present. These		
	should not be used to establish scoring boundaries unless they		
	coincide with areas where the hydrologic regime changes.		
	gg	X	
Ston E	In all instances, the Poter may enlarge the minimum accessor		
Step 5	In all instances, the Rater may enlarge the minimum scoring boundaries discussed here to score together wetlands that		
	could be scored separately.		
	Could be scored separatery.		X
Step 6	Consult ORAM Manual Section 5.0 for how to establish scoring		
	boundaries for wetlands that form a patchwork on the		
	landscape, divided by artificial boundaries, contiguous to		
	streams, lakes or rivers, or for dual classifications.		
			^
		ļ	

End of Scoring Boundary Determination. Begin Narrative Rating on next page.

Narrative Rating

INSTRUCTIONS. Answer each of the following questions. Questions 1, 2, 3 and 4 should be answered based on information obtained from the site visit or the literature and by submitting a Data Services Request to the Ohio Department of Natural Resources, Division of Natural Areas and Preserves, Natural Heritage Data Services, 1889 Fountain Square Court, Building F-1, Columbus, Ohio 43224, 614-265-6453 (phone), 614-265-3096 (fax), http://www.dnr.state.oh.us/dnap. The remaining questions are designed to be answered primarily by the results of the site visit. Refer to the User's Manual for descriptions of these wetland types. Note: "Critical habitat" is legally defined in the Endangered Species Act and is the geographic area containing physical or biological features essential to the conservation of a listed species or as an area that may require special management considerations or protection. The Rater should contact the Region 3 Headquarters or the Columbus Ecological Services Office for updates as to whether critical habitat has been designated for other federally listed threatened or endangered species. "Documented" means the wetland is listed in the appropriate State of Ohio database.

#	Question	Circle one	
1	Critical Habitat. Is the wetland in a township, section, or subsection of a	YES	*NO
	United States Geological Survey 7.5 minute Quadrangle that has been designated by the U.S. Fish and Wildlife Service as "critical habitat" for any threatened or endangered plant or animal species? Note: as of January 1, 2001, of the federally listed endangered or threatened species which can be found in Ohio, the Indiana Bat has had critical habitat designated (50 CFR 17.95(a)) and the piping plover has had critical habitat proposed (65 FR 41812 July 6, 2000).	Wetland should be evaluated for possible Category 3 status Go to Question 2	Go to Question 2
_	Threatened or Endangered Species. Is the wetland known to contain an individual of,	YES	*NO
	or documented occurrences of federal or state-listed threatened or endangered plant or animal species?	Wetland is a Category 3 wetland. Go to Question 3	Go to Question 3
3	Documented High Quality Wetland. Is the wetland on record in Natural Heritage	YES	*NO
	Database as a high quality wetland?	Wetland is a Category 3 wetland Go to Question 4	Go to Question 4
4	Significant Breeding or Concentration Area. Does the wetland contain documented	YES	*NO
	regionally significant breeding or nonbreeding waterfowl, neotropical songbird, or shorebird concentration areas?	Wetland is a Category 3 wetland Go to Question 5	Go to Question 5
5	Category 1 Wetlands. Is the wetland less than 0.5 hectares (1 acre) in size and	YES	*NO
	hydrologically isolated and either 1) comprised of vegetation that is dominated (greater than eighty per cent areal cover) by <i>Phalaris arundinacea, Lythrum salicaria,</i> or <i>Phragmites australis</i> , or 2) an acidic pond created or excavated on mined lands that has little or no vegetation?	Wetland is a Category 1 wetland Go to Question 6	Go to Question 6
~	Bogs. Is the wetland a peat-accumulating wetland that 1) has no significant inflows or	YES	*NO
	outflows, 2) supports acidophilic mosses, particularly <i>Sphagnum</i> spp., 3) the acidophilic mosses have >30% cover, 4) at least one species from Table 1 is present, and 5) the cover of invasive species (see Table 1) is <25%?	Wetland is a Category 3 wetland Go to Question 7	Go to Question 7
	Fens. Is the wetland a carbon accumulating (peat, muck) wetland that is saturated	YES	*NO
	during most of the year, primarily by a discharge of free flowing, mineral rich, ground water with a circumneutral ph (5.5-9.0) and with one or more plant species listed in Table 1 and the cover of invasive species listed in Table 1 is <25%?	Wetland is a Category 3 wetland Go to Question 8a	Go to Question 8a
	"Old Growth Forest." Is the wetland a forested wetland and is the forest characterized	YES	*NO
	by, but not limited to, the following characteristics: overstory canopy trees of great age (exceeding at least 50% of a projected maximum attainable age for a species); little or no evidence of human-caused understory disturbance during the past 80 to 100 years; an allaged structure and multilayered canopies; aggregations of canopy trees interspersed with canopy gaps; and significant numbers of standing dead snags and downed logs?	Wetland is a Category 3 wetland. Go to Question 8b	Go to Question 8b

01:	Material Secretaria and a lateral and a lateral and a lateral secretaria	T	
8b	Mature forested wetlands . Is the wetland a forested wetland with 50% or more of the cover of upper forest canopy consisting of deciduous trees with large diameters at breast height (dbh), generally diameters greater than 45cm (17.7in) dbh?	YES Wetland should be evaluated for possible Category 3 status. Go to Question 9a	*NO Go to Question 9a
9a	Lake Erie coastal and tributary wetlands. Is the wetland located at an elevation less	YES	*NO
	than 575 feet on the USGS map, adjacent to this elevation, or along a tributary to Lake Erie that is accessible to fish?	Go to Question 9b	Go to Question 10
9b	Does the wetland's hydrology result from measures designed to prevent erosion and the loss of aquatic plants, i.e. the wetland is partially hydrologically restricted from Lake Erie due to lakeward or landward dikes or other hydrological controls?	YES Wetland should be evaluated for possible Category 3 status Go to Question 10	*NO Go to Question 9c
9с	Are Lake Erie water levels the wetland's primary hydrological influence,	YES	*NO
	i.e. the wetland is hydrologically unrestricted (no lakeward or upland border alterations), or the wetland can be characterized as an "estuarine" wetland with lake and river influenced hydrology. These include sandbar deposition wetlands, estuarine wetlands, river mouth wetlands, or those dominated by submersed aquatic vegetation.		Go to Question 10
9d	Does the wetland have a predominance of native species within its vegetation	YES	*NO
	communities, although non-native or disturbance tolerant native species can also be present?	Wetland is a Category 3 wetland Go to Question 10	Go to Question 9e
9e	Does the wetland have a predominance of non-native or disturbance tolerant native plant	YES	*NO
	species within its vegetation communities?	Wetland should be evaluated for possible Category 3 status Go to Question 10	Go to Question 10
10	Lake Plain Sand Prairies (Oak Openings) Is the wetland located in Lucas, Fulton,	YES	*NO
	Henry, or Wood Counties and can the wetland be characterized by the following description: the wetland has a sandy substrate with interspersed organic matter, a water table often within several inches of the surface, and often with a dominance of the gramineous vegetation listed in Table 1 (woody species may also be present). The Ohio Department of Natural Resources Division of Natural Areas and Preserves can provide assistance in confirming this type of wetland and its quality.	Wetland is a Category 3 wetland. Go to Question 11	Go to Question 11
1		YES	*NO
11	Relict Wet Prairies. Is the wetland a relict wet prairie community dominated by some or		110
11	Relict Wet Prairies. Is the wetland a relict wet prairie community dominated by some or all of the species in Table 1. Extensive prairies were formerly located in the Darby Plains (Madison and Union Counties), Sandusky Plains (Wyandot, Crawford, and Marion Counties), northwest Ohio (e.g. Erie, Huron, Lucas, Wood Counties), and portions of western Ohio Counties (e.g. Darke, Mercer, Miami, Montgomery, Van Wert etc.).	Wetland should be evaluated for possible Category 3 status Complete Quantitative Rating	Complete Quantitative Rating

invasive/exotic spp	fen species	bog species	oak opening species	wet prairie species
Lythrum salicaria	Zygadenus elegans var. glaucus	Calla palustris	Carex cryptolepis	Calamagrostis canadensis
Myriophyllum spicatum	Cacalia plantaginea	Carex atlantica var. capillacea	Carex lasiocarpa	Calamogrostis stricta
Najas minor	Carex flava	Carex echinata	Carex stricta	Carex atherodes
Phalaris arundinacea	Carex sterilis	Carex oligosperma	Cladium mariscoides	Carex buxbaumii
Phragmites australis	Carex stricta	Carex trisperma	Calamagrostis stricta	Carex pellita
Potamogeton crispus	Deschampsia caespitosa	Chamaedaphne calyculata	Calamagrostis canadensis	Carex sartwellii
Ranunculus ficaria	Eleocharis rostellata	Decodon verticillatus	Quercus palustris	Gentiana andrewsii
Rhamnus frangula	Eriophorum viridicarinatum	Eriophorum virginicum		Helianthus grosseserratus
Typha angustifolia	Gentianopsis spp.	Larix laricina		Liatris spicata
Typha xglauca	Lobelia kalmii	Nemopanthus mucronatus		Lysimachia quadriflora
	Parnassia glauca	Schechzeria palustris		Lythrum alatum
	Potentilla fruticosa	Sphagnum spp.		Pycnanthemum virginianum
	Rhamnus alnifolia	Vaccinium macrocarpon		Silphium terebinthinaceum
	Rhynchospora capillacea	Vaccinium corymbosum		Sorghastrum nutans
	Salix candida	Vaccinium oxycoccos		Spartina pectinata
	Salix myricoides	Woodwardia virginica		Solidago riddellii
	Salix serissima	Xyris difformis		
	Solidago ohioensis			
	Tofieldia glutinosa			
	Triglochin maritimum			
	Triglochin palustre			

End of Narrative Rating. Begin Quantitative Rating on next page.

/etland ID: Wetland				
e: Innovation Station	Rater(s): Jake Lu	ubbers	Date: 6/03/20	020
		Field ID:		
2.0 2.0 Metric 1. We	tland Area (size).	w-jbl-20210603-01		
	• •	W-JSI-20210000-01		
pts subtotal Select one size cla >50 acres (>20.2ha	ss and assign score.			
	.1 to <20.2ha) (5 pts)	Delineated acres:	0.44	
10 to <25 acres (4 to 3 to <10 acres (1.2 to			0.44	
x 0.3 to <3 acres (0.12		Total acres:	Approx. 2.69	
0.1 to <0.3 acres (0. <0.1 acres (0.04ha)	.04 to <0.12ha) (1 pt)			
	(U pis)			
10.0 12.0 Metric 2. Upl	and buffers and surr	ounding land use.		
<u> </u>		ne and assign score. Do not double check		
	age 50m (164ft) or more around w			
MEDIUM. Buffers av	verage 25m to <50m (82 to <164f	t) around wetland perimeter (4)		
	average 10m to <25m (32ft to <82 uffers average <10m (<32ft) arou			
	rounding land use. Select one	, , ,		
—	owth or older forest, prairie, savar	. ,		
	years), shrubland, young second	d growth forest. (5) ark, conservation tillage, new fallow field. (3)		
 	trial, open pasture, row cropping,			
ш .		. ,		
8.5 20.5 Metric 3. Hyd	drology.			
ts. subtotal 3a. Sources of Wat	ter. Score all that apply.	3b. Connectivity. Score al	I that apply.	
High pH groundwate	er (5)	100 year floodplain (1)		
Other groundwater ((3)	Between stream/lake and o x Part of wetland/upland (e.g.		
x_ Precipitation (1) Seasonal/Intermitter	nt surface water (3)	Part of wetland/upland (e.g.		
Perennial surface w	ater (lake or stream) (5)	3d. Duration inundation/s	aturation. Score one or dbl check.	
3c. Maximum wate >0.7 (27.6in) (3)	r depth. Select one.	Semi- to permanently inund x Regularly inundated/saturat		
0.4 to 0.7m (15.7 to	27.6in) (2)	x Seasonally inundated (2)	• •	
x<0.4m (<15.7in) (1)	o natural hydrologic rogimo. S	Seasonally saturated in upp core one or double check and average.	er 30cm (12in) (1)	
None or none appar		Check all disturbances of	served	
Recovered (7)		x ditch	point source (nonstormwater)	
x Recovering (3) Recent or no recove	erv (1)	x tile dike	x filling/grading road bed/RR track	
	,	weir	dredging	
		stormwater input	Other:	
6.0 26.5 Metric 4. Hat	oitat Alteration and D	evelopment.		
	ırbance. Score one or double c	•		
None or none appar	ent (4)	-		
Recovered (3) x Recovering (2)				
Recent or no recove				
	oment. Select only one and ass	sign score.		
Excellent (7) Very good (6)				
Good (5)				
Moderately good (4) Fair (3)	i			
x Poor to fair (2)				
Poor (1)	on Score one or devible at!-	and average		
None or none appar	on. Score one or double check rent (9)	and average. Check all disturbances obse	erved_	
Recovered (6)	• /	mowing	x shrub/sapling removal	,
x Recovering (3) x Recent or no recove	erv (1)	grazing x clearcutting	herbaceous/aquatic bed remove sedimentation	val
- x Indeedit of 110 tecove	"" (' /	x selective cutting	x dredging	
		x woody debris removal	x farming	
		toxic pollutants	nutrient enrichment	
26.5				
	Form Quantitative Rating			

w-jbl-20210603-02 ORAM.xlsx | Quantitative Form

Wetla	and ID:	Wetland					
Site:	Innovation	Station	Rater(s):	Jake Lubbers	,	Date:	6/03/2020
Oite.	IIIIOVALIOI	1 Otation	rtater(s).	Jake Lubbers	•	Date.	0/03/2020
				Field ID	٠.		
	26.5				210603-01		
	subtotal this page			1. ,5: 202	-10000 01		
	subtotal tris page						
	0.0 26.5	Metric 5. Special We	tlands.				
max 10 pts.	subtotal	Check all that apply and	d score as indicated.				
		Bog (10)					
		Fen (10) Old growth forest (10)					
		Mature forested wetland (5)					
		Lake Erie coastal/tributary wetla	nd-unrestricted hydrology (10))			
		Lake Erie coastal/tributary wetla Lake Plain Sand Prairies (Oak C					
		Relict Wet Prairies (10)	ppenings) (10)				
		Known occurrence state/federal	threatened or endangered sp	pecies (10)			
		Significant migratory songbird/w					
		Category 1 Wetland. See Quest	ion 5 Qualitative Rating (-10)				
	1.0 27.5	Metric 6. Plant comr	nunities. intersper	sion. microto	ppography.		
max 20pts.	subtotal	6a. Wetland Vegetation (•		ion Community C	Cover Scale	
	_	Score all present using 0 to 3 so				71 acres) contiguous area	
		Aquatic bed			d either comprises sma		
		2 Emergent Shrub			and is of moderate qua part but is of low quality		
		Forest				nificant part of wetland's 2	
		Mudflats				lity or comprises a small	
		Open water Other			of high quality	part, or more, of wetland's 3	
		6b. horizontal (plan view) Inte	rspersion.		and is of high quality	part, or more, or welland's 3	
		Select only one.	•	-			
		High (5)			Description of Vegeta		
		Moderately high(4) Moderate (3)			versity and/or predomir e tolerant native specie	nance of nonnative or low	
		Moderately low (2)				ent of the vegetation, mod	
		x Low (1)				ance tolerant native spp	
		None (0) 6c. Coverage of invasive plant	te Dofor		e present, and species high, but generallyw/o		
		Table 1 ORAM long form for list.			or endangered spp to	presence or rare	
		or deduct points for coverage		A predomin	nance of native species	, with nonnative spp high	
		Extensive >75% cover (-5)			urbance tolerant native		
		x Moderate 25-75% cover (-3) Sparse 5-25% cover (-1)			d high spp diversity and se of rare, threatened,		
		Nearly absent <5% cover (0)		and product	oo or rare, ameatories,	or origanigorou opp	
		Absent (1)			d Open Water Class	Quality	
		6d. Microtopography. Score all present using 0 to 3 so	nalo.		1ha (0.247 acres) <1ha (0.247 to 2.47 ac	rool	
		Vegetated hummucks/tussucks	ale.		to <4ha (2.47 to 9.88 a		
		0 Coarse woody debris >15cm (6i			9.88 acres) or more		
		O Standing dead >25cm (10in) dbl	ı	5.0° · · · · ·	b O O		
		1 Amphibian breeding pools		Microtopog 0 Absent	graphy Cover Scale		
					ry small amounts or if n	nore common	
				of marginal	quality		
	a= -1	TOTAL (11		2 Present in r	moderate amounts, but	not of highest	
	27.5	TOTAL (Max 100 pts)		quality or in	small amounts of high	est quality	
	1	Category		3 Present in r	moderate or greater an	nounts	
				and of highe	est quality		

ORAM Summary Worksheet

		Circle answer or insert score		Result
Narrative Rating	Question 1 Critical Habitat	YES	*NO	If yes, Category 3.
	Question 2. Threatened or Endangered Species	YES	*NO	If yes, Category 3.
	Question 3. High Quality Natural Wetland	YES	*NO	If yes, Category 3.
	Question 4. Significant bird habitat	YES	*NO	If yes, Category 3.
	Question 5. Category 1 Wetlands	YES	*NO	If yes, Category 1.
	Question 6. Bogs	YES	*NO	If yes, Category 3.
	Question 7. Fens	YES	*NO	If yes, Category 3.
	Question 8a. Old Growth Forest	YES	*NO	If yes, Category 3.
	Question 8b. Mature Forested Wetland	YES	*NO	If yes, evaluate for Category 3; may also be 1 or 2.
	Question 9b. Lake Erie Wetlands - Restricted	YES	*NO	If yes, evaluate for Category 3; may also be 1 or 2.
	Question 9d. Lake Erie Wetlands – Unrestricted with native plants	YES	*NO	If yes, Category 3
	Question 9e. Lake Erie Wetlands - Unrestricted with invasive plants	YES	*NO	If yes, evaluate for Category 3; may also be 1 or 2.
	Question 10. Oak Openings	YES	*NO	If yes, Category 3
	Question 11. Relict Wet Prairies	YES	*NO	If yes, evaluate for Category 3; may also be 1 or 2.
Quantitative Rating	Metric 1. Size	2	2	
	Metric 2. Buffers and surrounding land use	1	0	
	Metric 3. Hydrology	8	.5	
	Metric 4. Habitat		6	
	Metric 5. Special Wetland Communities		0	
	Metric 6. Plant communities, interspersion, microtopography	1	1	
	TOTAL SCORE	27	7.5	Category based on score breakpoints

Complete Wetland Categorization Worksheet.

Watland ID.	Motlend
Wetland ID:	Wetland

Wetland Categorization Worksheet

Choices	Circle one		Evaluation of Categorization Result of ORAM					
Did you answer "Yes" to any of the following questions: Narrative Rating Nos. 2, 3, 4, 6, 7, 8a, 9d, 10	YES Wetland is categorized as a Category 3 wetland	*NO	Is quantitative rating score <i>less</i> than the Category 2 scoring threshold (excluding gray zone)? If yes, reevaluate the category of the wetland using the narrative criteria in OAC Rule 3745-1-54(C) and biological and/or functional assessments to determine if the wetland has been over- categorized by the ORAM					
Did you answer "Yes" to any of the following questions: Narrative Rating Nos. 1, 8b, 9b, 9e, 11	YES Wetland should be evaluated for possible Category 3 status	*NO	Evaluate the wetland using the 1) narrative criteria in OAC Rule 3745–1-54(C) and 2) the quantitative rating score. If the wetland is determined to be a Category 3 wetland using either of these, it should be categorized as a Category 3 wetland. Detailed biological and/or functional assessments may also be used to determine the wetland's category.					
Did you answer "Yes" to Narrative Rating No. 5	YES Wetland is categorized as a Category 1 wetland	*NO	Is quantitative rating score <i>greater</i> than the Category 2 scoring threshold <i>(including</i> any gray zone)? If yes, reevaluate the category of the wetland using the narrative criteria in OAC Rule 3745-1-54(C) and biological and/or functional assessments to determine if the wetland has been under-categorized by the ORAM					
Does the quantitative score fall within the scoring range of a Category 1, 2, or 3 wetland?	*YES Wetland is assigned to the appropriate category based on the scoring range	NO	If the score of the wetland is located within the scoring range for a particular category, the wetland should be assigned to that category. In all instances however, the narrative criteria described in OAC Rule 3745-1-54(C) can be used to clarify or change a categorization based on a quantitative score.					
Does the quantitative score fall with the "gray zone" for Category 1 or 2 or Category 2 or 3 wetlands?	YES Wetland is assigned to the higher of the two categories or assigned to a category based on detailed assessments and the narrative criteria	*NO	Rater has the option of assigning the wetland to the higher of the two categories or to assign a category based on the results of a nonrapid wetland assessment method, e.g. functional assessment, biological assessment, etc, and a consideration of the narrative criteria in OAC rule 3745-1-54(C).					
moderate OR superior hydrologic OR habitat, OR recreational	YES Wetland was undercategorized by this method. A written justification for recategorization should be provided on Background Information Form	*NO Wetland is assigned to category as determined the ORAM.	Imay he degraded by human activities, but the wetland may still exhibit					
Final Category								



WETLAND 01

Client Name:

Site Location:

Project No.

AEP

Innovation 138kV Station Project

60660544

Wetland 02

Date:

June 3, 2021

Description:

PEM

Category 1

Facing North



Wetland 02

Date:

June 3, 2021

Description:

PEM

Category 1

Facing East





WETLAND 01

Client Name:

Site Location:

Project No.

AEP

Innovation 138kV Station Project

60660544

Wetland 02

Date:

June 3, 2021

Description:

PEM

Category 1

Facing South



Wetland 02

Date:

June 3, 2021

Description:

PEM

Category 1

Facing West





WETLAND 01

Client Name: Site Location: Project No.

AEP Innovation 138kV Station Project 60660544

Wetland 02

Date:

June 3, 2021

Description:

PEM

Category 1

Soil Pit



WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Innovation Station Project		City/Cou	inty: Licking (County	Sampling Date:	6/3/2021
Applicant/Owner: AEP			State: OH	Sampling Point:	upl-jbl-20210603-01	
Investigator(s): JBL, SKM		Section, T	 Гownship, Ra	nge: Q / T2N / R15W		
Landform (hillside, terrace, etc.): swale		!	Local relief (c	concave, convex, none):	concave	
Slope (%):1	<u> </u>	Long: -	-82.72548		Datum: NAD 83	
Soil Map Unit Name: Cen1B1 - Centerburg silt loam, 2	to 6 percent	t slopes		NWI classif	ication: N/A	
Are climatic / hydrologic conditions on the site typical fo	or this time o	of year?	Yes	No x (If no, exp	olain in Remarks.)	
Are Vegetation, Soil, or Hydrologys	significantly	disturbed? F	Are "Normal C	Circumstances" present?	Yes x No	ı
Are Vegetation , Soil , or Hydrology n			[If needed, ex	plain any answers in Rei	marks.)	
SUMMARY OF FINDINGS – Attach site ma			ıg point lo	cations, transects,	important feat	ures, etc.
Wetland Hydrology Present? Yes X No	X		e Sampled Ar n a Wetland?		No_X_	
Remarks: Upland UPL-JBL-20210603-01 consists of a drainage	swale with	cottonwoods.	Swale does n	ot drain to another wate	r.	
VEGETATION – Use scientific names of plan	nts.					
<u>Tree Stratum</u> (Plot size: 30' radius)	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test wor	ksheet:	
1. N/A				Number of Dominant S Are OBL, FACW, or F	•	3 (A)
3.				Total Number of Domi		5 (7.)
4.				Across All Strata:	•	4 (B)
5.				Percent of Dominant S	Species That	
		=Total Cover		Are OBL, FACW, or F	•	.0% (A/B)
Sapling/Shrub Stratum (Plot size: 15' radius)		V.	540			
Populus deltoides 2.	60	Yes	<u>FAC</u>	Prevalence Index wo Total % Cover of		by:
3.				OBL species 0		0 0
4.				FACW species 20		40
5.				FAC species 90		70
	60	=Total Cover		FACU species 40		60
Herb Stratum (Plot size: 5' radius)				UPL species 0		0
1. Solidago gigantea	20	Yes	FACW	Column Totals: 15		70 (B)
2. Geum canadense	20	Yes	FAC	Prevalence Index =	= B/A = 3.13	
3. Ambrosia artemisiifolia	20	Yes	FACU	<u></u>		
4. Panicum virgatum	10	No	FAC	Hydrophytic Vegetat	ion Indicators:	
5. Setaria faberi	10	No	FACU	1 - Rapid Test for	Hydrophytic Vegeta	ation
6. Glechoma hederacea	10	No	FACU	X 2 - Dominance Te		
7.				3 - Prevalence Inc		
8					Adaptations ¹ (Provi	
9					s or on a separate s	•
10				Problematic Hydro	ophytic Vegetation ¹	(Explain)
	90	=Total Cover		¹ Indicators of hydric so		
Woody Vine Stratum (Plot size: 30' radius)				be present, unless dis	turbed or problemat	ic.
1. <u>N/A</u>				Hydrophytic		
2		-Total Cover		Vegetation	Y No	
		=Total Cover		Present? Yes	No	-
Remarks: (Include photo numbers here or on a separa Hydrophytic Vegetation present as dominance test > 5	,	ant species are	e FAC, FACW	V, FACU		

US Army Corps of Engineers

SOIL Sampling Point: -jbl-20210603

Profile Des	cription: (Describe t	o the depth	needed to doci	ument th	ne indica	tor or c	onfirm the absence	of indicators.)		
Depth	Matrix		Redo	x Featur	es					
(inches)	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²	Texture	R	emarks	
0-14	10YR 3/1	100					Loamy/Clayey			
14-17	10YR 3/2	95	10yr 4/6	5	С	M	Loamy/Clayey	Prominent re	dox concentration	ns
l — · · · · ·					<u> </u>					
-										
-								-		
¹ Type: C=C	oncentration, D=Depl	etion, RM=F	Reduced Matrix, N	//S=Mas	ked Sand	Grains	Location 2	n: PL=Pore Lining	, M=Matrix.	
Hydric Soil	Indicators:						Indicato	rs for Problemati	c Hydric Soils ³ :	
Histosol	(A1)		Sandy Gle	yed Mat	rix (S4)		Coa	st Prairie Redox (A	x 16)	
Histic Ep	oipedon (A2)		Sandy Red	dox (S5)			Iron-	Manganese Mass	es (F12)	
Black Hi	stic (A3)		Stripped M	latrix (S6	3)		Red	Parent Material (F	21)	
Hydroge	n Sulfide (A4)		Dark Surfa	ice (S7)			Very	Shallow Dark Sur	face (F22)	
Stratified	d Layers (A5)		Loamy Mu	cky Mine	eral (F1)		Othe	er (Explain in Rema	arks)	
2 cm Mu	ıck (A10)		Loamy Gle	eyed Mat	trix (F2)					
Depleted	d Below Dark Surface	(A11)	Depleted N	Лatrix (F	3)					
Thick Da	ark Surface (A12)		Redox Dar	rk Surfac	ce (F6)		³ Indicato	rs of hydrophytic v	egetation and	
Sandy N	lucky Mineral (S1)		Depleted D	Dark Sur	face (F7)		wetl	and hydrology mus	st be present,	
5 cm Mu	icky Peat or Peat (S3)	Redox Dep	oression	s (F8)		unle	ss disturbed or pro	blematic.	
Restrictive	Layer (if observed):									
Type:										
Depth (i	nches):		_				Hydric Soil Presen	it? Y	es No	Χ
Remarks:										
This data for	m is revised from Mic	west Region	nal Supplement \	ersion 2	2.0 to incl	ude the	NRCS Field Indicator	s of Hydric Soils ir	the United State	es,
	2018. (https://www.ni	cs.usda.gov	v/Internet/FSE_D	OCUME	NTS/nrcs	s142p2_	_053171.pdf)	•		
Hydric soil ir	ndicators not present									
HYDROLO	GY									
Wetland Hy	drology Indicators:									
	cators (minimum of o	ne is require	ed: check all that a	(vlage			Seconda	ary Indicators (mini	mum of two reau	uired)
	Water (A1)		Water-Stai		ves (B9)			ace Soil Cracks (B	-	
	iter Table (A2)		Aquatic Fa		(/			nage Patterns (B1	,	
Saturation			True Aqua		-			Season Water Tab	,	
	larks (B1)		Hydrogen)		fish Burrows (C8)		
	nt Deposits (B2)		Oxidized R					ıration Visible on A		9)
Drift Dep	posits (B3)		Presence of	of Reduc	ced Iron (C4)	Stur	ited or Stressed Pl	ants (D1)	
Algal Ma	at or Crust (B4)		Recent Iro	n Reduc	tion in Ti	led Soil	s (C6) x Geo	morphic Position (D2)	
Iron Dep	osits (B5)		Thin Muck	Surface	(C7)		FAC	-Neutral Test (D5)		
Inundati	on Visible on Aerial In	nagery (B7)	Gauge or \	Well Dat	a (D9)					
Sparsely	Vegetated Concave	Surface (B8	B)Other (Exp	olain in R	Remarks)					
Field Obser	vations:									
Surface Wat	er Present? Yes	6	No x	Depth (i	nches):					
Water Table					nches):					
Saturation P	resent? Yes			Depth (i	_		Wetland Hydrolo	gy Present? Y	es X No	
(includes ca	pillary fringe)				_	J				
Describe Re	corded Data (stream	gauge, mon	itoring well, aeria	l photos	, previous	sinspec	tions), if available:			
Remarks:										
no obvious o	trainage connectivity.	Primary so	urce of hydrology	is conc	entration	of preci	pitation in geomorphic	c position		

US Army Corps of Engineers

Midwest Region – Version 2.0

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Innovation Station Project		City/Cou	inty: Licking	County	Sampling Date:	06/03/2021
Applicant/Owner: AEP				State: OH	Sampling Point:	UPL-JBL-20210603-02
Investigator(s): JBL, SKM		Section, T	Γownship, Ra	nge: <u>Q / T2N / R15W</u>		
Landform (hillside, terrace, etc.): sloping		!	Local relief (c	concave, convex, none):	none	
Slope (%): 2 Lat: 40.09164		Long:	-82.72843		Datum: NAD 83	<u> </u>
Soil Map Unit Name: BeB - Bennington silt loam, 2 to 6	percent slo	pes		NWI classif	ication: N/A	
Are climatic / hydrologic conditions on the site typical for	r this time o	of year?	Yes X	No (If no, exp	olain in Remarks.)	
Are Vegetation, Soil, or Hydrologysi	ignificantly	disturbed? F	Are "Normal C	Circumstances" present?	Yes x No	o
Are Vegetation, Soil, or Hydrologyn	aturally pro	blematic? ((If needed, ex	plain any answers in Re	marks.)	
SUMMARY OF FINDINGS – Attach site ma			ig point lo	cations, transects	, important fea	tures, etc.
, , ,	Х		e Sampled Ar			
	<u>X</u>	withir	n a Wetland?	Yes	No X	
	<u>X</u>					
Remarks: Upland point UPL-JBL-20210603-02 for associated we	tland W-JR	u -20210603-0	11 to the sout	h		
Opiana point of L-05L-202 (0000-02 for according inc	lland vv ob	L-202 10000 0	/1 10 110 554.			
VEGETATION – Use scientific names of plar	nts.					
720217711017	Absolute	Dominant	Indicator			
<u>Tree Stratum</u> (Plot size: <u>30' radius</u>)	% Cover	Species?	Status	Dominance Test wor	ksheet:	
1. <u>N/A</u>				Number of Dominant	•	2 (4)
2				Are OBL, FACW, or F		2 (A)
3. 4.				Total Number of Dom Across All Strata:	inant Species	5 (B)
5.						<u>J</u> (D)
o		=Total Cover		Percent of Dominant S Are OBL, FACW, or F	•	0.0% (A/B)
Sapling/Shrub Stratum (Plot size: 15' radius)				· 		,
Rubus allegheniensis	20	Yes	FACU	Prevalence Index wo	orksheet:	
2. Fraxinus pennsylvanica	10	Yes	FACW	Total % Cover of	<u></u>	/ by:
3.				OBL species 0		0
4.				FACW species 1		20
5		- : : : : : : : : : : : : : : : : : : :		FAC species 3		90
(Dist size: El radius)	30	=Total Cover		FACU species 8		320
Herb Stratum (Plot size: 5' radius) 1. Solidago altissima	40	Yes	FACU	UPL species 0 Column Totals: 12		0 430 (B)
Solidago alussima Poa pratensis	30	Yes	FAC	Prevalence Index		``
3. Erigeron annuus	20	Yes	FACU	1 ICVAICTIOG THUCK	- 5/4 - 0.00	,
4.			17.00	Hydrophytic Vegetat	tion Indicators:	
5.					Hydrophytic Veget	ation
6.				2 - Dominance Te	est is >50%	
7.				3 - Prevalence Inc		
8.					Adaptations ¹ (Prov	
9.					s or on a separate	-
10				Problematic Hydr	ophytic Vegetation ¹	(Explain)
	90	=Total Cover		¹ Indicators of hydric se		
Woody Vine Stratum (Plot size: 30' radius)				be present, unless dis	turbed or problema	itic.
1. <u>N/A</u>				Hydrophytic		
2		=Total Cover		Vegetation Present? Yes	No X	
		- Total Gover		Pieseiit: 165		
Remarks: (Include photo numbers here or on a separa No hydrophytic vegetation present, dominant species a	,	FAC: and FAC	`\W			
The Hydrophysic vogotation process, definitions operated to	,, .	710, 4114 1710	, , ,			

US Army Corps of Engineers

SOIL Sampling Point: JBL-2021060

0-8 8-17	Color (moist)			x Featur					
		%	Color (moist)	%	Type ¹	Loc ²	Texture	Remarks	
8-17	10YR 4/3	100				·	Loamy/Clayey		
	10YR 4/3	99	10yr 4/6	1	С	M	Loamy/Clayey	Distinct redox concentrations	
		<u> </u>		<u> </u>		<u></u>			
Type: C=Cond	centration, D=Dep	letion, RM	======================================	MS=Mas	ked Sand	d Grains.	² Location	n: PL=Pore Lining, M=Matrix.	
Hydric Soil Ind		,	,					rs for Problematic Hydric Soils ³ :	
Histosol (A			Sandy Gle	yed Mat	rix (S4)			st Prairie Redox (A16)	
— Histic Epipe	•		Sandy Red					-Manganese Masses (F12)	
Black Histic			Stripped M					Parent Material (F21)	
— Hydrogen S	` '		Dark Surfa	`	- /			Shallow Dark Surface (F22)	
Stratified La			Loamy Mu	, ,	eral (F1)			er (Explain in Remarks)	
2 cm Muck			Loamy Gle	-				, , , , , , , , , , , , , , , , , , , ,	
	elow Dark Surface	e (A11)	Depleted N	•	, ,				
	Surface (A12)	. ()	Redox Da	•	•		³ Indicato	ors of hydrophytic vegetation and	
	ky Mineral (S1)		Depleted [` ')		and hydrology must be present,	
	y Peat or Peat (S3	3)	Redox De		, ,	•	unless disturbed or problematic.		
Restrictive Lav	yer (if observed):								
Type:	, . ,								
Depth (inch	es):						Hydric Soil Preser	nt? Yes No	
his data form i ersion 8.2, 20		ırcs.usda.	gional Supplement \ gov/Internet/FSE_D					rs of Hydric Soils in the United State	
This data form i /ersion 8.2, 20 lydric soil indic	18. (https://www.n cators not present	ırcs.usda.	• • • •					rs of Hydric Soils in the United State	
This data form in the second section 8.2, 20 style in the second section sec	18. (https://www.ncators not present	ırcs.usda.(• • • •					rs of Hydric Soils in the United State	
This data form i /ersion 8.2, 20 Hydric soil indic YDROLOG Wetland Hydro	18. (https://www.ncators not present Y plogy Indicators:	rcs.usda.(gov/Internet/FSE_D	OCUME			053171.pdf)	,	
This data form i /ersion 8.2, 20 Hydric soil indic YDROLOG Wetland Hydro Primary Indicato	18. (https://www.ncators not present Y logy Indicators: ors (minimum of o	rcs.usda.(gov/Internet/FSE_D	OCUME	NTS/nrcs	s142p2_(053171.pdf)	ary Indicators (minimum of two requ	
This data form i /ersion 8.2, 20 Hydric soil indic YDROLOG Wetland Hydro Primary Indicate Surface Wa	18. (https://www.ncators not present Y plogy Indicators: ors (minimum of oater (A1)	rcs.usda.(gov/Internet/FSE_D	OCUME	NTS/nrcs	s142p2_(053171.pdf) <u>Seconda</u> Surf	ary Indicators (minimum of two requirace Soil Cracks (B6)	
This data form i Persion 8.2, 20 Pydric soil indic YDROLOG Vetland Hydro Primary Indicate Surface Wa High Water	18. (https://www.ncators not present Y blogy Indicators: ors (minimum of oater (A1) Table (A2)	rcs.usda.(gov/Internet/FSE_D ired; check all that a Water-Sta	apply) ined Lea	NTS/nrcs	s142p2_(053171.pdf) SurfDrai	ary Indicators (minimum of two requ ace Soil Cracks (B6) nage Patterns (B10)	
YDROLOG Vetland Hydro Surface Wa High Water Saturation (18. (https://www.ncators not present Y Plogy Indicators: ors (minimum of oater (A1) Table (A2) (A3)	rcs.usda.(gov/Internet/FSE_D	apply) ined Lea auna (B1	NTS/nrcs	s142p2_(053171.pdf) Seconda Surf Drai Dry-	ary Indicators (minimum of two requ ace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2)	
YDROLOG Vetland Hydro Surface Water High Water Saturation (Water Mark	18. (https://www.ncators not present Y Plogy Indicators: ors (minimum of oater (A1) Table (A2) (A3)	rcs.usda.(nired; check all that a water-Sta	apply) ined Lea auna (B1 tic Plant Sulfide (NTS/nrcs ives (B9) 3) s (B14) Odor (C1	s142p2_(Surf Surf Drai DryCray	ary Indicators (minimum of two requ ace Soil Cracks (B6) nage Patterns (B10)	
YDROLOG Yetland Hydro Surface Water High Water Saturation (Water Mark	18. (https://www.ncators not present Y Dlogy Indicators: ors (minimum of orater (A1) Table (A2) (A3) (A3) (A5) (B1) Deposits (B2)	rcs.usda.(uired; check all that a Water-Sta Aquatic Fa True Aqua	apply) ined Lea auna (B1 titic Plant Sulfide (Rhizosph	ives (B9) 3) s (B14) Odor (C1 leres on I	s142p2_(Seconda Surf Drai Dry- Cray Sots (C3) Satu	ary Indicators (minimum of two requirace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2) /fish Burrows (C8)	
YDROLOG YDROLOG YDROLOG YURIAN Hydro Primary Indicate Surface Wa High Water Saturation (Water Mark Sediment D	18. (https://www.ncators not present Y Plogy Indicators: ors (minimum of orater (A1) Table (A2) (A3) (A3) (A3) (A9) (A9) (A9) (A9) (A9) (A9) (A9) (A9	rcs.usda.(ired; check all that a Water-Sta Aquatic Fa True Aqua Hydrogen Oxidized F	apply) ined Lea auna (B1 ttic Plant Sulfide (Rhizosph of Reduc	ives (B9) 3) s (B14) Odor (C1 leres on I	s142p2_() Living Ro (C4)	Seconda Surf Drai Dry- Cray Satu Stur	ary Indicators (minimum of two requivace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2) rfish Burrows (C8) uration Visible on Aerial Imagery (C8)	
YDROLOG Vetland Hydro Surface Wa High Water Saturation (Water Mark Sediment D Drift Deposi	18. (https://www.ncators not present Y blogy Indicators: ors (minimum of ocater (A1) Table (A2) (A3) is (B1) beposits (B2) its (B3) r Crust (B4)	rcs.usda.(gov/Internet/FSE_D ired; check all that a Water-Sta Aquatic Fa True Aqua Hydrogen Oxidized F Presence	apply) ined Lea auna (B1 stic Plant Sulfide (Rhizosph of Redu on Redu on Redu on Redu	ives (B9) 3) s (B14) Odor (C1 eres on led Iron (ction in Ti	s142p2_() Living Ro (C4)	Seconda Surf Drai Dry- Cray Sots (C3) Satu Stur	ary Indicators (minimum of two requirace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2) /fish Burrows (C8) uration Visible on Aerial Imagery (C9)	
YDROLOG YURAN Hydro YURAN HYD	18. (https://www.ncators not present Y blogy Indicators: ors (minimum of ocater (A1) Table (A2) (A3) is (B1) beposits (B2) its (B3) r Crust (B4)	ncs.usda.(gov/Internet/FSE_D irred; check all that a Water-Sta Aquatic Fa True Aqua Hydrogen Oxidized F Presence Recent Iro Thin Muck	apply) ined Lea auna (B1 stic Plant Sulfide (Rhizosph of Reduc	aves (B9) 3) s (B14) Odor (C1 eres on I ced Iron (ction in Ti e (C7)	s142p2_() Living Ro (C4)	Seconda Surf Drai Dry- Cray Sots (C3) Satu Stur	ary Indicators (minimum of two requivace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2) r/fish Burrows (C8) uration Visible on Aerial Imagery (C8) nted or Stressed Plants (D1) morphic Position (D2)	
YDROLOG YDROLOG Yetland Hydro Yimary Indicate Surface Wa High Water Saturation (Water Mark Sediment D Drift Deposi Algal Mat or Iron Deposi	18. (https://www.ncators not present Y Plogy Indicators: ors (minimum of of ater (A1) Table (A2) (A3) (s (B1) Deposits (B2) its (B3) r Crust (B4) its (B5)	ne is requ	ired; check all that a Water-Sta Aquatic Fa True Aqua Hydrogen Oxidized Fa Presence Recent Iro Thin Muck (7) Gauge or Variable (7)	apply) ined Lea auna (B1 tic Plant Sulfide (Rhizosph of Reduc in Reduc is Surface Well Dat	avves (B9) 3) s (B14) Odor (C1 eres on I ced Iron (ction in Ti e (C7) a (D9)) Living Ro (C4) Illed Soils	Seconda Surf Drai Dry- Cray Sots (C3) Satu Stur	ary Indicators (minimum of two requivace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2) r/fish Burrows (C8) uration Visible on Aerial Imagery (C8) nted or Stressed Plants (D1) morphic Position (D2)	
YDROLOG YDROLOG YDROLOG YUTAN YUTAN YUTAN YDROLOG YUTAN Y	18. (https://www.ncators not present Y Plogy Indicators: ors (minimum of orater (A1) Table (A2) (A3) (A3) (A3) (A5) (A6) (A6) (A6) (A6) (A6) (A7) (A7) (A8) (A8) (A8) (A9) (A9) (A9) (A9) (A9) (A9) (A9) (A9	ne is requ	ired; check all that a Water-Sta Aquatic Fa True Aqua Hydrogen Oxidized Fa Presence Recent Iro Thin Muck (7) Gauge or Variable (7)	apply) ined Lea auna (B1 tic Plant Sulfide (Rhizosph of Reduc in Reduc is Surface Well Dat	avves (B9) 3) s (B14) Odor (C1 eres on I ced Iron (ction in Ti e (C7) a (D9)) Living Ro (C4) Illed Soils	Seconda Surf Drai Dry- Cray Sots (C3) Satu Stur	ary Indicators (minimum of two requivace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2) r/fish Burrows (C8) uration Visible on Aerial Imagery (C8) nted or Stressed Plants (D1) morphic Position (D2)	
YDROLOG YDROLOG Vetland Hydro Surface Wa High Water Saturation (Water Mark Sediment D Drift Deposi Algal Mat or Iron Deposi Inundation (Sparsely Vetal	18. (https://www.ncators not present Y Plogy Indicators: ors (minimum of of ater (A1) Table (A2) (A3) (A3) (A3) (A3) (A3) (A3) (A3) (A3	ne is requ	mired; check all that a Water-Sta Aquatic Fa True Aqua Hydrogen Oxidized Facent Iro Recent Iro Thin Muck (7) Gauge or 188) Other (Exp.	apply) ined Lea auna (B1 stic Plant Sulfide (Rhizosph of Reduc on Reduc Surface Well Dat	avves (B9) 3) s (B14) Odor (C1 eres on I ced Iron (ction in Ti e (C7) a (D9)) Living Ra (C4) Illed Soils	Seconda Surf Drai Dry- Cray Sots (C3) Satu Stur	ary Indicators (minimum of two requivace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2) r/fish Burrows (C8) uration Visible on Aerial Imagery (C8) nted or Stressed Plants (D1) morphic Position (D2)	
This data form in version 8.2, 20 Hydric soil indicated Surface Water Mark Sediment Durift Deposition Deposition News 100 Drift Deposition Deposition News 100 Drift Deposition Deposition Deposition Deposition News 100 Drift Deposition Deposition News 100 Drift Deposition Deposition Deposition Deposition Deposition News 100 Drift Deposition News 100 Drift Deposition Deposi	18. (https://www.ncators not present Y Plogy Indicators: ors (minimum of orater (A1) Table (A2) (A3) (S (B1) Deposits (B2) its (B3) or Crust (B4) its (B5) Visible on Aerial Inegetated Concave tions: Present? Ye	magery (B	mired; check all that a water-Sta Aquatic Fa True Aqua Hydrogen Oxidized Fa Presence Recent Iro Thin Muck (7) Gauge or V(88) Other (Exp.	apply) ined Lea auna (B1 stic Plant Sulfide (Rhizosph of Reduc on Reduc surface Well Dat blain in F	avves (B9) 3) s (B14) Odor (C1 eres on I ced Iron (ction in Ti ct (C7) a (D9) Remarks)) Living Ro (C4) Illed Soils	Seconda Surf Drai Dry- Cray Sots (C3) Satu Stur	ary Indicators (minimum of two requivace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2) r/fish Burrows (C8) uration Visible on Aerial Imagery (C8) nted or Stressed Plants (D1) morphic Position (D2)	
Version 8.2, 20 Hydric soil indice Vetland Hydro Primary Indicate Surface Wa High Water Saturation (Water Mark Sediment D Drift Deposi Algal Mat of Iron Deposi Inundation	18. (https://www.n.cators not present Y Dlogy Indicators: Drs (minimum of orater (A1) Table (A2) (A3) (A3) (A3) (A3) (A3) (A3) (A3) (A3	magery (B	ired; check all that a Water-Sta Aquatic Fa True Aqua Hydrogen Oxidized For Presence Recent Iro Thin Muck (7) Gauge or (B8) Other (Exp.	apply) ined Lea auna (B1 tic Plant Sulfide (Rhizosph of Reduct in Reduct is Surface Well Dat Depth (i	aves (B9) 3) s (B14) Odor (C1 eres on I ced Iron (stion in Ti c (C7) a (D9) Remarks)) Living Ro (C4) Illed Soils	Seconda Surf Drai Dry- Cray Sots (C3) Satu Stur	ary Indicators (minimum of two requirace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2) /fish Burrows (C8) uration Visible on Aerial Imagery (C9 nted or Stressed Plants (D1) morphic Position (D2) E-Neutral Test (D5)	
IThis data form it Version 8.2, 20 Hydric soil indice IYDROLOG Wetland Hydro Primary Indicate Surface Wa High Water Saturation (Water Mark Sediment D Drift Deposi Inundation V Sparsely Versield Observate Water Table Pre	18. (https://www.n.cators not present eators (minimum of or eater (A1) Table (A2) (A3) (A3) (A3) (A3) (A3) (A3) (A3) (A3	magery (B	ired; check all that a Water-Sta Aquatic Fa True Aqua Hydrogen Oxidized For Presence Recent Iro Thin Muck (7) Gauge or (B8) Other (Exp.	apply) ined Lea auna (B1 tic Plant Sulfide (Rhizosph of Reduct in Reduct is Surface Well Dat Depth (i	avves (B9) 3) s (B14) Odor (C1 eres on I ced Iron (ction in Ti e (C7) a (D9) Remarks) nches): _ nches): _) Living Ro (C4) Illed Soils	Seconda Surf Drai Dry- Cray Satu Stur Stur Geo	ary Indicators (minimum of two requirace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2) r/fish Burrows (C8) uration Visible on Aerial Imagery (C9 nted or Stressed Plants (D1) morphic Position (D2) E-Neutral Test (D5)	
This data form in Version 8.2, 20 Hydric soil indicated and Hydro Primary Indicated Surface Water Mark Sediment Dorift Deposion Inundation Sparsely Version Deposion Inundation Sparsely Version Observated Surface Water Includes Capilla	18. (https://www.n.cators not present Y Dlogy Indicators: ors (minimum of orater (A1) Table (A2) (A3) (A3) (A3) (A3) (A3) (A3) (A3) (A3	magery (B	ired; check all that a Water-Sta Aquatic Fa True Aqua Hydrogen Oxidized For Presence Recent Iro Thin Muck (7) Gauge or (88) Other (Exp.	apply) ined Lea auna (B1 titic Plant Sulfide (Rhizosph of Reduc on Reduc o	ives (B9) 3) s (B14) Odor (C1 eres on I ced Iron (ction in Ti e (C7) a (D9) Remarks) nches): _ nches): _) Living Ro (C4) Illed Soils	Seconda	ary Indicators (minimum of two requirace Soil Cracks (B6) nage Patterns (B10) Season Water Table (C2) r/fish Burrows (C8) uration Visible on Aerial Imagery (C9 nted or Stressed Plants (D1) morphic Position (D2) E-Neutral Test (D5)	

US Army Corps of Engineers

Midwest Region – Version 2.0

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Innovation Station Project		City/Cou	inty: Licking (County	Sampling Date:	06/03/2021
Applicant/Owner: AEP				State: OH	Sampling Point:	UPL-JBL-20210603-03
Investigator(s): JBL, SKM		Section, T		nge: Q / T2N / R15W		
Landform (hillside, terrace, etc.): sloping			Local relief (c	concave, convex, none):	none	
Slope (%): 2 Lat: 40.09220		Long: -	-82.72874	-	Datum: NAD 83	
Soil Map Unit Name: BeB, Bennington silt loam, 2 to 6	percent slop				ication: N/A	
Are climatic / hydrologic conditions on the site typical fo			Yes			
Are Vegetation , Soil , or Hydrology s		-		Circumstances" present?)
Are Vegetation , Soil , or Hydrology n				plain any answers in Re		
SUMMARY OF FINDINGS – Attach site ma			`	•	,	tures, etc.
<u></u>	X		e Sampled Ar n a Wetland?		No X	
Remarks: Upland point UPL-JBL-20210603-03 in mixed vegetation	on area.					
VEGETATION – Use scientific names of plan	nts. Absolute	Dominant	Indicator			
<u>Tree Stratum</u> (Plot size: 30' radius)	% Cover	Species?	Indicator Status	Dominance Test wor	ksheet:	
1. <i>N/A</i>				Number of Dominant	Species That	
2				Are OBL, FACW, or F	AC:	2 (A)
3				Total Number of Domi	inant Species	(D)
4				Across All Strata:		4 (B)
5		=Total Cover		Percent of Dominant S Are OBL, FACW, or F	•).0% (A/B)
Sapling/Shrub Stratum (Plot size: 15' radius)		-10tai 00.5.		7110 ODE, 171011, 111	A0).0 /0 (/ • = /
1. <u>N/A</u>				Prevalence Index wo	orksheet:	
2.				Total % Cover of	: Multiply	by:
3.				OBL species 0	x 1 =	0
4				FACW species 10		20
5				FAC species 55		165
(DI) Standing)		=Total Cover		FACU species 60		240
Herb Stratum (Plot size: 5' radius)	20	Voo	EACH.	UPL species 0		0 125 (B)
1. Solidago altissima	20	Yes	FACU	Column Totals: 12 Prevalence Index		125 (B)
Poa pratensis Erigeron annuus	5	Yes No	FACU	Prevalence muex -	= B/A = 3.40)
Carex annectens	5	No	FACW	Hydrophytic Vegetat	ion Indicators:	
5. Rumex crispus	20	Yes	FAC		Hydrophytic Veget	ation
6. Juncus tenuis	15	No	FAC	2 - Dominance Te	, , ,	dion
7. Ambrosia artemisiifolia	20	Yes	FACU	3 - Prevalence Inc		
8. Packera glabella	5	No	FACW		Adaptations ¹ (Prov	ide supporting
9. Xanthium spinosum	5	No	FACU	data in Remark	s or on a separate	sheet)
10. Trifolium pratense	10	No	FACU	Problematic Hydro	ophytic Vegetation ¹	(Explain)
	125	=Total Cover		¹ Indicators of hydric se		
Woody Vine Stratum (Plot size: 30' radius)				be present, unless dis	turbed or problema	tic.
1. <u>N/A</u>				Hydrophytic		
2				Vegetation		
		=Total Cover		Present? Yes	No X	_
Remarks: (Include photo numbers here or on a separa Hydrophytic Vegetation not present as domincance tes	,	minant specie	es are FACU,	FAC, FACW		

US Army Corps of Engineers

SOIL Sampling Point: JBL-2021060

Profile Desc	cription: (Describe	to the depti	n needed to doc	ument t	he indica	tor or c	onfirm the abs	ence of indica	ators.)	
Depth	Matrix		Redo	x Featur	es					
(inches)	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²	Texture		Remarks	
0-7	10YR 4/3	100					Loamy/Clay	еу		
7-12	10YR 4/2	98	10YR 4/4	2	С	М	Loamy/Clay	ey Di	stinct redox conce	entrations
12-18	10YR 4/2	96	10YR 4/4	4	С	M	Loamy/Clay	ey Di	stinct redox conce	entrations
¹ Type: C=C	oncentration, D=Dep	letion RM=I	Reduced Matrix 1	MS=Mas	ked Sand	Grains	² l o	cation: PI =Po	ore Lining, M=Mat	trix
Hydric Soil	•		, .						oblematic Hydri	
Histosol			Sandy Gle	yed Mat	trix (S4)			Coast Prairie	-	
	oipedon (A2)		Sandy Re					_	ese Masses (F12)
Black Histic (A3) Stripped Matrix (S6)							Red Parent M		,	
Hydrogen Sulfide (A4) Dark Surface (S7)								Very Shallow	Dark Surface (F2	22)
Stratified	d Layers (A5)		Loamy Mu	icky Min	eral (F1)			Other (Explai	n in Remarks)	·
2 cm Mu	ıck (A10)		Loamy Gle	eyed Ma	trix (F2)			_		
Depleted	d Below Dark Surface	e (A11)	Depleted I	Matrix (F	3)					
Thick Dark Surface (A12) Redox Dark Surface (F6)							³ Inc	dicators of hyd	rophytic vegetation	on and
Sandy M	Sandy Mucky Mineral (S1) Depleted Dark Surface (F7)							wetland hydro	ology must be pre	esent,
5 cm Mu	5 cm Mucky Peat or Peat (S3) Redox Depressions (F8)						unless disturbed or problematic.			
Restrictive	Layer (if observed):									
Type:			<u></u>							
Depth (in	nches):						Hydric Soil Pi	resent?	Yes	No X
	ndicators not present									
HYDROLC										
Wetland Hy	drology Indicators:									
-	cators (minimum of o	ne is require							tors (minimum of	two required)
	Water (A1)		Water-Sta		, ,		X	Surface Soil (` ,	
	ater Table (A2)		Aquatic Fa					Drainage Pat		
Saturation	` '		True Aqua				-	-	Nater Table (C2)	
	larks (B1)		Hydrogen Ovidized 5					Crayfish Burr	ows (C8) sible on Aerial Im	
	nt Deposits (B2) posits (B3)		Oxidized F Presence			-		-	ressed Plants (D	,
	at or Crust (B4)		Recent Iro				s (C6) x	Geomorphic	•	1)
	posits (B5)		Thin Muck			ilou ooii	x (00)	FAC-Neutral		
	on Visible on Aerial Ir	nagery (B7)			, ,				. 551 (2-5)	
	Vegetated Concave									
Field Obser	vations:	•	<u> </u>		,					
Surface Wat		s	No x	Depth (i	nches):					
Water Table		s	No x		nches):					
Saturation P	resent? Ye	s	No x		nches):		Wetland Hy	drology Prese	ent? Yes X	No
(includes ca	pillary fringe)				_					
Describe Re	corded Data (stream	gauge, mor	nitoring well, aeria	l photos	, previou	s inspec	tions), if availabl	e:		
Remarks:	يلا ديندانياد مم اممامان		a ativity Deima		اعتاديط 6		naantrati	reeleltetier !		ion
potentially is	olated, no obvious dr	amage conf	iectivity. Primary	source	oi riyarok	ogy is co	oncentration of p	recipitation in	geomorpnic posit	IIUII

US Army Corps of Engineers Midwest Region – Version 2.0

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Innovation Station Project		City/Cour	nty: Licking	County	Sampling Date:	06/03/2021
Applicant/Owner: AEP				State: OH	Sampling Point:	
Investigator(s): JBL, SKM		Section, T	ownship, Ra	nge: Q / T2N / R15W		
Landform (hillside, terrace, etc.): hillside				concave, convex, none):	convex	
Slope (%): 2 Lat: 40.09356		Long: -	82.72866	-	Datum: NAD 83	
Soil Map Unit Name: Pe - Pewamo silty clay loam, low	carbonate ti			NWI classif	ication: N/A	
Are climatic / hydrologic conditions on the site typical fo		•	Yes			
Are Vegetation, Soil, or Hydrologys		-		 -	•	
Are Vegetation , Soil , or Hydrology r						
SUMMARY OF FINDINGS – Attach site ma						atures, etc.
Hydric Soil Present? Yes No	o X o X o X	withir	Sampled And a Wetland?	? Yes	No X	
		L-202 10000 0	2, 1000100 01	I Deliii iii Delwooii 300ao.	IIS OF WELLAND.	
VEGETATION – Use scientific names of pla		Directions	to diseason			
<u>Tree Stratum</u> (Plot size: 30' radius)	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test wor	ksheet:	
1. <i>N/A</i> 2.				Number of Dominant S Are OBL, FACW, or F	•	1 (A)
3.				Total Number of Domi		(
4 5.				Across All Strata:		3 (B)
J		=Total Cover		Percent of Dominant S Are OBL, FACW, or Factor	•	33.3% (A/B)
Sapling/Shrub Stratum (Plot size: 15' radius)						
Rubus allegheniensis	60	Yes	FACU	Prevalence Index wo		
2. Quercus macrocarpa	10	No	FAC	Total % Cover of:		
3. Quercus palustris	10	No	FACW	OBL species 0		0
4				FACW species 10		20
5				FAC species 30		90
Horb Stratum (Diet size) El radius	80	=Total Cover		FACU species 12		480
Herb Stratum (Plot size: 5' radius)	60	Yes	FACU	UPL species 0 Column Totals: 16		0 590 (B)
Solidago altissima Juncus tenuis	20	Yes	FAC	Prevalence Index =	`	`` ′
3.						
4.				Hydrophytic Vegetat	ion Indicators:	
5.				1 - Rapid Test for	Hydrophytic Vege	etation
6.				2 - Dominance Te	st is >50%	
7.				3 - Prevalence Inc	dex is ≤3.0 ¹	
8.				4 - Morphological		
9.				data in Remark	s or on a separate	e sheet)
10				Problematic Hydro	ophytic Vegetation	n¹ (Explain)
		=Total Cover		¹ Indicators of hydric so		
Woody Vine Stratum (Plot size: 30' radius)				be present, unless dis	turbed or problem	atic.
1. <i>N/A</i>				Hydrophytic		
2		T-4-1 O		Vegetation	N	,
		=Total Cover		Present? Yes	No_X	<u></u>
Remarks: (Include photo numbers here or on a separ Hydrophytic Vegetation present as dominance test <5	,	nt species are	FACU, FAC	, FACW		

US Army Corps of Engineers

SOIL Sampling Point: JBL-2021060

Depth N						onfirm the absence of indi		
-	Matrix	Redox	Features					
(inches) Color (m	noist) %	Color (moist)	% Ty	/pe ¹	Loc ²	Texture	Remarks	
0-10 10YR 2	2/2 100					Loamy/Clayey		
10-17 10YR 3	3/2 10					Loamy/Clayey		
¹ Type: C=Concentration,	D=Depletion, RM=	Reduced Matrix, MS	S=Masked	Sand	Grains.	² Location: PL=	Pore Lining, M=Matrix.	
Hydric Soil Indicators:						Indicators for I	Problematic Hydric Soils ³ :	
Histosol (A1)	Histosol (A1)		Sandy Gleyed Matrix (S4)			Coast Prairie Redox (A16)		
Histic Epipedon (A2)		Sandy Redo	ox (S5)			Iron-Manganese Masses (F12)		
Black Histic (A3)						Red Parent Material (F21)		
Hydrogen Sulfide (A4)	Dark Surfac	e (S7)			Very Shallo	w Dark Surface (F22)	
Stratified Layers (A5)		Loamy Mucl	ky Mineral	(F1)		Other (Expl	ain in Remarks)	
2 cm Muck (A10)		Loamy Gley	ed Matrix ((F2)				
Depleted Below Dark	Surface (A11)	Depleted Ma	atrix (F3)					
Thick Dark Surface (A	Redox Dark	Surface (F	- 6)		³ Indicators of hydrophytic vegetation and			
Sandy Mucky Mineral (S1) Depleted Dark Surface			ark Surface	(F7)		wetland hyd	drology must be present,	
5 cm Mucky Peat or Peat (S3)Redox Depressions (F8)			8)		unless disturbed or problematic.			
Restrictive Layer (if obs	erved):							
Туре:								
Depth (inches):		<u> </u>				Hydric Soil Present?	Yes No_X	
Hydric soil indicators not p	oresent							
HYDROLOGY								
Wetland Hydrology Indi	cators:							
Primary Indicators (minim								
	um of one is requir	ed; check all that ap	oply)			Secondary Indic	cators (minimum of two required)	
Surface Water (A1)	um of one is requir	ed; check all that ap Water-Stain		(B9)			cators (minimum of two required)	
Surface Water (A1) High Water Table (A2	•		ed Leaves	(B9)		Surface So Drainage P	atterns (B10)	
High Water Table (A2 Saturation (A3)	•	Water-Stain Aquatic Fau True Aquatic	ed Leaves ina (B13) c Plants (B	14)		Surface So Drainage P Dry-Seasor	il Cracks (B6) atterns (B10) n Water Table (C2)	
High Water Table (A2 Saturation (A3) Water Marks (B1)	2)	Water-Stain Aquatic Fau True Aquatic Hydrogen S	ed Leaves ina (B13) c Plants (B ulfide Odor	14) r (C1)		Surface So Drainage P Dry-Seasor Crayfish Bu	il Cracks (B6) atterns (B10) n Water Table (C2) nrows (C8)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B	2)	Water-Stain Aquatic Fau True Aquatic Hydrogen S Oxidized Rh	ed Leaves na (B13) c Plants (B ulfide Odor nizospheres	514) r (C1) s on Li	-	Surface So Drainage P Dry-Seasor Crayfish Bu ots (C3) Saturation	atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B Drift Deposits (B3)	2)	Water-Stain Aquatic Fau True Aquatic Hydrogen S Oxidized Rh	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I	14) r (C1) s on Li Iron (C	(4)	Surface So Drainage P Dry-Seasor Crayfish Bu oots (C3) Saturation S	atterns (B6) atterns (B10) n Water Table (C2) nrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B Drift Deposits (B3) Algal Mat or Crust (B4	2)	Water-Stain Aquatic Fau True Aquatic Hydrogen S Oxidized Rh Presence of Recent Iron	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I Reduction	(14) r (C1) s on Li Iron (C	(4)	Surface So Drainage P Dry-Seasor Crayfish Bu oots (C3) Saturation Stunted or S (C6) Geomorphi	atterns (B6) atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) c Position (D2)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B3) Algal Mat or Crust (B4 Iron Deposits (B5)	32)	Water-Stain Aquatic Fau True Aquatic Hydrogen S Oxidized Rh Presence of Recent Iron Thin Muck S	ed Leaves ina (B13) c Plants (B ulfide Odor izospheres f Reduced I Reduction Surface (C7	r (C1) s on Li lron (C in Till	(4)	Surface So Drainage P Dry-Seasor Crayfish Bu oots (C3) Saturation S	atterns (B6) atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) c Position (D2)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B3) Drift Deposits (B3) Algal Mat or Crust (B4 Iron Deposits (B5) Inundation Visible on	2) 32) 4) Aerial Imagery (B7	Water-Stain Aquatic Fau True Aquatic Hydrogen S Oxidized Rh Presence of Recent Iron Thin Muck S) Gauge or W	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I Reduction Surface (C7 /ell Data (D	114) r (C1) s on Li lron (C in Till 7)	(4)	Surface So Drainage P Dry-Seasor Crayfish Bu oots (C3) Saturation Stunted or S (C6) Geomorphi	Il Cracks (B6) atterns (B10) n Water Table (C2) nrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) c Position (D2)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B3) Algal Mat or Crust (B4 Iron Deposits (B5) Inundation Visible on Sparsely Vegetated C	2) 32) 4) Aerial Imagery (B7	Water-Stain Aquatic Fau True Aquatic Hydrogen S Oxidized Rh Presence of Recent Iron Thin Muck S) Gauge or W	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I Reduction Surface (C7 /ell Data (D	114) r (C1) s on Li lron (C in Till 7)	(4)	Surface So Drainage P Dry-Seasor Crayfish Bu oots (C3) Saturation Stunted or S (C6) Geomorphi	atterns (B6) atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) c Position (D2)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B3) Algal Mat or Crust (B4 Iron Deposits (B5) Inundation Visible on Sparsely Vegetated C	2) 32) 4) Aerial Imagery (B7 Concave Surface (B	Water-Stain Aquatic Fau True Aquatic Hydrogen S Oxidized Rh Presence of Recent Iron Thin Muck S Gauge or W 8) Other (Explain	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I Reduction Surface (C7 /ell Data (D	r (C1) s on Li lron (C in Till 7) 09) arks)	(4)	Surface So Drainage P Dry-Seasor Crayfish Bu oots (C3) Saturation Stunted or S (C6) Geomorphi	atterns (B6) atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) c Position (D2)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B3) Algal Mat or Crust (B4 Iron Deposits (B5) Inundation Visible on Sparsely Vegetated C Field Observations: Surface Water Present?	2) 32) 4) Aerial Imagery (B7 Concave Surface (B Yes	Water-Stain Aquatic Fau True Aquatic Hydrogen S Oxidized Rh Presence of Recent Iron Thin Muck S) Gauge or W 8) Other (Expla	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I Reduction Surface (C7 /ell Data (D ain in Rema	14) r (C1) s on Li lron (C in Till r)) arks) es):	(4) ed Soils	Surface So Drainage P Dry-Seasor Crayfish Bu oots (C3) Saturation Stunted or S (C6) Geomorphi	atterns (B6) atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) c Position (D2)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B3) Algal Mat or Crust (B4 Iron Deposits (B5) Inundation Visible on Sparsely Vegetated C Field Observations: Surface Water Present? Water Table Present?	2) 4) Aerial Imagery (B7 Concave Surface (B Yes Yes Yes	Water-Stain	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I Reduction Surface (C7 /ell Data (D ain in Rema	114) r (C1) s on Li lron (C in Till r))) arks) es):es):	(4) ed Soils	Surface So Drainage P Dry-Seasor Crayfish Bu oots (C3) Saturation Stunted or 3 (C6) Geomorphi FAC-Neutra	atterns (B6) atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) a Position (D2) al Test (D5)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B3) Algal Mat or Crust (B4 Iron Deposits (B5) Inundation Visible on Sparsely Vegetated C Field Observations: Surface Water Present? Water Table Present? Saturation Present?	2) 32) 4) Aerial Imagery (B7 Concave Surface (B Yes	Water-Stain	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I Reduction Surface (C7 /ell Data (D ain in Rema	114) r (C1) s on Li lron (C in Till r))) arks) es):es):	(4) ed Soils	Surface So Drainage P Dry-Seasor Crayfish Bu oots (C3) Saturation Stunted or S (C6) Geomorphi	atterns (B6) atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) a Position (D2) al Test (D5)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B3) Algal Mat or Crust (B4 Iron Deposits (B5) Inundation Visible on Sparsely Vegetated C Field Observations: Surface Water Present? Water Table Present? Saturation Present? (includes capillary fringe)	2) Aerial Imagery (B7 Concave Surface (B Yes Yes Yes Yes	Water-Stain	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I Reduction Surface (C7 fell Data (D ain in Rema Depth (inche	114) r (C1) s on Li Iron (C in Tille 7) 99) arks) es): es):	:4) ed Soils	Surface So Drainage P Dry-Seasor Crayfish Bu Saturation Stunted or S (C6) Geomorphi FAC-Neutra Wetland Hydrology Pre	atterns (B6) atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) a Position (D2) al Test (D5)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B3) Algal Mat or Crust (B4 Iron Deposits (B5) Inundation Visible on Sparsely Vegetated C Field Observations: Surface Water Present? Water Table Present? Saturation Present?	2) Aerial Imagery (B7 Concave Surface (B Yes Yes Yes Yes	Water-Stain	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I Reduction Surface (C7 fell Data (D ain in Rema Depth (inche	114) r (C1) s on Li Iron (C in Tille 7) 99) arks) es): es):	:4) ed Soils	Surface So Drainage P Dry-Seasor Crayfish Bu Saturation Stunted or S (C6) Geomorphi FAC-Neutra Wetland Hydrology Pre	atterns (B6) atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) a Position (D2) al Test (D5)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B3) Algal Mat or Crust (B4 Iron Deposits (B5) Inundation Visible on Sparsely Vegetated C Field Observations: Surface Water Present? Water Table Present? Saturation Present? (includes capillary fringe)	2) Aerial Imagery (B7 Concave Surface (B Yes Yes Yes Yes	Water-Stain	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I Reduction Surface (C7 fell Data (D ain in Rema Depth (inche	114) r (C1) s on Li Iron (C in Tille 7) 99) arks) es): es):	:4) ed Soils	Surface So Drainage P Dry-Seasor Crayfish Bu Saturation Stunted or S (C6) Geomorphi FAC-Neutra Wetland Hydrology Pre	atterns (B6) atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) a Position (D2) al Test (D5)	
High Water Table (A2 Saturation (A3) Water Marks (B1) Sediment Deposits (B3) Algal Mat or Crust (B4 Iron Deposits (B5) Inundation Visible on Sparsely Vegetated C Field Observations: Surface Water Present? Water Table Present? Saturation Present? (includes capillary fringe) Describe Recorded Data	2) Aerial Imagery (B7 Concave Surface (B Yes Yes Yes Yes (stream gauge, mo	Water-Stain Aquatic Fau True Aquatic Hydrogen S Oxidized Rh Presence of Recent Iron Thin Muck S) Gauge or W 8) Other (Explain No x D	ed Leaves ina (B13) c Plants (B ulfide Odor nizospheres f Reduced I Reduction Surface (C7 fell Data (D ain in Rema Depth (inche	114) r (C1) s on Li Iron (C in Tille 7) 99) arks) es): es):	:4) ed Soils	Surface So Drainage P Dry-Seasor Crayfish Bu Saturation Stunted or S (C6) Geomorphi FAC-Neutra Wetland Hydrology Pre	atterns (B10) atterns (B10) a Water Table (C2) arrows (C8) Visible on Aerial Imagery (C9) Stressed Plants (D1) a Position (D2) al Test (D5)	

US Army Corps of Engineers Midwest Region – Version 2.0

WETLAND DETERMINATION DATA FORM - Midwest Region

Project/Site: Innovation Station Project		City/Cour	nty: Licking	County	Sampling Da	nte: <u>0</u> 6/0	3/2021
Applicant/Owner: AEP				State: OH	Sampling Po	int: upl-jbl-2	20210603-05
Investigator(s): JBL, SKM		Section, T	ownship, Ra	nge: Q / T2N / R15W			
Landform (hillside, terrace, etc.): sloping depressional		ı	Local relief (c	concave, convex, none):	none		
Slope (%): 2 Lat: 40.09594						3	
Soil Map Unit Name: Pe - Pewamo silty clay loam, low c	arbonate ti						
Are climatic / hydrologic conditions on the site typical for				No x (If no, exp		s.)	
Are Vegetation x , Soil , or Hydrology sig		-				-	
Are Vegetation, Soil, or Hydrology na							-
SUMMARY OF FINDINGS – Attach site map						features	s, etc.
Hydric Soil Present? Yes No Wetland Hydrology Present? Yes X No	X X		Sampled Ar		No_X		
Remarks: Upland point UPL-JBL-20210603-05 on edge of area w vegetation.	ith appaen	t matted down	vegetation.	Sample point taken dow	n gradient of a	rea devoid	of
VEGETATION – Use scientific names of plan							
	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test wor	ksheet:		
1. <i>N/A</i> 2.				Number of Dominant S Are OBL, FACW, or FA	Species That	2	(A)
3				Total Number of Domi Across All Strata:	-	4	(B)
5.		=Total Cover		Percent of Dominant S Are OBL, FACW, or F.	•	50.0%	_ (A/B)
Sapling/Shrub Stratum (Plot size: 15' radius)							
1. <u>N/A</u>				Prevalence Index wo			
2				Total % Cover of:		Itiply by:	-
3				OBL species 0		0	- 1
4				FACW species 20		40	-
5		-Total Cover		FAC species 35 FACU species 25		105	-
- Herb Stratum (Plot size: 5' radius)		=Total Cover		UPL species 0		100 0	-
1. Rumex crispus	30	Yes	FAC	Column Totals: 80		245	(B)
2. Packera glabella	10	Yes	FACW	Prevalence Index =	`` / _	3.06	- \- '
3. Schedonorus arundinaceus	10	Yes	FACU				_
4. Viola bicolor	10	Yes	FACU	Hydrophytic Vegetati	ion Indicators	:	
5. Cyperus esculentus	5	No	FACW	1 - Rapid Test for	Hydrophytic V	egetation	
6. Phalaris arundinacea	5	No	FACW	2 - Dominance Te	st is >50%		
7. Ambrosia artemisiifolia	5	No	FACU	3 - Prevalence Ind	lex is ≤3.0 ¹		
Geum canadense 9.	5	No	FAC	4 - Morphological data in Remark			
10				Problematic Hydro	ophytic Vegeta	tion ¹ (Expl	ain)
Woody Vine Stratum (Plot size: 30' radius)	80	=Total Cover		¹ Indicators of hydric so be present, unless dist			must
1. <u>N/A</u>				Hydrophytic			
2		=Total Cover		Vegetation Present? Yes_	No _	x	
Remarks: (Include photo numbers here or on a separa Hydrophytic Vegetation not present as dominance test	,	%, dominant s	pecies are F	AC, FACW, FACU			

US Army Corps of Engineers

SOIL Sampling Point: -jbl-20210603

Profile Desc	cription: (Describe	to the dep	th needed to doc	ument t	he indica	tor or	confirm the absence	of indicators.)		
Depth	Matrix		Redo	x Featur	es					
(inches)	Color (moist)	<u>%</u>	Color (moist)	%	Type ¹	Loc ²	Texture	Remarks		
0-10	10YR 3/2	100					Loamy/Clayey			
10-15	10YR 3/2	98	7.5YR 3/4	2	С	М	Loamy/Clayey	Distinct redox concentrations		
15-18	10YR 3/2	96	7.5YR 4/4	4	С		Loamy/Clayey	Distinct redox concentrations		
	oncentration, D=Dep	letion, RM:	=Reduced Matrix, N	//S=Mas	ked Sand	Grains		: PL=Pore Lining, M=Matrix.		
Hydric Soil								rs for Problematic Hydric Soils ³ :		
— Histosol	` '			Sandy Gleyed Matrix (S4)				Coast Prairie Redox (A16)		
<u> </u>	— Histic Epipedon (A2)			Sandy Redox (S5)			Iron-Manganese Masses (F12)			
	Black Histic (A3)			Stripped Matrix (S6)			Red Parent Material (F21)			
I — -	n Sulfide (A4)		Dark Surfa	` ,			Very Shallow Dark Surface (F22)			
	d Layers (A5)		Loamy Mu	-			Other (Explain in Remarks)			
	ick (A10) d Below Dark Surface	. (Δ11)	Loamy Gle	-						
I — ·	ark Surface (A12)	(A11)	Depleted N				³ Indicators of hydrophytic vegetation and			
I —	` '			Redox Dark Surface (F6)			wetland hydrology must be present,			
I —	Sandy Mucky Mineral (S1)			Depleted Dark Surface (F7) Redox Depressions (F8)			unless disturbed or problematic.			
5 cm Mucky Peat or Peat (S3) Restrictive Layer (if observed):							dilloc	unless disturbed of problematic.		
Type:	Layer (ii observed).									
Depth (ir	nches):						Hydric Soil Present	t? Yes No X		
							,			
Remarks:	m is revised from Mi	dwest Pea	ional Supplement \	/orgion '	2 0 to incl	ludo tha	NPCS Field Indicator	s of Hydric Soils in the United States,		
	2018. (https://www.n							s of Flydric Solis in the Officed States,		
	ndicators not present		_				_ , ,			
HYDROLO)GV									
1	drology Indicators:						0			
-	cators (minimum of c	ne is requ					Secondary Indicators (minimum of two required)			
Surface Water (A1)			Water-Stained Leaves (B9) Aquatic Fauna (B13)				_x_ Surface Soil Cracks (B6) Drainage Patterns (B10)			
_	<u> </u>		,	,		Season Water Table (C2)				
	Saturation (A3) Water Marks (B1) True Aquatic Plants Hydrogen Sulfide O			١		fish Burrows (C8)				
	Sediment Deposits (B2) Nydrogen Sunde Gdor (C1) Oxidized Rhizospheres on Living				ration Visible on Aerial Imagery (C9)					
Drift Deposits (B3) Presence of I		•		•	· · · —	ted or Stressed Plants (D1)				
Algal Mat or Crust (B4) Recent Iron F						morphic Position (D2)				
Iron Deposits (B5) Thin Muck Surface (C7)			• • —	-Neutral Test (D5)						
l — ·	on Visible on Aerial I	magery (B			` '		_	,		
	Vegetated Concave		· —							
Field Obser	vations:									
Surface Wat	er Present? Ye	s	No x	Depth (i	nches):					
Water Table	Present? Ye			Depth (i	nches):					
Saturation P	resent? Ye	s x			nches):	15	Wetland Hydrolog	gy Present? Yes X No		
(includes ca	pillary fringe)				_					
Describe Re	corded Data (stream	gauge, mo	onitoring well, aeria	l photos	, previous	s insped	ctions), if available:			
- Domoris-										
Remarks:	ning and abundant re	ain over las	st 48 hours, and no	water to	able obse	rved in	of Primary source of h	ydrology is concentration of		
1	in geomorphic positi		10 115415, 4114 110		0036		a, i iiiiai y oodioo oi i	., a. stogy to combonition of		
US Army Corp	os of Engineers							Midwest Region Version		



APPENDIX C

HABITAT AND OTHER IDENTIFIED FEATURES PHOTOGRAPHS



Habitat and Other Features

Client Name:

Site Location:

Project No.

AEP

Innovation 138kV Station Project

60660544

Wetland

Date:

June 3, 2021

Description:

View of Wetland 2

Facing North



Scrub Shrub

Date:

June 3, 2021

Description:

View of scrub-shrub area in eastern portion of the Project survey area.

Facing North





Habitat and Other Features

Client Name:

Site Location:

Project No.

AEP

Innovation 138kV Station Project

60660544

Old Field

Date:

June 3, 2021

Description:

View of old field habitat in central portion of the Project survey area.

Facing South



Upland Drainage Feature

Date:

June 3, 2021

Description:

View of constructed upland drainage feature along southern border of the Project survey area.

Facing East





Habitat and Other Features

Project No. Client Name: Site Location:

60660544 AEP Innovation 138kV Station Project

Upland Drainage Feature

Date:

June 3, 2021 **Description:**

View of constructed upland drainage feature along southern border of the Project survey area.

Facing West





APPENDIX D

AGENCY CORRESPONDENCE



Ohio Department of Natural Resources

MIKE DEWINE, GOVERNOR

MARY MERTZ, DIRECTOR

Fax: (614) 267-4764

Office of Real Estate John Kessler, Chief 2045 Morse Road – Bldg. E-2 Columbus, OH 43229 Phone: (614) 265-6621

October 21, 2021

Jake Lubbers AECOM 525 Vine Street, Suite 1800 Cincinnati, Ohio 45202

Re: 21-0913; AEP Innovation Station Project

Project: The proposed project involves the construction of the Innovation Substation.

Location: The proposed project is located in Jersey Township, Licking County, Ohio.

The Ohio Department of Natural Resources (ODNR) has completed a review of the above referenced project. These comments were generated by an inter-disciplinary review within the Department. These comments have been prepared under the authority of the Fish and Wildlife Coordination Act (48 Stat. 401, as amended; 16 U.S.C. 661 et seq.), the National Environmental Policy Act, the Coastal Zone Management Act, Ohio Revised Code and other applicable laws and regulations. These comments are also based on ODNR's experience as the state natural resource management agency and do not supersede or replace the regulatory authority of any local, state or federal agency nor relieve the applicant of the obligation to comply with any local, state or federal laws or regulations.

Natural Heritage Database: The Natural Heritage Database has no records at or within a one-mile radius of the project area.

A review of the Ohio Natural Heritage Database indicates there are no other records of state endangered or threatened plants or animals within the project area. There are also no records of state potentially threatened plants, special interest or species of concern animals, or any federally listed species. In addition, we are unaware of any unique ecological sites, geologic features, animal assemblages, scenic rivers, state wildlife areas, state nature preserves, state or national parks, state or national wildlife refuges, or other protected natural areas within the project area. The review was performed on the project area you specified in your request as well as an additional one-mile radius. Records searched date from 1980.

Please note that Ohio has not been completely surveyed and we rely on receiving information from many sources. Therefore, a lack of records for any particular area is not a statement that rare species or unique features are absent from that area. Although all types of plant communities have been surveyed, we only maintain records on the highest quality areas.

Fish and Wildlife: The Division of Wildlife (DOW) has the following comments.

The DOW recommends that impacts to streams, wetlands and other water resources be avoided and minimized to the fullest extent possible, and that Best Management Practices be utilized to minimize erosion and sedimentation.

The project is within the vicinity of records for the northern long-eared bat (*Myotis septentrionalis*), a state endangered and federally threatened species. Because presence of state endangered bat species has been established in the area, summer tree cutting is not recommended, and additional summer surveys would not constitute presence/absence in the area. However, limited summer tree cutting inside this buffer may be acceptable after further consultation with DOW (contact Erin Hazelton at Erin.hazelton@dnr.ohio.gov).

In addition, the entire state of Ohio is within the range of the Indiana bat (*Myotis sodalis*), a state endangered and federally endangered species, the northern long-eared bat (*Myotis septentrionalis*), a state endangered and federally threatened species, the little brown bat (*Myotis lucifugus*), a state endangered species, and the tricolored bat (*Perimyotis subflavus*), a state endangered species. During the spring and summer (April 1 through September 30), these bat species predominately roost in trees behind loose, exfoliating bark, in crevices and cavities, or in the leaves. However, these species are also dependent on the forest structure surrounding roost trees. The DOW recommends tree cutting only occur from October 1 through March 31, conserving trees with loose, shaggy bark and/or crevices, holes, or cavities, as well as trees with DBH ≥ 20 if possible.

The DOW also recommends that a desktop habitat assessment is conducted, followed by a field assessment if needed, to determine if a potential hibernaculum is present within the project area. Direction on how to conduct habitat assessments can be found in the current USFWS "Rangewide Indiana Bat Survey Guidelines." If a habitat assessment finds that a potential hibernaculum is present within 0.25 miles of the project area, please send this information to Erin Hazelton for project recommendations. If a potential or known hibernaculum is found, the DOW recommends a 0.25-mile tree cutting and subsurface disturbance buffer around the hibernaculum entrance, however, limited summer or winter tree cutting may be acceptable after consultation with the DOW. If no tree cutting or subsurface impacts to a hibernaculum are proposed, this project is not likely to impact these species.

The project is within the range of the fawnsfoot (*Truncilla donaciformis*), a state threatened mussel. Due to the location, and that there is no in-water work proposed in a perennial stream of sufficient size, this project is not likely to impact this species.

The project is within the range the lake chubsucker (*Erimyzon sucetta*) a state threatened fish. The DOW recommends no in-water work in perennial streams from March 15 through June 30 to reduce impacts to indigenous aquatic species and their habitat. If no in-water work is proposed in a perennial stream, this project is not likely to impact this or other aquatic species.

The project is within the range of the least bittern (*Ixobrychus exilis*), a state threatened bird. This secretive marsh species prefers dense emergent wetlands with dense, tall growths of aquatic or semiaquatic vegetation (particularly cattail, sedge, rushes, arrowheads, or sawgrass) interspersed with clumps of woody vegetation and open water. Nests are made from dried vegetation suspended .5 to 2.5 feet above the water. If this type of habitat will be impacted, construction should be avoided in this habitat during the species' nesting period of May 1 through July 31. If this type of habitat will not be impacted, this project is not likely to impact this species.

The project is within the range of the northern harrier (*Circus hudsonis*), a state endangered bird. This is a common migrant and winter species. Nesters are much rarer, although they occasionally breed in large marshes and grasslands. Harriers often nest in loose colonies. The female builds a nest out of sticks on the ground, often on top of a mound. Harriers hunt over grasslands. If this type of habitat will be impacted, construction should be avoided in this habitat during the species' nesting period of April 15 through July 31. If this habitat will not be impacted, this project is not likely to impact this species.

The project is within the range of the upland sandpiper (*Bartramia longicauda*), a state endangered bird. Nesting upland sandpipers utilize dry grasslands including native grasslands, seeded grasslands, grazed and ungrazed pasture, hayfields, and grasslands established through the Conservation Reserve Program (CRP). If this type of habitat will be impacted, construction should be avoided in this habitat during the species' nesting period of April 15 through July 31. If this type of habitat will not be impacted, this project is not likely to impact this species.

Due to the potential of impacts to federally listed species, as well as to state listed species, we recommend that this project be coordinated with the US Fish & Wildlife Service.

Water Resources: The Division of Water Resources has the following comment.

The local floodplain administrator should be contacted concerning the possible need for any floodplain permits or approvals for this project. Your local floodplain administrator contact information can be found at the website below.

http://water.ohiodnr.gov/portals/soilwater/pdf/floodplain/Floodplain%20Manager%20Community%20Contact%20List 8 16.pdf

ODNR appreciates the opportunity to provide these comments. Please contact Mike Pettegrew at mike.pettegrew@dnr.ohio.gov if you have questions about these comments or need additional information.

Mike Pettegrew Environmental Services Administrator (Acting)

Brewster, Heather

From: Ohio, FW3 <ohio@fws.gov>

Sent: Thursday, October 07, 2021 3:27 PM

To: Lubbers, Jake

Cc: nathan.reardon@dnr.state.oh.us; Parsons, Kate; ajtoohey@aep.com; Brewster, Heather

Subject: [EXTERNAL] AEP Innovation Station Project in Licking County, Ohio



UNITED STATES DEPARTMENT OF THE INTERIOR
U.S. Fish and Wildlife Service
Ecological Services Office
4625 Morse Road, Suite 104
Columbus, Ohio 43230
(614) 416-8993 / Fax (614) 416-8994



TAILS# 03E15000-2019-TA-1865

Dear Mr. Lubbers,

The U.S Fish and Wildlife Service (Service) has received your recent correspondence requesting information about the subject proposal. We offer the following comments and recommendations to assist you in minimizing and avoiding adverse impacts to threatened and endangered species pursuant to the Endangered Species Act of 1973 (16 U.S.C. 1531 et seq), as amended (ESA).

Federally Threatened and Endangered Species: The endangered Indiana bat (*Myotis sodalis*) and threatened northern long-eared bat (*Myotis septentrionalis*) occur throughout the State of Ohio. The Indiana bat and northern long-eared bat may be found wherever suitable habitat occurs unless a presence/absence survey has been performed to document absence. Suitable summer habitat for Indiana bats and northern long-eared bats consists of a wide variety of forested/wooded habitats where they roost, forage, and breed that may also include adjacent and interspersed nonforested habitats such as emergent wetlands and adjacent edges of agricultural fields, woodlots, fallow fields, and pastures. Roost trees for both species include live and standing dead trees ≥3 inches diameter at breast height (dbh) that have any exfoliating bark, cracks, crevices, hollows and/or cavities. These roost trees may be located in forested habitats as well as linear features such as fencerows, riparian forests, and other wooded corridors. Individual trees may be considered suitable habitat when they exhibit the characteristics of a potential roost tree and are located within 1,000 feet of other forested/wooded habitat. Northern long-eared bats have also been observed roosting in human-made structures, such as buildings, barns, bridges, and bat houses; therefore, these structures should also be considered potential summer habitat. In the winter, Indiana bats and northern long-eared bats hibernate in caves, rock crevices and abandoned mines.

Seasonal Tree Clearing for Federally Listed Bat Species: Should the proposed project site contain trees ≥3 inches dbh, we recommend avoiding tree removal wherever possible. If any caves or abandoned mines may be disturbed, further coordination with this office is requested to determine if fall

or spring portal surveys are warranted. If no caves or abandoned mines are present and trees ≥3 inches dbh cannot be avoided, we recommend removal of any trees ≥3 inches dbh only occur between October 1 and March 31. Seasonal clearing is recommended to avoid adverse effects to Indiana bats and northern long-eared bats. While incidental take of northern long-eared bats from most tree clearing is exempted by a 4(d) rule (see http://www.fws.gov/midwest/endangered/mammals/nleb/index.html), incidental take of Indiana bats is still prohibited without a project-specific exemption. Thus, seasonal clearing is recommended where Indiana bats are assumed present.

If implementation of this seasonal tree cutting recommendation is not possible, a summer presence/absence survey may be conducted for Indiana bats. If Indiana bats are not detected during the survey, then tree clearing may occur at any time of the year. Surveys must be conducted by an approved surveyor and be designed and conducted in coordination with the Ohio Field Office. Surveyors must have a valid federal permit. Please note that in Ohio summer mist net surveys may only be conducted between June 1 and August 15.

Section 7 Coordination: If there is a federal nexus for the project (e.g., federal funding provided, federal permits required to construct), then no tree clearing should occur on any portion of the project area until consultation under section 7 of the ESA, between the Service and the federal action agency, is completed. We recommend the federal action agency submit a determination of effects to this office, relative to the Indiana bat and northern long-eared bat, for our review and concurrence. This letter provides technical assistance only and does not serve as a completed section 7 consultation document.

Stream and Wetland Avoidance: Over 90% of the wetlands in Ohio have been drained, filled, or modified by human activities, thus is it important to conserve the functions and values of the remaining wetlands in Ohio (https://epa.ohio.gov/portals/47/facts/ohio wetlands.pdf). We recommend avoiding and minimizing project impacts to all wetland habitats (e.g., forests, streams, vernal pools) to the maximum extent possible in order to benefit water quality and fish and wildlife habitat. Additionally, natural buffers around streams and wetlands should be preserved to enhance beneficial functions. If streams or wetlands will be impacted, the U.S. Army Corps of Engineers should be contacted to determine whether a Clean Water Act section 404 permit is required. Best management practices should be used to minimize erosion, especially on slopes. Disturbed areas should be mulched and revegetated with native plant species. In addition, prevention of non-native, invasive plant establishment is critical in maintaining high quality habitats.

Due to the project type, size, and location, we do not anticipate adverse effects to any other federally endangered, threatened, or proposed species, or proposed or designated critical habitat. Should the project design change, or additional information on listed or proposed species or their critical habitat become available, or if new information reveals effects of the action that were not previously considered, coordination with the Service should be initiated to assess any potential impacts.

Thank you for your efforts to conserve listed species and sensitive habitats in Ohio. We recommend coordinating with the Ohio Department of Natural Resources due to the potential for the proposed project to affect state listed species and/or state lands. Contact Mike Pettegrew, Acting Environmental Services Administrator, at (614) 265-6387 or at mike.pettegrew@dnr.state.oh.us.

If you have questions, or if we can be of further assistance in this matter, please contact our office at (614) 416-8993 or ohio@fws.gov.

Sincerely,



Patrice M. Ashfield Field Office Supervisor

cc: Nathan Reardon, ODNR-DOW Kate Parsons, ODNR-DOW